

Jan 1, 2017

July 1, 2017

Jan 1, 2018

July 1, 2018

Jan 1, 2019

January 1, 2017	July 1, 2017	January 1, 2018	July 1, 2018	January 1, 2019
Estimated Date Rule Effective	New USTs must be double-walled/interstitial monitoring	<i>Existing</i> Airport, Field Constructed Tanks must comply with all regs but release detection	1 st Spill Bucket Test required	Vapor Monitoring sunsets as a release detection method (without chemical marker)
Spill, Overfill, and Containment Sump Test required at install	Replaced piping must be double-walled/interstitial monitoring		1 st Overfill Prevention Equipment Test required	Groundwater Monitoring sunsets as a release detection method
<i>New</i> Airport, Field Constructed Tanks must comply with all regs	Dispenser replacement requires sump install		1 st Walkthrough inspection due	<i>Existing</i> Airport, Field Constructed Tanks must comply with release detection regs
<i>Existing</i> Airport, Field Constructed Tanks must register	New linings must be UL1856 listed		1 st operability test of release detection equipment due	

Proposed Underground Storage Tank Compliance Dates