STATE OF MISSOURI

DEPARTMENT OF NATURAL RESOURCES

MISSOURI CLEAN WATER COMMISSION

GENERAL PERMIT for SEWER EXTENSION CONSTRUCTION

The Missouri Department of Natural Resources hereby issues a permit to:

Construction Permit ID:	MOGC00034
Title of Project:	Amberleigh Woods Phase 3
Owner:	Ryan G'Sell Investments LLC
Address:	P.O. Box 857 Imperial, MO 63052

The project will also include general site work appropriate to the scope and purpose of the project and will include all the necessary appurtenances to make a complete and usable collection system. The construction of this project will be in the vicinity of the county below and discharge to Receiving Permit ID below:

County: Jefferson Receiving Permit ID: MO0106461

for the construction of (described construction project):

Construction of approximately 5,240 lf of 8-inch PVC SDR-35 gravity sewer lines with 41 manholes to serve a 407 PE and a design average flow of 40,700 gpd.

Project is in the vicinity of Amber Meadows Dr. and Lions Den Rd., Jefferson County and discharges to an existing system to be treated at Kimmswick Wastewater Treatment Facility, MO-0106461. Don Daniel, System Administrator, with Rock Creek Public Sewer District provided an acceptance letter dated July 2, 2015.

Construction of such proposed facilities shall be in accordance with the provisions of the Missouri Clean Water Law, Chapter 644, RSMo, and regulation promulgated thereunder, or this permit may be revoked by the Department of Natural Resources (Department). As the Department does not examine structural features of design or the efficiency of mechanical equipment, the issuance of this permit does not include approval of these features.
This permit applies only to the construction of water pollution control components; it does not apply to other environmentally regulated areas.

August 28, 2015
Issue Date

Sara Parker Pauley, Director
Department of Natural Resources

August 27, 2017
Expiration Date

John Madras
Director, Water Protection Program

APPLICABILITY

1. This permit authorizes the construction of gravity sewer extensions, force mains, and lift stations. Storage basins, considered part of the collection system, are also included. Earthen basins are not included under this General Sewer Extension Construction permit.

2. A Sewer Extension Construction Permit may be required by the department due to compliance and enforcement actions.

3. This permit does not apply to:
   A. Earthen storage basins;
   B. Projects located within an Approved Sewer Program. These include the City of Blue Springs, City of Columbia, City of Kansas City, City of Jefferson City, City of Joplin, City of Lebanon, City of Springfield, City of St. Peters, Duckett Creek Sewer District, and Metropolitan St. Louis Sewer District;
   C. Projects funded by the Department of Natural Resources;
   D. Projects that substantially deviate from the Design Guides in 10 CSR 20-8; and
   E. Exempt projects unless requested by the applicant or required by enforcement.

PREREQUISITES:

1. The General Sewer Extension Construction Permit application, appropriate fee, and a schedule for construction with the date on which construction will begin and anticipated completion date.

2. The engineering report, as required, plans and specifications each signed and sealed by a professional engineer registered in the State of Missouri. A Summary of Design is an acceptable substitute for the engineering report required by this permit prerequisite.

3. The Design Certification form signed and sealed by a professional engineer registered in the State of Missouri certifying the design of the system was done in accordance with 10 CSR 20-6 and 10 CSR 20-8.

4. A statement from the continuing authority was received accepting the wastewater for treatment.

5. A statement from the continuing authority was received accepting the responsibility for operation, maintenance, and modernization of these facilities

PERMIT CONDITIONS:

1. Contact the department's appropriate regional office 48 hours prior to starting construction. Contact information can be found at http://dnr.mo.gov/regions/regions.htm.

2. This permit authorizes the activities and scope of work detailed in the plans and specifications submitted with the request.

3. The construction must be in accordance with the design certification stating the plans and specifications comply with 10 CSR 20-6 and 10 CSR 20-8.

PERMIT CONDITIONS: (continued)

4. State and Federal Law does not permit bypassing of raw wastewater, therefore steps must be taken to ensure that raw wastewater does not discharge during construction. If a sanitary sewer overflow or bypass occurs, report the appropriate information to the department's regional office per 10 CSR 20-7.015(9)(E)2.

5. Protection of drinking water supplies shall be in accordance with 10 CSR 20-8.120(10). "There shall be no physical connections between a public or private potable water supply system and a sewer, or appurtenance thereto which would permit the passage of any wastewater or polluted water into the potable supply. No water pipe shall pass through or come in contact with any part of a sewer manhole."

   A. Sewers in relation to water works structures shall meet the requirements of 10 CSR 23-3.010 with respect to minimum distances from public water supply wells or other water supply sources and structures.

   B. Sewer mains shall be laid at least ten feet (10') horizontally from any existing or proposed water main. The distances shall be measured edge-to-edge. In cases where it is not practical to maintain a ten foot (10') separation, the department may allow a deviation on a case-by-case basis, if supported by data from the design engineer. Such a deviation may allow installation of the sewer closer to a water main, provided that the water main is in a separate trench or on an undisturbed earth shelf located on either side of the sewer and at an elevation so the bottom of the water main is at least 18 inches above the top of the sewer. If it is impossible to obtain proper horizontal and vertical separation as described above for sewers, the sewer must be constructed of slip-on or mechanical joint pipe or continuously encased and be pressure tested to 150 pounds per square inch to assure water tightness.

   C. Manholes shall be located with the top access at or above grade level.

   D. Manholes should be located at least ten feet (10') horizontally from any existing or proposed water main.

   E. Sewers crossing water mains shall be laid to provide a minimum vertical distance of 18 inches between the outside of the water main and the outside of the sewer. This shall be the case where the water main is either above or below the sewer. The crossing shall be arranged so that the sewer joints will be equidistant and as far as possible from the water main joints. Where a water main crosses under a sewer, adequate structural support shall be provided for the sewer to maintain line and grade. When it is impossible to obtain proper vertical separation as stipulated above, one of the following methods must be specified:

      1) The sewer shall be designed and constructed equal to the water pipe and shall be pressure tested to assure water tightness prior to backfilling; or
      2) Either the water main or sewer line may be continuously encased or enclosed in a watertight carrier pipe which extends ten feet (10') on both sides of the crossing, measured perpendicular to the water main. The carrier pipe shall be of materials approved by the department for use in water main construction.

PERMIT CONDITIONS: (continued)

6. In addition to the requirements for a construction permit, 10 CSR 20-6.200 requires land disturbance activities of one acre or more to obtain a Missouri State Operating Permit to discharge stormwater. The permit requires Best Management Practices sufficient to control runoff and sedimentation to protect waters of the state. Land disturbance permits will only be obtained by means of the department's ePermitting system available online at www.dnr.mo.gov/env/wpp/epermit/help.htm.

   See www.dnr.mo.gov/env/wpp/stormwater/sw-land-disturb-permits.htm for more information.

7. A United States (U.S.) Army Corps of Engineers (COE) permit (404) and a Water Quality Certification (401) issued by the department or permit waiver may be required for the activities described in this permit. This permit is not valid until these requirements are satisfied. If construction activity will disturb any land below the ordinary high water mark of Jurisdictional Waters of the U.S. then a 404/401 will be required. Since the COE makes determinations on what is jurisdictional, you must contact the COE to determine permitting requirements. You may call the department's Water Protection Program at (573) 751-1300 for more information.

   See www.dnr.mo.gov/env/wpp/401/ for more information.

8. If this project eliminates a wastewater treatment facility, then a full closure plan shall be submitted to the department's appropriate regional office for review and approval of any permitted wastewater treatment system being replaced. In accordance with 10 CSR 20-6.010(12), the closure plan must meet the requirements outlined in Standard Conditions Part III, Section I, of the Missouri State Operating Permit. Closure shall not commence until the submitted closure plan is approved by the department. Form J – Request for Termination of a State Operating Permit, shall be submitted to the department's appropriate Regional Office for termination of any existing Missouri State Operating Permit, once closure is completed in accordance with the approved closure plan.

9. Submit a Statement of Work Completed Form to the department following completion of construction. Submit an electronic copy of the as built plans if the project was not constructed in accordance with previously submitted plans and specifications.

MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM

APPLICATION FOR CONSTRUCTION PERMIT – SEWER EXTENSION

FOR DEPARTMENT USE ONLY	
APP NO.	CP NO.
FEE RECEIVED $300.00	CHECK NO. 2005
DATE RECEIVED 7/14/15 SB	

NOTE ▶ PLEASE READ THE ACCOMPANYING INSTRUCTIONS BEFORE COMPLETING THIS FORM

1.0 APPLICATION INFORMATION (Note – If any of the questions in this section are answered NO, this application may be considered incomplete and returned.)

1.1 Is this a Federal/State funded project? ☐ YES ☑ N/A Funding Agency: Project #:

1.2 Has the Department of Natural Resources approved the proposed project's engineering report*?
☐ YES Date of Approval: ☐ NO ☑ N/A

1.3 Is a copy of the appropriate plans* and specifications* included with this application? ☑ YES ☐ NO

1.4 Is a summary of design* included with this application? ☑ YES ☐ NO

1.5 Is the appropriate fee included with this application? (See instructions for appropriate fee.) ☑ YES ☐ NO

* Must be affixed with a Missouri registered professional engineer's seal, signature and date.

2.0 PROJECT INFORMATION

2.1 NAME OF PROJECT
Amberleigh Woods Phase 3

ADDRESS	CITY	STATE	ZIP CODE	COUNTY
Amber Meadows Dr. @ Lions Den Road	Jefferson County	MO	63052	Jefferson

2.2 Legal Description: ¼, ¼, ¼, Sec. 3 , T 42N , R 5E

2.3 Project Components (check all that apply):
☑ Gravity sewers ☐ Pumping stations ☐ Force mains ☐ Alternative sewer system ☐ Other (Describe below.)

2.4 PROJECT DESCRIPTION
4,082 ft. of 8-inch PVC gravity sewer pipe

RECEIVED
JUL 13 2015
Water Protection Program

2.5 DESIGN INFORMATION
A. Population or number of lots to be served by this extension: 110 residences
B. Estimated flow to be contributed by this extension: Design Average Flow: gpd Design Peak Hourly Flow: 5653 gph
C. Industrial Wastes: Type: Flow: gpd
D. Receiving Sewer: Size: 8 inches Capacity: gpm

3.0 PROJECT OWNER

NAME	TELEPHONE NUMBER WITH AREA CODE	E-MAIL ADDRESS
Ryan G'Sell Investments, LLC	(636) 282-9122	ryan@ryangsellhomes.com

ADDRESS	CITY	STATE	ZIP CODE
1516 Professional Drive	Imperial	MO	63052

4.0 CONTINUING AUTHORITY: Permanent organization that will serve as the continuing authority for the operation, maintenance and modernization of the wastewater collection system.

NAME	TELEPHONE NUMBER WITH AREA CODE	E-MAIL ADDRESS
Rock Creek Public Sewer District	(636) 464-3305	dondaniel@rockcreekpsd.com

ADDRESS	CITY	STATE	ZIP CODE
P.O. Box 1060	Imperial	MO	63052

4.1 A letter from the continuing authority, if different than the owner, is included with this application. ☑ YES ☐ NO ☐ N/A

5.0 ENGINEER

ENGINEER NAME / COMPANY NAME	TELEPHONE NUMBER WITH AREA CODE	E-MAIL ADDRESS
The Sterling Company	(314) 487-0440	sackley@sterling-eng-sur.com

ADDRESS	CITY	STATE	ZIP CODE
5055 New Baumgartner Road	St. Louis	MO	63129

6.0 RECEIVING WASTEWATER TREATMENT FACILITY		
NAME Kimmswick Wastewater Treatment Facility	TELEPHONE NUMBER WITH AREA CODE (636) 461-2578	E-MAIL ADDRESS dondaniel@rockcreekpsd.com
MISSOURI STATE OPERATING PERMIT # 0106461	REMAINING CAPACITY (GPD) 2,007,582	
6.1 Has the receiving treatment facility agreed to accept the additional wastewater flow? ☑ YES ☐ NO		
6.2 A letter from the receiving wastewater treatment facility, if different than the continuing authority, is included with this application. ☑ YES ☐ NO ☐ N/A		
7.0 PROJECT OWNER: I hearby certify that I am familiar with the information contained in this application and to the best of my knowledge and belief such information is true, complete, and accurate, and if granted this permit, I agree to abide by the Missouri Clean Water Law and all rules, regulations, orders, and decisions, subject to any legitimate appeal available to applicant under Missouri Clean Water Law.		
PROJECT OWNER SIGNATURE		
PRINTED NAME Ryan G'Sell		DATE 7-6-15
TITLE OR COPORATE POSITION President	TELEPHONE NUMBER WITH AREA CODE (636) 282-9122	E-MAIL ADDRESS gsellcontracting@gmail.com
Mail completed copy to:	MISSOURI DEPARTMENT OF NATURAL RESOURCES WATER PROTECTION PROGRAM P.O. BOX 176 JEFFERSON CITY, MO 65102-0176	

Rock Creek Public Sewer District

BOARD OF TRUSTEES
ALFRED BARBAGALLO
WESLEY GRIFFITH
JAMES NAES
ERIC KNOLL
TIM HOLLERBACH

JEFFERSON COUNTY, MISSOURI
P.O. Box 1060 • Imperial, MO 63052
4133 W. Outer Rd. • Arnold, MO 63010

Phone: 636-464-3305
Fax: 636-464-2196

DONALD DANIEL
District Administrator

July 2, 2015

Missouri Department of Natural Resources
Water Protection Program
P.O. Box 176
Jefferson City, Missouri 65102

Re: Approval of Amberleigh Woods Phase 3

Dear Sir:

Enclosed you will please find a sealed set of construction plans for Amberleigh Woods Phase 3 Sewer Extension, the application for a construction permit, and a check in the amount of $300.00 for the filing fee.

Project Description:

The Sterling Company has completed plans to extend sanitary sewers for the Amberleigh Woods Phase 3 Sewer Extension. This project involves the construction of 4,082 feet of 8" diameter PVC pipe, and 40 manholes.

Compliance and Approval:

The construction plans meet district standards and have been reviewed and approved by the Board of Trustees.

Acceptance as Continuing Authority:

After the sewers and manholes have been completed and have passed the required testing, the district will act as the continuing authority for the acceptance and treatment of sanitary sewage from this pump station and the maintenance of the public sewer mains and manholes.

Wastewater Treatment Plant Capacity:

RECEIVED
JUL 13 2015
Water Protection Program

This project will add 40,700 gallons per day to the Kimmswick Wastewater Treatment Plant (Mo-0106461). The remaining capacity will be 2,007,582 gallons per day at the Kimmswick Treatment Plant.

If you have any questions, please feel free to contact my office.

Sincerely,

Don Daniel

Don Daniel
District Administrator