

STATE OF MISSOURI

DEPARTMENT OF NATURAL RESOURCES

MISSOURI CLEAN WATER COMMISSION



MISSOURI STATE OPERATING PERMIT

In compliance with the Missouri Clean Water Law, (Chapter 644 R.S. Mo. as amended, hereinafter, the Law), and the Federal Water Pollution Control Act (Public Law 92-500, 92<sup>nd</sup> Congress) as amended,

Permit No. MO-0086126

Owner: Metropolitan Saint Louis Sewer District  
Address: 2350 Market Street, St. Louis, MO 63103

Continuing Authority: Same as above  
Address: Same as above

Facility Name: MSD Fenton Wastewater Treatment Plant  
Facility Address: 75 Opps Lane, Fenton, MO 63026

Legal Description: Landgrant 03012, St. Louis County  
UTM Coordinates: X=724245, Y=4265582

Receiving Stream: Meramec River (P)  
First Classified Stream and ID: Meramec River (P) (2183) 303(d) List  
USGS Basin & Sub-watershed No.: (07140102-1003)

is authorized to discharge from the facility described herein, in accordance with the effluent limitations and monitoring requirements as set forth herein:

**FACILITY DESCRIPTION**

Outfall #001 – POTW – SIC #4952

The use or operation of this facility shall be by or under the supervision of a Certified “A” Operator.

Influent lift station / primary clarifier / activated sludge / 2 final clarifiers / 3 - ultraviolet disinfection units / gravity sludge thickener / sludge belt press / sludge holding tank / sludge is hauled to other MSD facilities, landfilled, or land applied.

Design population equivalent is 67,500.

Design flow is 6.75 million gallons per day.

Actual flow is 4.8 million gallons per day.

Design sludge production is 2,570 dry tons/year.

Outfall #S1 - Eliminated

Outfall #S2 - Eliminated

This permit authorizes only wastewater discharges under the Missouri Clean Water Law and the National Pollutant Discharge Elimination System; it does not apply to other regulated areas. This permit may be appealed in accordance with Section 621.250 RSMo, Section 640.013 RSMo and Section 644.051.6 of the Law.

January 1, 2015

Effective Date

  
Sara Parker Pauley, Director, Department of Natural Resources

December 31, 2017

Expiration Date

  
John Madras, Director, Water Protection Program

OUTFALL #001	TABLE A-1. FINAL EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS				PAGE NUMBER 2 of 9	
					PERMIT NUMBER MO-0086126	
The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The final effluent limitations shall become effective on <b>January 1, 2015</b> , and remain in effect until expiration of the permit. Such discharges shall be controlled, limited and monitored by the permittee as specified below:						
EFFLUENT PARAMETER(S)	UNITS	FINAL EFFLUENT LIMITATIONS			MONITORING REQUIREMENTS	
		DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Flow	MGD	*		*	once/day	24 hr. total
Carbonaceous Biochemical Oxygen Demand <sub>5</sub>	mg/L		40	25	two/week	composite**
Total Suspended Solids	mg/L		45	30	two/week	composite**
<i>E. coli</i> (Note 1)	#/100 ml		630	126	two/week	grab
pH – Units	SU	***		***	two/week	grab
Ammonia as N	mg/L	*		*	two/week	grab
Oil & Grease	mg/L	15		10	once/month	grab
MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u> ; THE FIRST REPORT IS DUE <u>FEBRUARY 28, 2015</u> . THERE SHALL BE NO DISCHARGE OF FLOATING SOLIDS OR VISIBLE FOAM IN OTHER THAN TRACE AMOUNTS.						
Cadmium, Total Recoverable	µg/L	7.2		2.4	once/quarter****	grab
Zinc, Total Recoverable	µg/L	345.7		132.3	once/quarter****	grab
Copper, Total Recoverable	µg/L	*		*	once/quarter****	grab
Lead, Total Recoverable	µg/L	*		*	once/quarter****	grab
Total Phosphorus	mg/L	*		*	once/quarter****	grab
Total Nitrogen	mg/L	*		*	once/quarter****	grab
MONITORING REPORTS SHALL BE SUBMITTED <u>QUARTERLY</u> ; THE FIRST REPORT IS DUE <u>APRIL 28, 2015</u> .						
Total Toxic Organics (Note 2)	µg/L	*			once/year	composite**
MONITORING REPORTS SHALL BE SUBMITTED <u>ANNUALLY</u> ; THE FIRST REPORT IS DUE <u>JANUARY 28, 2016</u> .						

\* Monitoring requirement only.

\*\* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

\*\*\* pH is measured in pH units and is not to be averaged. The pH is limited to the range of 6.0-9.0 pH units.

\*\*\*\* See table below for quarterly sampling.

Minimum Sampling Requirements			
Quarter	Months	Effluent Parameters	Report is Due
First	January, February, March	Sample at least once during any month of the quarter	April 28 <sup>th</sup>
Second	April, May, June	Sample at least once during any month of the quarter	July 28 <sup>th</sup>
Third	July, August, September	Sample at least once during any month of the quarter	October 28 <sup>th</sup>
Fourth	October, November, December	Sample at least once during any month of the quarter	January 28 <sup>th</sup>

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a geometric mean. The Weekly Average for *E. coli* will be expressed as a geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

Note 2 – See Special Condition #23

OUTFALL #001	TABLE A-3. WHOLE EFFLUENT TOXICITY FINAL EFFLUENT LIMITATIONS AND MONITORING			PAGE NUMBER 3 of 9		
				PERMIT NUMBER MO-00861216		
The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The final effluent limitations shall become effective on <b>January 28, 2015</b> , and remain in effect until expiration of the permit. Such discharges shall be controlled, limited and monitored by the permittee as specified below:						
EFFLUENT PARAMETER(S)	UNITS	FINAL EFFLUENT LIMITATIONS			MONITORING REQUIREMENTS	
		DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Acute Whole Effluent Toxicity (Note 3)	TU <sub>a</sub>	*			once/year	composite**
MONITORING REPORTS SHALL BE SUBMITTED <u>ANNUALLY</u> ; THE FIRST REPORT IS DUE <u>OCTOBER 28, 2015</u> .						
Chronic Whole Effluent Toxicity (Note 4)	TU <sub>c</sub>	*			once/permit cycle	composite**
MONITORING REPORTS SHALL BE SUBMITTED <u>ONCE/PERMIT CYCLE</u> ; THE FIRST REPORT IS DUE <u>OCTOBER 28, 2016</u> .						

\* Monitoring requirement only.

Note 3 – The Acute WET test shall be conducted once per year during calendar year 2015 and 2017. See Special Condition #21 for additional requirements.

Note 4 –The Chronic WET test shall be conducted during calendar year 2016. See Special Condition #22 for additional requirements.

TABLE B. INFLUENT MONITORING REQUIREMENTS			
The facility is required to meet a removal efficiency of 85% or more as a monthly average. The monitoring requirements shall become effective on <b>Effective Date</b> and remain in effect until expiration of the permit. To determine removal efficiencies, the influent wastewater shall be monitored by the permittee as specified below:			
SAMPLING LOCATION AND PARAMETER(S)	UNITS	MONITORING REQUIREMENTS	
		MEASUREMENT FREQUENCY	SAMPLE TYPE
Carbonaceous Biochemical Oxygen Demand <sub>5</sub>	mg/L	once/month	composite**
Total Suspended Solids	mg/L	once/month	composite**
MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u> ; THE FIRST REPORT IS DUE <u>FEBRUARY 28, 2015</u> .			

\*\* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

### C. STANDARD CONDITIONS

In addition to specified conditions stated herein, this permit is subject to the attached Parts I, II, & III standard conditions dated August 1, 2014, May 1, 2013, and March 1, 2014 and hereby incorporated as though fully set forth herein.

D. SPECIAL CONDITIONS

1. This permit establishes final ammonia limitations based on Missouri's current Water Quality Standard. On August 22, 2013, the U.S. Environmental Protection Agency (EPA) published a notice in the Federal Register announcing of the final national recommended ambient water quality criteria for protection of aquatic life from the effects of ammonia in freshwater. The EPA's guidance, Final Aquatic Life Ambient Water Quality Criteria for Ammonia – Fresh Water 2013, is not a rule, nor automatically part of a state's water quality standards. States must adopt new ammonia criteria consistent with EPA's published ammonia criteria into their water quality standards that protect the designated uses of the water bodies. The Department of Natural Resources has initiated stakeholder discussions on how to best incorporate these new criteria into the State's rules. A date for when this rule change will occur has not been determined. Also, refer to Section VI of this permit's factsheet for further information including estimated future effluent limits for this facility. It is recommended the permittee view the Department's 2013 EPA criteria Factsheet located at <http://dnr.mo.gov/pubs/pub2481.htm>.
2. This permit may be reopened and modified, or alternatively revoked and reissued, to:
  - (a) Comply with any applicable effluent standard or limitation issued or approved under Sections 301(b)(2)(C) and (D), 304(b)(2), and 307(a) (2) of the Clean Water Act, if the effluent standard or limitation so issued or approved:
    - (1) contains different conditions or is otherwise more stringent than any effluent limitation in the permit; or
    - (2) controls any pollutant not limited in the permit.
  - (b) Incorporate new or modified effluent limitations or other conditions, if the result of a waste load allocation study, toxicity test or other information indicates changes are necessary to assure compliance with Missouri's Water Quality Standards.
  - (c) Incorporate new or modified effluent limitations or other conditions if, as the result of a watershed analysis, a Total Maximum Daily Load (TMDL) limitation is developed for the receiving waters which are currently included in Missouri's list of waters of the state not fully achieving the state's water quality standards, also called the 303(d) list.
  - (d) Incorporate the requirement to develop a pretreatment program pursuant to 40 CFR 403.8(a) when the Director of the Water Protection Program determines that a pretreatment program is necessary due to any new introduction of pollutants into the Publically Owned Treatment Works or any substantial change in the volume or character of pollutants being introduced.

The permit as modified or reissued under this paragraph shall also contain any other requirements of the Clean Water Act then applicable.

3. All outfalls must be clearly marked in the field.
4. Permittee will cease discharge by connection to a facility with an area-wide management plan per 10 CSR 20-6.010(3)(B) within 90 days of notice of its availability.
5. Water Quality Standards
  - (a) To the extent required by law, discharges to waters of the state shall not cause a violation of water quality standards rule under 10 CSR 20-7.031, including both specific and general criteria.
  - (b) General Criteria. The following general water quality criteria shall be applicable to all waters of the state at all times including mixing zones. No water contaminant, by itself or in combination with other substances, shall prevent the waters of the state from meeting the following conditions:
    - (1) Waters shall be free from substances in sufficient amounts to cause the formation of putrescent, unsightly or harmful bottom deposits or prevent full maintenance of beneficial uses;
    - (2) Waters shall be free from oil, scum and floating debris in sufficient amounts to be unsightly or prevent full maintenance of beneficial uses;
    - (3) Waters shall be free from substances in sufficient amounts to cause unsightly color or turbidity, offensive odor or prevent full maintenance of beneficial uses;
    - (4) Waters shall be free from substances or conditions in sufficient amounts to result in toxicity to human, animal or aquatic life;
    - (5) There shall be no significant human health hazard from incidental contact with the water;
    - (6) There shall be no acute toxicity to livestock or wildlife watering;
    - (7) Waters shall be free from physical, chemical or hydrologic changes that would impair the natural biological community;
    - (8) Waters shall be free from used tires, car bodies, appliances, demolition debris, used vehicles or equipment and solid waste as defined in Missouri's Solid Waste Law, section 260.200, RSMo, except as the use of such materials is specifically permitted pursuant to section 260.200-260.247.

D. SPECIAL CONDITIONS (continued)

6. Changes in Discharges of Toxic Substances

The permittee shall notify the Director as soon as it knows or has reason to believe:

- (a) That any activity has occurred or will occur which would result in the discharge of any toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels:"
  - (1) One hundred micrograms per liter (100 µg/L);
  - (2) Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,5 dinitrophenol and for 2-methyl-4, 6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
  - (3) Five (5) times the maximum concentration value reported for the pollutant in the permit application;
  - (4) The level established by the Director in accordance with 40 CFR 122.44(f).
- (b) That they have begun or expect to begin to use or manufacture as an intermediate or final product or byproduct any toxic pollutant, which was not reported in the permit application.

7. Report as no-discharge when a discharge does not occur during the report period.

8. It is a violation of the Missouri Clean Water Law to fail to pay fees associated with this permit (644.055 RSMo).

9. The permittee shall comply with any applicable requirements listed in 10 CSR 20-9, unless the facility has received written notification that the Department has approved a modification to the requirements. The monitoring frequencies contained in this permit shall not be construed by the permittee as a modification of the monitoring frequencies listed in 10 CSR 20-9. If a modification of the monitoring frequencies listed in 10 CSR 20-9 is needed, the permittee shall submit a written request to the Department for review and, if deemed necessary, approval.

10. The permittee has developed and is currently implementing a program for maintenance and repair of the collection system. The permittee's program is consistent with the US EPA's Guide For Evaluating Capacity, Management, Operation, And Maintenance (CMOM) Programs At Sanitary Sewer Collection Systems (Document number EPA 305-B-05-002). The permittee shall continue to submit semi-annual and annual reports as required by the federal consent decree entered in the matter of The United States et al. v. The Metropolitan St. Louis Sewer District, No. 4:07-CV-1120 (E.D. Mo.) which was entered on April 27, 2012.

11. Bypasses are not authorized at this facility unless they meet the criteria in 40 CFR 122.41(m). If a bypass occurs, the permittee shall report in accordance to 40 CFR 122.41(m)(3)(i), and with Standard Condition Part I, Section B, subsection 2.b. Bypasses are to be reported to the St. Louis Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. Blending, which is the practice of combining a partially-treated wastewater process stream with a fully-treated wastewater process stream prior to discharge, is not considered a form of bypass. If the permittee wishes to utilize blending, the permittee shall file an application to modify this permit to facilitate the inclusion of appropriate monitoring conditions.

12. The facility must be sufficiently secured to restrict entry by children, livestock and unauthorized persons as well as to protect the facility from vandalism.

13. A least one gate must be provided to access the wastewater treatment facility and provide for maintenance and mowing. The gate shall remain closed except when temporarily opened by; the permittee to access the facility, perform operational monitoring, sampling, maintenance, mowing, or for inspections by the Department. The gate shall be closed and locked when the facility is not staffed.

14. At least one (1) warning sign shall be placed on each side of the facility enclosure in such positions as to be clearly visible from all directions of approach. There shall also be one (1) sign placed for every five hundred feet (500') (150 m) of the perimeter fence. A sign shall also be placed on each gate. Minimum wording shall be SEWAGE TREATMENT FACILITY—KEEP OUT. Signs shall be made of durable materials with characters at least two inches (2") high and shall be securely fastened to the fence, equipment or other suitable locations.

15. An Operation and Maintenance (O & M) manual shall be maintained by the permittee and made available to the operator. The O & M manual shall include key operating procedures and a brief summary of the operation of the facility.

16. An all-weather access road shall be provided to the treatment facility.

17. The discharge from the wastewater treatment facility shall be conveyed to the receiving stream via a closed pipe or a paved or rip-rapped open channel. Sheet or meandering drainage is not acceptable. The outfall sewer shall be protected against the effects of floodwater, ice or other hazards as to reasonably insure its structural stability and freedom from stoppage. The outfall shall be maintained so that a sample of the effluent can be obtained at a point after the final treatment process and before the discharge mixes with the receiving waters.

D. SPECIAL CONDITIONS (continued)

18. Land application of biosolids shall be conducted in accordance with Standard Conditions III and a Department approved biosolids management plan. Land application of biosolids during frozen, snow covered, or saturated soil conditions in accordance with the additional requirements specified in WQ426 shall occur only with prior notification to the St. Louis Regional Office.
19. The permittee shall implement and enforce its approved pretreatment program in accordance with the requirements of 10 CSR 20-6.100. The approved pretreatment program is hereby incorporated by reference. The permittee shall submit to the Department on or before **September 30<sup>th</sup> of each year** a report briefly describing its pretreatment activities during the previous calendar year. At a minimum, the report shall include the following:
  - (a) An updated list of the Permittee's Industrial Users, including their names and addresses, or a list of deletions and additions keyed to a previously submitted list. The Permittee shall provide a brief explanation of each deletion. This list shall identify which Industrial Users are subject to categorical pretreatment Standards and specify which Standards are applicable to each Industrial User. The list shall indicate which Industrial Users are subject to local standards that are more stringent than the categorical Pretreatment Standards. The Permittee shall also list the Industrial Users that are subject only to local Requirements;
  - (b) A summary of the status of Industrial User compliance over the reporting period;
  - (c) A summary of compliance and enforcement activities (including inspections) conducted by the Permittee during the reporting period; and
  - (d) Any other relevant information requested by the Department.

Pursuant to 40 CFR 122.44(j)(2)(ii), the permittee shall submit to the Department a written technical evaluation of the need to revise local limits under 40 CFR 403.5(c)(1) along with the application for renewal of this permit.

20. Sewer Extension

The Department has approved the construction permit program to regulate and approve construction of sanitary sewers, which are tributary to this wastewater treatment plant. This approval may be modified or revoked by the Department if the sewage collection, transportation, or treatment facilities reach their design limitations, if the facility falls into chronic noncompliance with the permit, or if the permittee fails to follow the terms and conditions of the submitted and approved program.

This permit may be reopened and modified or alternatively revoked and reissued to incorporate new or modified conditions to the sewer construction permit authority, if information indicates changes are necessary to assure compliance with Missouri's Clean Water Law and associated regulations. When any of the above mentioned conditions occur, the permittee will be notified prior to any modifications of this permit condition. Plans and specifications for all projects which include a proposed by-pass must be submitted to the Department to provide record information for location and size of the by-pass.

An annual report on the sewer extension program must be submitted by January 28 of each year to the Missouri Department of Natural Resources' St. Louis Regional Office. The report must list the name of the projects approved and the length of sewers and force mains constructed under the sewer extension program. Detailed project information and data including design flows and inspection records shall be available for review upon request. A summary of total flow at the treatment facility shall be included.

D. SPECIAL CONDITIONS (continued)

21. Acute Whole Effluent Toxicity (WET) tests shall be conducted as follows:

SUMMARY OF ACUTE WET TESTING FOR THIS PERMIT					
OUTFALL	AEC	Acute Toxic Unit (TU <sub>a</sub> )	FREQUENCY	SAMPLE TYPE	MONTH
001	52%	*	once/year (2015 & 2017)	composite**	any

\* Monitoring only

\*\* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

Dilution Series						
100%	52%	25%	12.5%	6.25%	(Control) 100% upstream, if available	(Control) 100% Lab Water, also called synthetic water

a) Freshwater Species and Test Methods

- i. Species and short-term test methods for estimating the acute toxicity of NPDES effluents are found in the fifth edition of *Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms*

(EPA/821/R-02/012, 2002; Table IA, 40 CFR Part 136). The permittee shall concurrently conduct 48-hour static non-renewal toxicity tests with the following vertebrate species:

- The fathead minnow, *Pimephales promelas* (Acute Toxicity Test Method 2000.0).

And the following invertebrate species:

- The daphnid, *Ceriodaphnia dubia* (Acute Toxicity Test Method 2002.0).

- ii. Chemical and physical analysis of an upstream control sample and effluent sample shall occur immediately upon being received by the laboratory, prior to any manipulation of the effluent sample beyond preservation methods consistent with federal guidelines for WET testing that are required to stabilize the sample during shipping. Where upstream receiving water is not available, synthetic laboratory control water may be used.
- iii. Test conditions must meet all test acceptability criteria required by the EPA Method used in the analysis.
- iv. Any and all chemical or physical analysis of the effluent sample performed in conjunction with the WET test shall be performed at the 100% Effluent concentration in addition to analysis performed upon any other effluent concentration.
- v. All chemical analyses shall be performed and results shall be recorded in the appropriate field of the report form. The parameters for chemical analysis include Temperature (°C), pH (SU), Conductivity (µmohs/cm), Dissolved Oxygen (mg/L), Total Residual Chlorine (mg/L), Un-ionized Ammonia (mg/L), Total Alkalinity (mg/L), Total Hardness (mg/L), Cadmium, Total Recoverable (µg/L), Zinc, Total Recoverable (µg/L), Copper, Total Recoverable (µg/L), and Lead, Total Recoverable (µg/L).

b) Reporting of Acute Toxicity Monitoring Results

- i. WET test results shall be submitted to the St. Louis Regional Office, or by eDMR, with the permittee's Discharge Monitoring Reports by **October 28, 2015, and October 28, 2017**. The submittal shall include:
  1. A full laboratory report for all toxicity testing.
  2. Copies of chain-of-custody forms.
  3. The WET form provided by the Department upon permit issuance.
- ii. The report must include a quantification of acute toxic units (TU<sub>a</sub> = 100/LC<sub>50</sub>) reported according to the test methods manual chapter on report preparation and test review. The Lethal Concentration, 50 Percent (LC<sub>50</sub>) is the toxic or effluent concentration that would cause death in 50 percent of the test organisms over a specified period of time.

c) Permit Reopener for Acute Toxicity

In accordance with 40 CFR Parts 122 and 124, this permit may be modified to include effluent limitations or permit conditions to address acute toxicity in the effluent or receiving waterbody, as a result of the discharge; or to implement new, revised, or newly interpreted water quality standards applicable to acute toxicity.

D. SPECIAL CONDITIONS (continued)

22. Chronic Whole Effluent Toxicity (WET) tests shall be conducted as follows:

SUMMARY OF CHRONIC WET TESTING FOR THIS PERMIT					
OUTFALL	AEC	Chronic Toxic Unit (TU <sub>c</sub> )	FREQUENCY	SAMPLE TYPE	MONTH
001	100%	*	once/year (2016)	24 hr. composite	any

\* Monitoring only

\*\* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

Dilution Series						
100%	50%	25%	10%	6.25%	(Control) 100% upstream, if available	(Control) 100% Lab Water, also called synthetic water

d) Freshwater Species and Test Methods

i. Species and short-term test methods for estimating the chronic toxicity of NPDES effluents are found in the fourth edition of *Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Freshwater Organisms* (EPA/821/R-02/013, 2002; Table IA, 40 CFR Part 136). The permittee shall concurrently conduct 7-day, static, renewal toxicity tests with the following vertebrate species:

- The fathead minnow, *Pimephales promelas* (Survival and Growth Test Method 1000.0).

And the following invertebrate species:

- The daphnid, *Ceriodaphnia dubia* (Survival and Reproduction Test Method 1002.0).

ii. Chemical and physical analysis of an upstream control sample and effluent sample shall occur immediately upon being received by the laboratory, prior to any manipulation of the effluent sample beyond preservation methods consistent with federal guidelines for WET testing that are required to stabilize the sample during shipping. Where upstream receiving water is not available, synthetic laboratory control water may be used.

iii. Test conditions must meet all test acceptability criteria required by the EPA Method used in the analysis.

iv. Any and all chemical or physical analysis of the effluent sample performed in conjunction with the WET test shall be performed at the 100% Effluent concentration in addition to analysis performed upon any other effluent concentration.

v. All chemical analyses shall be performed and results shall be recorded in the appropriate field of the report form. The parameters for chemical analysis include Temperature (°C), pH (SU), Conductivity (µmohs/cm), Dissolved Oxygen (mg/L), Total Residual Chlorine (mg/L), Un-ionized Ammonia (mg/L), Total Alkalinity (mg/L), Total Hardness (mg/L), Cadmium, Total Recoverable (µg/L), Zinc, Total Recoverable (µg/L), Copper, Total Recoverable (µg/L), and Lead, Total Recoverable (µg/L).

e) Reporting of Chronic Toxicity Monitoring Results

iii. WET test results shall be submitted to the St. Louis Regional Office, or by eDMR, with the permittee's Discharge Monitoring Reports by **October 28, 2016**. The submittal shall include:

1. A full laboratory report for all toxicity testing.
2. Copies of chain-of-custody forms.
3. The WET form provided by the Department upon permit issuance.

iv. The report must include a quantification of chronic toxic units (TU<sub>c</sub> = 100/IC<sub>25</sub>) reported according to the *Methods for Measuring the Chronic Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms* chapter on report preparation and test review. The 25 percent Inhibition Effect Concentration (IC<sub>25</sub>) is the toxic or effluent concentration that would cause 25 percent reduction in mean young per female or in growth for the test populations.

f) Permit Reopener for Chronic Toxicity

In accordance with 40 CFR Parts 122 and 124, this permit may be modified to include effluent limitations or permit conditions to address chronic toxicity in the effluent or receiving waterbody, as a result of the discharge; or to implement new, revised, or newly interpreted water quality standards applicable to chronic toxicity.

D. SPECIAL CONDITIONS (continued)

23. **Total Toxic Organics** – report as a total of all detections

Acenaphthene	4-chlorophenyl phenyl ether
Acrolein	4-bromophenyl phenyl ether
Acrylonitrile	Bis (2-chloroisopropyl) ether
Benzene	Bis (2-chloroethoxy) methane
Benzidine	Methylene Chloride (dichloromethane)
Carbon Tetrachloride (tetrachloromethane)	Methyl Chloride (chloromethane)
Chlorobenzene	Methyl bromide (bromomethane)
1,2,4-trichlorobenzene	Bromoform (tribromomethane)
Hexachlorobenzene	Dichlorobromomethane
1,2-dichloroethane	Chlorodibromomethane
1,1,1-trichloroethane	Hexachlorobutadiene
Hexachloroethane	Hexachlorocyclopentadiene
1,1-dichloroethane	Isophorone
1,1,2-trichloroethane	Naphthalene
1,1,2,2-tetrachloroethane	Nitrobenzene
Chloroethane	2-nitrophenol
Bis (2-chloroethyl) ether	4-nitrophenol
2-chloroethyl vinyl ether	2,4-dinitrophenol
N-nitrosodi-n-propylamine	4,6-dinitro-o-cresol
Pentachlorophenol	N-nitrosodimethylamine
Phenol	N-nitrosodiphenylamine
Bis (2-ethylhexyl) phthalate	Phenanthrene
Butyl benzyl phthalate	1,2,5,6-dibenzanthracene (dibenzo(a,h)anthracene)
Di-n-butyl phthalate	Indeno (1,2,3-cd) pyrene (2,3-o-phenylene pyrene)
Di-n-octyl phthalate	Pyrene
Diethyl phthalate	Tetrachloroethylene
Dimethyl phthalate	Toluene
1,2-benzanthracene (benzo(a)anthracene)	Trichloroethylene
Benzo(a)pyrene (3,4-benzopyrene)	Vinyl Chloride (chloroethylene)
3,4-benzofluoranthene (benzo(b)fluoranthene)	Aldrin
1,1,2-benzofluoranthene (benzo(k)fluoranthene)	Dieldrin
Chrysene	Chlordane (technical mixture and metabolites)
Anthracene	4,4-DDT
1,12-benzoperylene (benzo(ghi)perylene)	4,4-DDE (p,p-DDX)
Fluorene	4,4-DDD (p,p-TDE)
2-chloronaphthalene	Alpha-endosulfan
2,4,6-trichlorophenol	Beta-endosulfan
Parachlorometa cresol	Endosulfan sulfate
Chloroform (trichloromethane)	Endrin
2-chlorophenol	Endrin aldehyde
1,2-dichlorobenzene	Heptachlor
1,3-dichlorobenzene	Heptachlor epoxide (BHC hexachlorocyclohexane)
1,4-dichlorobenzene	Alpha-BHC
3,3-dichlorobenzidine	Beta-BHC
1,1-dichloroethylene	Gamma-BHC
1,2-trans-dichloroethylene	Delta-BHC (PCB polychlorinated biphenyls)
2,4-dichlorophenol	PCB-1242 (Arochlor 1242)
1,2-dichloropropane (1,3-dichloropropane)	PCB-1254 (Arochlor 1254)
2,4-dimethylphenol	PCB-1221 (Arochlor 1221)
2,4-dinitrotoluene	PCB-1232 (Arochlor 1232)
2,6-dinitrotoluene	PCB-1248 (Arochlor 1248)
1,2-diphenylhydrazine	PCB-1260 (Arochlor 1260)
Ethylbenzene	PCB-1016 (Arochlor 1016)
Fluoranthene	Toxaphene

**MISSOURI DEPARTMENT OF NATURAL RESOURCES  
FACT SHEET  
FOR THE PURPOSE OF RENEWAL  
OF  
MO-0086126  
MSD FENTON WASTEWATER TREATMENT PLANT**

The Federal Water Pollution Control Act ("Clean Water Act" Section 402 Public Law 92-500 as amended) established the National Pollution Discharge Elimination System (NPDES) permit program. This program regulates the discharge of pollutants from point sources into the waters of the United States, and the release of storm water from certain point sources. All such discharges are unlawful without a permit (Section 301 of the "Clean Water Act"). After a permit is obtained, a discharge not in compliance with all permit terms and conditions is unlawful. Missouri State Operating Permits (MSOPs) are issued by the Director of the Missouri Department of Natural Resources (Department) under an approved program, operating in accordance with federal and state laws (Federal "Clean Water Act" and "Missouri Clean Water Law" Section 644 as amended). MSOPs are issued for a period of five (5) years unless otherwise specified.

As per [40 CFR Part 124.8(a)] and [10 CSR 20-6.020(1)2.] a Factsheet shall be prepared to give pertinent information regarding the applicable regulations, rationale for the development of effluent limitations and conditions, and the public participation process for the Missouri State Operating Permit (operating permit) listed below.

A Factsheet is not an enforceable part of an operating permit.

This Factsheet is for a Major

**Part I – Facility Information**

Facility Type: POTW - SIC #4952

Facility Description:

Influent lift station / primary clarifier / activated sludge / ultraviolet disinfection / gravity sludge thickener / sludge belt press / sludge holding tank / sludge is hauled to other MSD facilities, landfilled, or land applied.

Have any changes occurred at this facility or in the receiving water body that effects effluent limit derivation?

- No.

Application Date: 05/30/2012

Expiration Date: 11/29/2012

**OUTFALL(S) TABLE:**

OUTFALL	DESIGN FLOW (CFS)	TREATMENT LEVEL	EFFLUENT TYPE
#001	10.5	Secondary	Domestic

Facility Performance History:

The facility had no reported Discharge Monitoring Report exceedances since December 1, 2007. The facility was last inspected on June 6, 2013. The conditions of the facility at the time of inspection were found to be satisfactory.

**Part II – Operator Certification Requirements**

Applicable ; This facility is required to have a certified operator.

As per [10 CSR 20-6.010(8) Terms and Conditions of a Permit], permittees shall operate and maintain facilities to comply with the Missouri Clean Water Law and applicable permit conditions and regulations. Operators or supervisors of operations at regulated wastewater treatment facilities shall be certified in accordance with [10 CSR 20-9.020(2)] and any other applicable state law or regulation. As per [10 CSR 20-9.020(2)(A)], requirements for operation by certified personnel shall apply to all wastewater treatment systems, if applicable, as listed below:

Check boxes below that are applicable to the facility;

- Owned or operated by or for:
  - Municipalities
  - Public Sewer District:
  - County
  - Public Water Supply Districts:
  - Private sewer company regulated by the Public Service Commission:
  - State or Federal agencies:

Each of the above entities are only applicable if they have a Population Equivalent greater than two hundred (200) and/or fifty (50) or more service connections.

This facility currently requires an operator with an A Certification Level. Please see **Appendix - Classification Worksheet**. Modifications made to the wastewater treatment facility may cause the classification to be modified.

Operator’s Name: Todd V. Heller  
 Certification Number: 3882  
 Certification Level: A

The listing of the operator above only signifies that staff drafting this operating permit have reviewed appropriate Department records and determined that the name listed on the operating permit application has the correct and applicable Certification Level.

**Part III– Operational Monitoring**

As per [10 CSR 20-9.010(4)], the facility is required to conduct operational monitoring.

**Part IV – Receiving Stream Information**

10 CSR 20-7.031 Missouri Water Quality Standards, the Department defines the Clean Water Commission water quality objectives in terms of "water uses to be maintained and the criteria to protect those uses." The receiving stream and/or 1<sup>st</sup> classified receiving stream’s beneficial water uses to be maintained are located in the Receiving Stream Table located below in accordance with [10 CSR 20-7.031(3)].

**RECEIVING STREAM(S) TABLE: OUTFALL #001**

WATER-BODY NAME	CLASS	WBID	DESIGNATED USES*	12-DIGIT HUC	DISTANCE TO CLASSIFIED SEGMENT (MI)
Meramec River	P	2183	LWW, AQL, WBC-A, SCR, DWS, IND	07140102-1003	0

\* - Irrigation (IRR), Livestock & Wildlife Watering (LWW), Protection of Warm Water Aquatic Life and Human Health-Fish Consumption (AQL), Cool Water Fishery(CLF), Cold Water Fishery (CDF), Whole Body Contact Recreation (WBC), Secondary Contact Recreation (SCR), Drinking Water Supply (DWS), Industrial (IND), Groundwater (GRW).

\*\* - Ecological Drainage Unit

**RECEIVING STREAM(S) LOW-FLOW VALUES:**

RECEIVING STREAM (U, C, P)	LOW-FLOW VALUES (CFS)		
	1Q10	7Q10	30Q10
Meramec River (P)	369	387	449

**MIXING CONSIDERATIONS**

**MIXING CONSIDERATIONS TABLE:**

MIXING ZONE (CFS) [10 CSR 20-7.031(4)(A)4.B.(II)(a)]			ZONE OF INITIAL DILUTION (CFS) [10 CSR 20-7.031(4)(A)4.B.(II)(b)]		
1Q10	7Q10	30Q10	1Q10	7Q10	30Q10
92.25	96.75	112.25	9.225	9.675	11.225

**RECEIVING STREAM MONITORING REQUIREMENTS:**

No receiving water monitoring requirements recommended at this time. Outfalls S1 and S2 were eliminated as there were no impacts observed.

Receiving Water Body's Water Quality

No stream surveys have been conducted for this facility.

**Part V – Rationale and Derivation of Effluent Limitations & Permit Conditions**

**ALTERNATIVE EVALUATIONS FOR NEW FACILITIES:**

As per [10 CSR 20-7.015(4)(A)], discharges to losing streams shall be permitted only after other alternatives including land application, discharges to a gaining stream and connection to a regional wastewater treatment facility have been evaluated and determined to be unacceptable for environmental and/or economic reasons.

Not Applicable ; The facility does not discharge to a Losing Stream as defined by [10 CSR 20-2.010(36)] & [10 CSR 20-7.031(1)(N)], or is an existing facility.

**ANTI-BACKSLIDING:**

A provision in the Federal Regulations [CWA §303(d)(4); CWA §402(c); 40 CFR Part 122.44(I)] that requires a reissued permit to be as stringent as the previous permit with some exceptions.

Limitations in this operating permit for the reissuance of this permit conform to the anti-backsliding provisions of Section 402(o) of the Clean Water Act, and 40 CFR Part 122.44.

- Information is available which was not available at the time of permit issuance (other than revised regulations, guidance, or test methods) and which would have justified the application of a less stringent effluent limitation at the time of permit issuance. The parameters changed include; Ammonia as N, Temperature, Cadmium, Copper, and Lead. Ammonia, Temperature, Copper, and Lead did not show a reasonable potential to violate Water Quality Standards. Ammonia, Copper, and Lead were changed to monitoring only and Temperature was removed from the permit. Cadmium limits were recalculated based on facility data.

**AREA-WIDE WASTE TREATMENT MANAGEMENT & CONTINUING AUTHORITY:**

As per [10 CSR 20-6.010(3)(B)], ... An applicant may utilize a lower preference continuing authority by submitting, as part of the application, a statement waiving preferential status from each existing higher preference authority, providing the waiver does not conflict with any area-wide management plan approved under section 208 of the Federal Clean Water Act or any other regional sewage service and treatment plan approved for higher preference authority by the Department.

**BIOSOLIDS & SEWAGE SLUDGE:**

Biosolids are solid materials resulting from domestic wastewater treatment that meet federal and state criteria for beneficial uses (i.e. fertilizer). Sewage sludge is solids, semi-solids, or liquid residue generated during the treatment of domestic sewage in a treatment works; including but not limited to, domestic septage; scum or solids removed in primary, secondary, or advanced wastewater treatment process; and a material derived from sewage sludge. Sewage sludge does not include ash generated during the firing of sewage sludge in a sewage sludge incinerator or grit and screening generated during preliminary treatment of domestic sewage in a treatment works. Additional information regarding biosolids and sludge is located at the following web address:

<http://dnr.mo.gov/env/wpp/pub/index.html>, items WQ422 through WQ449.

- Permittee land applies biosolids in accordance with Standard Conditions III and a Department approved biosolids management plan.

**COMPLIANCE AND ENFORCEMENT:**

Enforcement is the action taken by the Water Protection Program (WPP) to bring an entity into compliance with the Missouri Clean Water Law, its implementing regulations, and/or any terms and conditions of an operating permit. The primary purpose of the enforcement activity in the WPP is to resolve violations and return the entity to compliance.

Not Applicable ; The permittee/facility is not currently under Water Protection Program enforcement action.

**PRETREATMENT PROGRAM:**

The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to or in lieu of discharging or otherwise introducing such pollutants into a Publicly Owned Treatment Works [40 CFR Part 403.3(q)].

Pretreatment programs are required at any POTW (or combination of POTW operated by the same authority) and/or municipality with a total design flow greater than 5.0 MGD and receiving industrial wastes that interfere with or pass through the treatment works or are otherwise subject to the pretreatment standards. Pretreatment programs can also be required at POTWs/municipals with a design flow less than 5.0 MGD if needed to prevent interference with operations or pass through.

Several special conditions pertaining to the permittee's pretreatment program may be included in the permit, and are as follows:

- Implementation and enforcement of the program,
- Annual pretreatment report submittal,
- Submittal of list of industrial users,
- Technical evaluation of need to establish local limitations, and
- Submittal of the results of the evaluation

Applicable ; This permittee has an approved pretreatment program in accordance with the requirements of [40 CFR Part 403] and [10 CSR 20-6.100] and is expected to implement and enforce its approved program.

**REASONABLE POTENTIAL ANALYSIS (RPA):**

Federal regulation [40 CFR Part 122.44(d)(1)(i)] requires effluent limitations for all pollutants that are or may be discharged at a level that will cause or have the reasonable potential to cause or contribute to an in-stream excursion above narrative or numeric water quality standard.

In accordance with [40 CFR Part 122.44(d)(iii)] if the permit writer determines that any given pollutant has the reasonable potential to cause, or contribute to an in-stream excursion above the WQS, the permit must contain effluent limits for that pollutant.

Applicable ; A RPA was conducted on appropriate parameters. Please see **APPENDIX – RPA RESULTS**.

**REMOVAL EFFICIENCY:**

Removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD<sub>5</sub>) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals.

Applicable ; Secondary Treatment is 85% removal [40 CFR Part 133.102(a)(3) & (b)(3)].

**SANITARY SEWER OVERFLOWS (SSO) AND INFLOW AND INFILTRATION (I&I):**

Sanitary Sewer Overflows (SSOs) are defined as untreated sewage releases and are considered bypassing under state regulation [10 CSR 20-2.010(11)] and should not be confused with the federal definition of bypass. SSOs result from a variety of causes including blockages, line breaks, and sewer defects that can either allow wastewater to backup within the collection system during dry weather conditions or allow excess stormwater and groundwater to enter and overload the collection system during wet weather conditions. SSOs can also result from lapses in sewer system operation and maintenance, inadequate sewer design and construction, power failures, and vandalism. SSOs include overflows out of manholes, cleanouts, broken pipes, and other into waters of the state and onto city streets, sidewalks, and other terrestrial locations.

Inflow and Infiltration (I&I) is defined as unwanted intrusion of stormwater or groundwater into a collection system. This can occur from points of direct connection such as sump pumps, roof drain downspouts, foundation drains, and storm drain cross-connections or through cracks, holes, joint failures, faulty line connections, damaged manholes, and other openings in the collection system itself. I&I results from a variety of causes including line breaks, improperly sealed connections, cracks caused by soil erosion/settling, penetration of vegetative roots, and other sewer defects. In addition, excess stormwater and groundwater entering the collection system from line breaks and sewer defects have the potential to negatively impact the treatment facility.

Missouri RSMo §644.026.1.(13) mandates that the Department issue permits for discharges of water contaminants into the waters of this state, and also for the operation of sewer systems. Such permit conditions shall ensure compliance with all requirements as established by sections 644.006 to 644.141. Standard Conditions Part I, referenced in the permit, contains provisions requiring proper operation and maintenance of all facilities and systems of treatment and control. Missouri RSMo §644.026.1.(15) instructs the Department to require proper maintenance and operation of treatment facilities and sewer systems and proper disposal of residual waste from all such facilities. To ensure that public health and the environment are protected, any noncompliance which may endanger public health or the environment must be reported to the Department within 24 hours of the time the permittee becomes aware of the noncompliance. Standard Conditions Part I, referenced in the permit, contains the reporting requirements for the permittee when bypasses and upsets occur.

- The permittee has developed and is currently implementing a program for maintenance and repair of the collection system. The permittee's program is consistent with the US EPA's Guide For Evaluating Capacity, Management, Operation, And Maintenance (CMOM) Programs At Sanitary Sewer Collection Systems (Document number EPA 305-B-05-002). The permittee shall continue to submit semi-annual and annual reports as required by the federal consent decree entered in the matter of The United States et al. v. The Metropolitan St. Louis Sewer District, No. 4:07-CV-1120 (E.D. Mo.) which was entered on April 27, 2012.

- This facility is not required to develop or implement a program for maintenance and repair of the collection system; however, it is a violation of Missouri State Environmental Laws and Regulations to allow untreated wastewater to discharge to waters of the state.

**SCHEDULE OF COMPLIANCE (SOC):**

A schedule of remedial measures included in a permit, including an enforceable sequence of interim requirements (actions, operations, or milestone events) leading to compliance with the Missouri Clean Water Law, its implementing regulations, and/or the terms and conditions of an operating permit.

Not Applicable ; This permit does not contain a SOC.

**STORMWATER POLLUTION PREVENTION PLAN (SWPPP):**

In accordance with 40 CFR 122.44(k) *Best Management Practices (BMPs)* to control or abate the discharge of pollutants when: (1) Authorized under section 304(e) of the Clean Water Act (CWA) for the control of toxic pollutants and hazardous substances from ancillary industrial activities; (2) Authorized under section 402(p) of the CWA for the control of stormwater discharges; (3) Numeric effluent limitations are infeasible; or (4) the practices are reasonably necessary to achieve effluent limitations and standards or to carry out the purposes and intent of the CWA.

Not Applicable ; At this time, the permittee is not required to develop and implement a SWPPP.

**VARIANCE:**

As per the Missouri Clean Water Law § 644.061.4, variances shall be granted for such period of time and under such terms and conditions as shall be specified by the commission in its order. The variance may be extended by affirmative action of the commission. In no event shall the variance be granted for a period of time greater than is reasonably necessary for complying with the Missouri Clean Water Law §§644.006 to 644.141 or any standard, rule or regulation promulgated pursuant to Missouri Clean Water Law §644.006 to 644.141.

Not Applicable ; This operating permit is not drafted under premises of a petition for variance.

**WASTELOAD ALLOCATIONS (WLA) FOR LIMITS:**

As per [10 CSR 20-2.010(78)], the amount of pollutant each discharger is allowed by the Department to release into a given stream after the Department has determined total amount of pollutant that may be discharged into that stream without endangering its water quality.

Applicable ; Wasteload allocations were calculated where applicable using water quality criteria or water quality model results and the dilution equation below:

$$C_e = \frac{(Q_e + Q_s)C - (C_s \times Q_s)}{(Q_e)} \quad (\text{EPA/505/2-90-001, Section 4.5.5})$$

Where C = downstream concentration  
Cs = upstream concentration  
Qs = upstream flow  
Ce = effluent concentration  
Qe = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

Number of Samples "n":

Additionally, in accordance with the TSD for water quality-based permitting, effluent quality is determined by the underlying distribution of daily values, which is determined by the Long Term Average (LTA) associated with a particular Wasteload Allocation (WLA) and by the Coefficient of Variation (CV) of the effluent concentrations. Increasing or decreasing the monitoring frequency does not affect this underlying distribution or treatment performance, which should be, at a minimum, be targeted to comply with the values dictated by the WLA. Therefore, it is recommended that the actual planned frequency of monitoring normally be used to determine the value of "n" for calculating the AML. However, in situations where monitoring frequency is once per month or less, a higher value for "n" must be assumed for AML derivation purposes. Thus, the statistical procedure being employed using an assumed number of samples is "n = 4" at a minimum. For Total Ammonia as Nitrogen, "n = 30" is used.

**WLA MODELING:**

There are two general types of effluent limitations, technology-based effluent limits (TBELs) and water quality based effluent limits (WQBELs). If TBELs do not provide adequate protection for the receiving waters, then WQBEL must be used.

Not Applicable ; A WLA study was either not submitted or determined not applicable by Department staff.

**WATER QUALITY STANDARDS:**

Per [10 CSR 20-7.031(3)], General Criteria shall be applicable to all waters of the state at all times including mixing zones. Additionally, [40 CFR 122.44(d)(1)] directs the Department to establish in each NPDES permit to include conditions to achieve water quality established under Section 303 of the Clean Water Act, including State narrative criteria for water quality.

**WHOLE EFFLUENT TOXICITY (WET) TEST:**

A WET test is a quantifiable method of determining if a discharge from a facility may be causing toxicity to aquatic life by itself, in combination with or through synergistic responses when mixed with receiving stream water.

Applicable ; Under the federal Clean Water Act (CWA) §101(a)(3), requiring WET testing is reasonably appropriate for site-specific Missouri State Operating Permits for discharges to waters of the state issued under the National Pollutant Discharge Elimination System (NPDES). WET testing is also required by 40 CFR 122.44(d)(1). WET testing ensures that the provisions in the 10 CSR 20-6.010(8)(A)7. and the Water Quality Standards 10 CSR 20-7.031(3)(D),(F),(G),(I)2.A & B are being met. Under [10 CSR 20-6.010(8)(A)4], the Department may require other terms and conditions that it deems necessary to assure compliance with the Clean Water Act and related regulations of the Missouri Clean Water Commission. In addition the following MCWL apply: §§644.051.3 requires the Department to set permit conditions that comply with the MCWL and CWA; 644.051.4 specifically references toxicity as an item we must consider in writing permits (along with water quality-based effluent limits, pretreatment, etc...); and 644.051.5 is the basic authority to require testing conditions. WET test will be required by facilities meeting the following criteria:

Facility is a designated Major.

- Facility continuously or routinely exceeds its design flow.
- Facility (industrial) that alters its production process throughout the year.
- Facility handles large quantities of toxic substances, or substances that are toxic in large amounts.
- Facility has Water Quality-based Effluent Limitations for toxic substances (other than NH<sub>3</sub>)
- Facility is a municipality or domestic discharger with a Design Flow  $\geq$  22,500 gpd.
- Other – please justify.

**40 CFR 122.41(M) - BYPASSES:**

The federal Clean Water Act (CWA), Section 402 prohibits wastewater dischargers from “bypassing” untreated or partially treated sewage (wastewater) beyond the headworks. A bypass is defined as an intentional diversion of waste streams from any portion of a treatment facility, [40 CFR 122.41(m)(1)(i)]. Additionally, Missouri regulation 10 CSR 20-7.015(9)(G) defines a bypass as the intentional diversion of waste streams from any portion of a treatment facility, except in the case of blending. Only under exceptional and specified limitations do the federal regulations allow for a facility to bypass some or all of the flow from its treatment process. Bypasses are prohibited by the CWA unless a permittee can meet all of the criteria listed in 40 CFR 122.41(m)(4)(i)(A), (B), & (C). Any bypasses from this facility are subject to the reporting required in 40 CFR 122.41(l)(6) and per Missouri’s Standard Conditions I, Section B, part 2.b. Additionally, Anticipated Bypasses include bypasses from peak flow basins or similar devices designed for peak wet weather flows.

Not Applicable ; This facility does not anticipate bypassing.

**303(d) LIST & TOTAL MAXIMUM DAILY LOAD (TMDL):**

Section 303(d) of the federal Clean Water Act requires that each state identify waters that are not meeting water quality standards and for which adequate water pollution controls have not been required. Water quality standards protect such beneficial uses of water as whole body contact (such as swimming), maintaining fish and other aquatic life, and providing drinking water for people, livestock and wildlife. The 303(d) list helps state and federal agencies keep track of waters that are impaired but not addressed by normal water pollution control programs.

Not Applicable ; This facility does not discharge to a 303(d) listed stream.

## **Part VI –2013 Water Quality Criteria for Ammonia**

Upcoming changes to the Water Quality Standard for ammonia may require significant upgrades to wastewater treatment facilities.

On August 22, 2013, the U.S. Environmental Protection Agency (EPA) finalized new water quality criteria for ammonia, based on toxicity studies of mussels and gill breathing snails. Missouri's current ammonia criteria are based on toxicity testing of several species, but did not include data from mussels or gill breathing snails. Missouri is home to 69 of North America's mussel species, which are spread across the state. According to the Missouri Department of Conservation nearly two-thirds of the mussel species in Missouri are considered to be "of conservation concern". Nine species are listed as federally endangered, with an additional species currently proposed as endangered and another species proposed as threatened.

The adult forms of mussels that are seen in rivers, lakes, and streams are sensitive to pollutants because they are sedentary filter feeders. They vacuum up many pollutants with the food they bring in and cannot escape to new habitats, so they can accumulate toxins in their bodies and die. But very young mussels, called glochidia, are exceptionally sensitive to ammonia in water. As a result of a citizen suit, the EPA was compelled to conduct toxicity testing and develop ammonia water quality criteria that would be protective if young mussels may be present in a waterbody. These new criteria will apply to any discharge with ammonia levels that may pose a reasonable potential to violate the standards. Nearly all discharging domestic wastewater treatment facilities (cities, subdivisions, mobile home parks, etc.), as well as certain industrial and stormwater dischargers with ammonia in their effluent, will be affected by this change in the regulations.

When new water quality criteria are established by the EPA, states must adopt them into their regulations in order to keep their authorization to issue permits under the National Pollutant Discharge Elimination System (NPDES). States are required to review their water quality standards every three years, and if new criteria have been developed they must be adopted. States may be more protective than the Federal requirements, but not less protective. Missouri does not have the resources to conduct the studies necessary for developing new water quality standards, and therefore our standards mirror those developed by the EPA; however, we will utilize any available flexibility based on actual species of mussels that are native to Missouri and their sensitivity to ammonia.

Many treatment facilities in Missouri are currently scheduled to be upgraded to comply with the current water quality standards. But these new ammonia standards may require a different treatment technology than the one being considered by the permittee. It is important that permittees discuss any new and upcoming requirements with their consulting engineers to ensure that their treatment systems are capable of complying with the new requirements. The Department encourages permittees to construct treatment technologies that can attain effluent quality that supports the EPA ammonia criteria.

Ammonia toxicity varies by temperature and by pH of the water. Assuming a stable pH value, but taking into account winter and summer temperatures, Missouri includes two seasons of ammonia effluent limitations. There are no current effluent limitations in this permit as the facility did not show a reasonable potential to violate current Water Quality Standards for Ammonia as N.

Under the new EPA criteria, where mussels of the family Unionidae are present or expected to be present, the estimated effluent limitations for a facility in a location such as this that discharges to a receiving stream with the mixing consideration listed in Part IV of the Fact Sheet will be:

Summer – 6.4 mg/L daily maximum, 2.4 mg/L monthly average.  
Winter – 15.2 mg/L daily maximum, 5.8 mg/L monthly average.

Actual effluent limits will depend in part on the actual performance of the facility.

Operating permits for facilities in Missouri must be written based on current statutes and regulations. Therefore permits will be written with the existing effluent limitations until the new standards are adopted. To aid permittees in decision making, an advisory will be added to permit Fact Sheets notifying permittees of the expected effluent limitations for ammonia. When setting schedules of compliance for ammonia effluent limitations, consideration will be given to facilities that have recently constructed upgraded facilities to meet the current ammonia limitations.

For more information on this topic feel free to contact the Missouri Department of Natural Resources, Water Protection Program, Water Pollution Control Branch, Operating Permits Section at (573) 751-1300.

## Part VII – Effluent Limits Determination

### APPLICABLE DESIGNATIONS OF WATERS OF THE STATE:

As per Missouri’s Effluent Regulations [10 CSR 20-7.015], the waters of the state are divided into the below listed seven (7) categories. Each category lists effluent limitations for specific parameters, which are presented in each outfall’s Effluent Limitation Table and further discussed in the Derivation & Discussion of Limits section.

- Missouri or Mississippi River [10 CSR 20-7.015(2)]:
- Lake or Reservoir [10 CSR 20-7.015(3)]:
- Losing [10 CSR 20-7.015(4)]:
- Metropolitan No-Discharge [10 CSR 20-7.015(5)]:
- Special Stream [10 CSR 20-7.015(6)]:
- Subsurface Water [10 CSR 20-7.015(7)]:
- All Other Waters [10 CSR 20-7.015(8)]:

### OUTFALL #001 – MAIN FACILITY OUTFALL

Effluent limitations derived and established in the below Effluent Limitations Table are based on current operations of the facility. Future permit action due to facility modification may contain new operating permit terms and conditions that supersede the terms and conditions, including effluent limitations, of this operating permit.

### EFFLUENT LIMITATIONS TABLE:

PARAMETER	Unit	Basis for Limits	Daily Maximum	Weekly Average	Monthly Average	Modified	Previous Permit Limitations
Flow	MGD	1	*		*	*/*	*/*
CBOD <sub>5</sub>	mg/L	1		40	25	No	40/25
TSS	mg/L	1		45	30	No	45/30
pH	SU	1	6.0 – 9.0			No	6.0 – 9.0
Ammonia as N (April 1 – Sept 30)	mg/L	2, 3	*		*	Yes	19/9.5
Ammonia as N (Oct 1 – March 31)	mg/L	2, 3	*		*	Yes	19/9.5
Escherichia coli	***	1, 3		630	126	Yes	Previously Fecal Coliform
Oil & Grease (mg/L)	mg/L	1, 3	15		10	No	15/10
Cadmium, TR	µg/L	2, 3	7.2		2.4	Yes	6.2/2.6
Zinc, TR	µg/L	2, 3	345.7		132.3	Yes	*/*
Copper, TR	µg/L	7	*		*	Yes	40.1/16.7
Lead, TR	µg/L	7	*		*	Yes	54.0/19.5
Total Toxic Organics	µg/L	7	*		*	No	*/*
Total Phosphorus	mg/L	1	*		*	Yes	****
Total Nitrogen	mg/L	1	*		*	Yes	****
Acute Toxicity	TUa	9	*			Yes	% survival
Chronic Toxicity	TUc	9	*			Yes	****

\* - Monitoring requirement only.

\*\* - For DO the Daily Maximum is a Daily Minimum and the Monthly Average is a Monthly Average Minimum.

\*\*\* - # of colonies/100mL; the Monthly Average for *E. coli* is a geometric mean.

\*\*\*\* - Parameter not previously established in previous state operating permit.

#### Basis for Limitations Codes:

1. State or Federal Regulation/Law
2. Water Quality Standard (includes RPA)
3. Water Quality Based Effluent Limits
4. Antidegradation Review
5. Antidegradation Policy
6. Water Quality Model
7. Best Professional Judgment
8. TMDL or Permit in lieu of TMDL
9. WET Test Policy

**OUTFALL #001 – DERIVATION AND DISCUSSION OF LIMITS:**

- **Flow**. In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the Department, which may require the submittal of an operating permit modification.
- **Carbonaceous Biochemical Oxygen Demand (CBOD<sub>5</sub>)**.
  - Effluent limitations have been retained from previous state operating permit, please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information**.
- **Total Suspended Solids (TSS)**.
  - Effluent limitations have been retained from previous state operating permit, please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information**.
- **pH**. – 6.0-9.0 SU. Technology based limits [10 CSR 20-7.015] are protective of the water quality standard [10 CSR 20-7.031(4)(E)], due to the buffering capacity of the mixing zone.
- **Total Ammonia Nitrogen**. Monitoring only as the facility did not show a reasonable potential to violate water quality standards. The parameter will be reviewed at the next renewal.
- **Escherichia coli (E. coli)**. Monthly average of 126 per 100 ml as a geometric mean and Weekly Average of 630 during the recreational season (April 1 – October 31), to protect Whole Body Contact Recreation (A) designated use of the receiving stream, as per 10 CSR 20-7.031(4)(C). An effluent limit for both monthly average and weekly average is required by 40 CFR 122.45(d).
- **Oil & Grease**. Conventional pollutant, effluent limitation for protection of aquatic life; 10 mg/L monthly average, 15 mg/L daily maximum.
- **Temperature**. This parameter was removed as it did not show a reasonable potential to violate Water Quality Standards.
- **Total Phosphorus and Total Nitrogen**. Monitoring required for facilities greater than 100,000 gpd design flow per 10 CSR 20-7.015(9)(D)7.

**Metals**

Effluent limitations for total recoverable metals were developed using methods and procedures outlined in the “Technical Support Document For Water Quality-based Toxic Controls” (EPA/505/2-90-001) and “The Metals Translator: Guidance For Calculating A Total Recoverable Permit Limit From A Dissolved Criterion” (EPA 823-B-96-007). General warm-water fishery criteria apply and a water hardness of 162 mg/L is used in the conversion below.

Due to the absence of contemporaneous effluent and instream data for total recoverable metals, dissolved metals, hardness, and total suspended solids with which to calculate metals translators, partitioning between the dissolved and absorbed phases was assumed to be minimal (Section 5.7.3, EPA/505/2-90-001). Freshwater criteria conversion factors for dissolved metals were used as the metals translator as recommended in guidance (Section 1.3, 1.5.3, and Table 1, EPA 823-B-96-007). If concurrent site-specific data for total recoverable metals, dissolved metals, hardness, and total suspended solids are provided to the Department, partitioning evaluations may be considered and site-specific translators developed.

METAL	CONVERSION FACTORS	
	ACUTE	CHRONIC
Cadmium	0.924	0.889
Zinc	0.980	0.980

Conversion factors for Cadmium and Zinc are hardness dependent. Values calculated using equation found in Section 1.3 of EPA 823-B-96-007 and hardness = 162 mg/L.

- **Cadmium, Total Recoverable**. Protection of Aquatic Life Chronic Criteria = 0.344 µg/L, Acute Criteria = 7.6 µg/L.

Chronic =  $0.344/0.889 = 0.39 \mu\text{g/L}$   
 Acute =  $7.6/0.924 = 8.23 \mu\text{g/L}$

Chronic WLA:  $C_e = ((10.46 + 96.75)0.39 - (96.75 * 0.0))/10.46$   
 $C_e = 3.99 \mu\text{g/L}$

Acute WLA:  $C_e = ((10.46 + 9.675)8.23 - (9.675 * 0.0))/10.46$   
 $C_e = 15.84 \mu\text{g/L}$

$LTA_c = 3.99 (0.242) = 0.96 \mu\text{g/L}$  [CV = 1.65, 99<sup>th</sup> Percentile]  
 $LTA_a = 15.84 (0.134) = 2.1 \mu\text{g/L}$  [CV = 1.65, 99<sup>th</sup> Percentile]  
Use most protective number of  $LTA_c$  or  $LTA_a$ .

MDL =  $0.96 (7.46) = 7.2 \mu\text{g/L}$  [CV = 1.65, 99<sup>th</sup> Percentile]  
AML =  $0.96 (2.52) = 2.4 \mu\text{g/L}$  [CV = 1.65, 95<sup>th</sup> Percentile, n = 4]

- **Zinc, TR.** Protection of Aquatic Life Chronic Criteria = 176  $\mu\text{g/L}$ , Acute Criteria = 176  $\mu\text{g/L}$ .

Chronic =  $176/0.980 = 179.59 \mu\text{g/L}$   
Acute =  $176/0.980 = 179.59 \mu\text{g/L}$

Chronic WLA:  $C_e = ((10.46 + 96.75)179.59 - (96.75 * 0.0))/10.46$   
 $C_e = 1840.33 \mu\text{g/L}$

Acute WLA:  $C_e = ((10.46 + 9.675)179.59 - (9.675 * 0.0))/10.46$   
 $C_e = 345.67 \mu\text{g/L}$

$LTA_c = 1840.33 (0.346) = 636.9 \mu\text{g/L}$  [CV = 1.09, 99<sup>th</sup> Percentile]  
 $LTA_a = 345.67 (0.188) = 64.94 \mu\text{g/L}$  [CV = 1.09, 99<sup>th</sup> Percentile]

Use most protective number of  $LTA_c$  or  $LTA_a$ .

MDL =  $64.94 (5.32) = 345.7 \mu\text{g/L}$  [CV = 1.09, 99<sup>th</sup> Percentile]  
AML =  $64.94 (2.04) = 132.3 \mu\text{g/L}$  [CV = 1.09, 95<sup>th</sup> Percentile, n = 4]

- **Copper, TR.** This parameter was retained in the permit as monitoring only. During the last permit renewal, the parameter was found to have a reasonable potential to violate Water Quality Standards, however it did not show a reasonable potential to violate Water Quality Standards during this renewal. The parameter will be reviewed during the next renewal period to determine if it has a reasonable potential. If it does not, this parameter may be removed.
- **Lead, TR.** This parameter was retained in the permit as monitoring only. During the last permit renewal, the parameter was found to have a reasonable potential to violate Water Quality Standards, however it did not show a reasonable potential to violate Water Quality Standards during this renewal. The parameter will be reviewed during the next renewal period to determine if it has a reasonable potential. If it does not, this parameter may be removed.
- **Arsenic, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Chromium III, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Chromium VI, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Arsenic, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Mercury, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Nickel, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Silver, TR.** This parameter was removed from the permit as it did not have a reasonable potential to violate Water Quality Standards.
- **Total Toxic Organics.** This parameter was retained from the previous permit as the facility did not ensure that proper test methods were used as several results were listed as non-detects, but the detection limits were above Water Quality Standards. The facility shall ensure that the test methods use test at or below the appropriate Water Quality Standards for the pollutant tested.

- **Acute WET Test.** Monitoring requirement only. Monitoring is required to determine if reasonable potential exists for this facility's discharge to exceed water quality standards

(Classified P with other than default Mixing Considerations, the AEC% is determined as follows:.

$$\text{Acute AEC\%} = ((\text{design flow}_{\text{cfs}} + \text{ZID}_{7\text{Q}10}) / \text{design flow}_{\text{cfs}})^{-1}] \times 100 = \#\#\%$$

$$((10.5+9.675)/10.5)^{-1} \times 100 = \mathbf{52\%}$$

- **Chronic Whole Effluent Toxicity.** Monitoring requirement only. Monitoring is required to determine if reasonable potential exists for this facility's discharge to exceed water quality standards.

Classified P with other than default Mixing Considerations, the AEC% is determined as follows:.

$$\text{Chronic AEC\%} = ((\text{design flow}_{\text{cfs}} + \text{MZ}_{7\text{Q}10}) / \text{design flow}_{\text{cfs}})^{-1}] \times 100 = \#\#\%$$

$$((10.5+96.75)/10.5)^{-1} \times 100 = \mathbf{10\%}$$

**Minimum Sampling and Reporting Frequency Requirements.**

PARAMETER	SAMPLING FREQUENCY	REPORTING FREQUENCY
Flow	once/day	once/month
CBOD <sub>5</sub>	three/week	once/month
TSS	three/week	once/month
pH	three/week	once/month
Ammonia as N	three/week	once/month
<i>E. coli</i>	three/week	once/month
Oil & Grease	once/month	once/month
Cadmium, TR	once/quarter	once/quarter
Zinc, TR	once/quarter	once/quarter
Copper, TR	once/quarter	once/quarter
Lead, TR	once/quarter	once/quarter
Total Phosphorus	once/quarter	once/quarter
Total Nitrogen	once/quarter	once/quarter
Total Toxic Organics	once/year	once/year
Acute WET Test	once/year	once/year
Chronic WET Test	once/permit cycle	once/permit cycle

**WET Test.** WET Testing schedules and intervals are established in accordance with the Department's Permit Manual; Section 5.2 *Effluent Limits / WET Testing for Compliance Bio-monitoring.* It is recommended that WET testing be conducted during the period of lowest stream flow.

**Acute Whole Effluent Toxicity**

- No less than ONCE/YEAR:**
  - Facility is designated as a Major facility or has a design flow  $\geq$  1.0 MGD.
  - Facility continuously or routinely exceeds their design flow.
  - Facility exceeds its design population equivalent (PE) for BOD<sub>5</sub> whether or not its design flow is being exceeded.
  - Facility has Water Quality-based effluent limitations for toxic substances (other than NH<sub>3</sub>).

**Chronic Whole Effluent Toxicity**

- No less than ONCE/PERMIT CYCLE:**
  - POTW facilities with a design flow of greater than 1.0 million gallons per day, but less than 10 million gallons per day, shall conduct and submit to the Department a chronic WET test no less than once per five years.

**Sampling Frequency Justification:**

Sampling and Reporting Frequency was retained from previous permit except for the parameters that the previous permit required to be conducted three times per week were changed to twice per week and the WET test, which was reduced to annually.

**Sampling Type Justification**

As per 10 CSR 20-7.015, BOD<sub>5</sub>, TSS, and WET test samples collected for mechanical plants shall be a 24 hour composite sample. Grab samples, however, must be collected for pH, Ammonia as N, *E. coli*, Oil & Grease, and Total Phosphorus. This is due to the holding time restriction for *E. coli*, the volatility of Ammonia, and the fact that pH cannot be preserved and must be sampled in the field. As Ammonia, Oil & Grease, and Total Phosphorus samples must be immediately preserved with acid, these samples are to be collected as a grab.

## **Part VIII – Finding of Affordability**

Pursuant to Section 644.145, RSMo., the Department is required to determine whether a permit or decision is affordable and makes a finding of affordability for certain permitting and enforcement decisions. This requirement applies to discharges from combined or separate sanitary sewer systems or publically-owned treatment works.

Applicable; The Department is required to determine findings of affordability because the permit applies to a **combined or separate sanitary sewer system for a publically-owned treatment works**. MSD waived the requirement of requiring an Affordability Analysis.

## **Part IX – Administrative Requirements**

On the basis of preliminary staff review and the application of applicable standards and regulations, the Department, as administrative agent for the Missouri Clean Water Commission, proposes to issue a permit(s) subject to certain effluent limitations, schedules, and special conditions contained herein and within the operating permit. The proposed determinations are tentative pending public comment.

### **PERMIT SYNCHRONIZATION:**

The Department of Natural Resources is currently undergoing a synchronization process for operating permits. Permits are normally issued on a five-year term, but to achieve synchronization many permits will need to be issued for less than the full five years allowed by regulation. The intent is that all permits within a watershed will move through the Watershed Based Management (WBM) cycle together will all expire in the same fiscal year. This will allow further streamlining by placing multiple permits within a smaller geographic area on public notice simultaneously, thereby reducing repeated administrative efforts. This will also allow the Department to explore a watershed based permitting effort at some point in the future.

### **PUBLIC NOTICE:**

The Department shall give public notice that a draft permit has been prepared and its issuance is pending. Additionally, public notice will be issued if a public hearing is to be held because of a significant degree of interest in and water quality concerns related to a draft permit. No public notice is required when a request for a permit modification or termination is denied; however, the requester and permittee must be notified of the denial in writing.

The Department must issue public notice of a pending operating permit or of a new or reissued statewide general permit. The public comment period is the length of time not less than 30 days following the date of the public notice which interested persons may submit written comments about the proposed permit.

For persons wanting to submit comments regarding this proposed operating permit, then please refer to the Public Notice page located at the front of this draft operating permit. The Public Notice page gives direction on how and where to submit appropriate comments.

- The Public Notice period for this operating permit was from September 19, 2014 to October 20, 2014. No responses received.

**DATE OF FACT SHEET:** AUGUST 4, 2014

### **COMPLETED BY:**

**BRANT FARRIS, ENVIRONMENTAL SPECIALIST III**  
**MISSOURI DEPARTMENT OF NATURAL RESOURCES**  
**WATER PROTECTION PROGRAM**  
**OPERATING PERMITS SECTION - DOMESTIC WASTEWATER UNIT**  
**(660) 385-8061**  
**brant.farris@dnr.mo.gov**

**Appendices**

**APPENDIX - CLASSIFICATION WORKSHEET:**

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
Maximum Population Equivalent (P.E.) served (Max 10 pts.)	1 pt./10,000 PE or major fraction thereof.	7
Maximum: 10 pt Design Flow (avg. day) or peak month; use greater (Max 10 pts.)	1 pt. / MGD or major fraction thereof.	7
<b>EFFLUENT DISCHARGE RECEIVING WATER SENSITIVITY:</b>		
Missouri or Mississippi River	0	
All other stream discharges except to losing streams and stream reaches supporting whole body contact	1	
Discharge to lake or reservoir outside of designated whole body contact recreational area	2	
Discharge to losing stream, or stream, lake or reservoir area supporting whole body contact recreation	3	3
<b>PRELIMINARY TREATMENT - Headworks</b>		
Screening and/or comminution	3	3
Grit removal	3	3
Plant pumping of main flow (lift station at the headworks)	3	3
<b>PRIMARY TREATMENT</b>		
Primary clarifiers	5	5
Combined sedimentation/digestion	5	
Chemical addition (except chlorine, enzymes)	4	
<b>REQUIRED LABORATORY CONTROL – performed by plant personnel (highest level only)</b>		
Push – button or visual methods for simple test such as pH, Settleable solids	3	
Additional procedures such as DO, COD, BOD, titrations, solids, volatile content	5	
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.	7	
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph	10	10
<b>ALTERNATIVE FATE OF EFFLUENT</b>		
Direct reuse or recycle of effluent	6	
Land Disposal – low rate	3	
High rate	5	
Overland flow	4	
<b>Total from page ONE (1)</b>	----	<b>41</b>

**APPENDIX - CLASSIFICATION WORKSHEET (CONTINUED):**

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
<b>VARIATION IN RAW WASTE (highest level only) (DMR exceedances and Design Flow exceedances)</b>		
Variation do not exceed those normally or typically expected	0	
Recurring deviations or excessive variations of 100 to 200 % in strength and/or flow	2	
Recurring deviations or excessive variations of more than 200 % in strength and/or flow	4	4
Raw wastes subject to toxic waste discharge	6	
<b>SECONDARY TREATMENT</b>		
Trickling filter and other fixed film media with secondary clarifiers	10	
Activated sludge with secondary clarifiers (including extended aeration and oxidation ditches)	15	15
Stabilization ponds without aeration	5	
Aerated lagoon	8	
Advanced Waste Treatment Polishing Pond	2	
Chemical/physical – without secondary	15	
Chemical/physical – following secondary	10	
Biological or chemical/biological	12	
Carbon regeneration	4	
<b>DISINFECTION</b>		
Chlorination or comparable	5	
Dechlorination	2	
On-site generation of disinfectant (except UV light)	5	
UV light	4	4
<b>SOLIDS HANDLING - SLUDGE</b>		
Solids Handling Thickening	5	5
Anaerobic digestion	10	
Aerobic digestion	6	
Evaporative sludge drying	2	
Mechanical dewatering	8	8
Solids reduction (incineration, wet oxidation)	12	
Land application	6	6
Total from page <b>TWO (2)</b>	----	42
Total from page <b>ONE (1)</b>	---	41
<b>Grand Total</b>	---	83

- A: 71 points and greater
- B: 51 points – 70 points
- C: 26 points – 50 points
- D: 0 points – 25 points

**APPENDIX – RPA RESULTS:**

Parameter	CMC*	RWC Acute*	CCC*	RWC Chronic*	n**	Range max/min	CV***	MF	RP Yes/No
Total Ammonia as Nitrogen (Summer) mg/L	12.1	5.50	1.5	0.89	259.00	9/0.025	1.55	1.15	No
Total Ammonia as Nitrogen (Winter) mg/L	12.1	7.62	3.1	1.23	393.00	13.9/0.025	1.60	1.03	No
Arsenic, Total Recoverable	NA	NA	20.00	0.46	22	5/1	0.503	0.949	No
Cadmium, Total Recoverable	8.23	2.22	0.39	0.42	21	4.5/0.05	1.651	0.948	Yes
Chromium III, Total Recoverable	2676.88	10.13	127.96	1.90	20	10/1	0.508	1.951	No
Chromium VI, Total Recoverable	15.00	8.15	10.00	1.53	21	12/1	0.451	1.307	No
Copper, Total Recoverable	22.05	2.90	14.09	0.54	21	5/1.5	0.276	1.115	No
Lead, Total Recoverable	150.82	6.51	5.88	1.22	22	10/0.45	0.733	1.254	No
Mercury, Total Recoverable	2.40	0.81	0.50	0.15	21	1/0.05	0.814	1.559	No
Nickel, Total Recoverable	706.10	10.16	78.50	1.91	21	20/4.5	0.438	0.981	No
Silver, Total Recoverable	8.69	7.50	NA	NA	21	15/1	1.004	0.962	No
Zinc, Total Recoverable	179.59	438.03	179.59	82.27	22	250/15	1.097	3.372	Yes

N/A – Not Applicable

\* - Units are (µg/L) unless otherwise noted.

\*\* - If the number of samples is 10 or greater, then the CV value must be used in the WQBEL for the applicable constituent. If the number of samples is < 10, then the default CV value must be used in the WQBEL for the applicable constituent.

\*\*\* - Coefficient of Variation (CV) is calculated by dividing the Standard Deviation of the sample set by the Mean of the same sample set.

RWC – Receiving Water Concentration. It is the concentration of a toxicant or the parameter toxicity in the receiving water after mixing (if applicable).

n – Is the number of samples.

MF – Multiplying Factor. 99% Confidence Level and 99% Probability Basis.

RP – Reasonable Potential. It is where an effluent is projected or calculated to cause an excursion above a water quality standard based on a number of factors including, as a minimum, the four factors listed in 40 CFR 122.44(d)(1)(ii).

Reasonable Potential Analysis is conducted as per (TSD, EPA/505/2-90-001, Section 3.3.2). A more detailed version including calculations of this RPA is available upon request.



STANDARD CONDITIONS FOR NPDES PERMITS  
ISSUED BY  
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES  
MISSOURI CLEAN WATER COMMISSION  
REVISED  
AUGUST 1, 2014

These Standard Conditions incorporate permit conditions as required by 40 CFR 122.41 or other applicable state statutes or regulations. These minimum conditions apply unless superseded by requirements specified in the permit.

## Part I – General Conditions

### Section A – Sampling, Monitoring, and Recording

1. **Sampling Requirements.**
  - a. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity.
  - b. All samples shall be taken at the outfall(s) or Missouri Department of Natural Resources (Department) approved sampling location(s), and unless specified, before the effluent joins or is diluted by any other body of water or substance.
2. **Monitoring Requirements.**
  - a. Records of monitoring information shall include:
    - i. The date, exact place, and time of sampling or measurements;
    - ii. The individual(s) who performed the sampling or measurements;
    - iii. The date(s) analyses were performed;
    - iv. The individual(s) who performed the analyses;
    - v. The analytical techniques or methods used; and
    - vi. The results of such analyses.
  - b. If the permittee monitors any pollutant more frequently than required by the permit at the location specified in the permit using test procedures approved under 40 CFR Part 136, or another method required for an industry-specific waste stream under 40 CFR subchapters N or O, the results of such monitoring shall be included in the calculation and reported to the Department with the discharge monitoring report data (DMR) submitted to the Department pursuant to Section B, paragraph 7.
3. **Sample and Monitoring Calculations.** Calculations for all sample and monitoring results which require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in the permit.
4. **Test Procedures.** The analytical and sampling methods used shall conform to the reference methods listed in 10 CSR 20-7.015 unless alternates are approved by the Department. The facility shall use sufficiently sensitive analytical methods for detecting, identifying, and measuring the concentrations of pollutants. The facility shall ensure that the selected methods are able to quantify the presence of pollutants in a given discharge at concentrations that are low enough to determine compliance with Water Quality Standards in 10 CSR 20-7.031 or effluent limitations unless provisions in the permit allow for other alternatives. A method is “sufficiently sensitive” when; 1) the method minimum level is at or below the level of the applicable water quality criterion for the pollutant or, 2) the method minimum level is above the applicable water quality criterion, but the amount of pollutant in a facility’s discharge is high enough that the method detects and quantifies the level of pollutant in the discharge, or 3) the method has the lowest minimum level of the analytical methods approved under 10 CSR 20-7.015. These methods are also required for parameters that are listed as monitoring only, as the data collected may be used to determine if limitations need to be established. A permittee is responsible for working with their contractors to ensure that the analysis performed is sufficiently sensitive.
5. **Record Retention.** Except for records of monitoring information required by the permit related to the permittee’s sewage sludge use and disposal activities, which shall be retained for a period of at least five (5) years (or longer as required by 40 CFR part 503), the permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the application for the permit, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Department at any time.

6. **Illegal Activities.**
  - a. The Federal Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the permit shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than two (2) years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than \$20,000 per day of violation, or by imprisonment of not more than four (4) years, or both.
  - b. The Missouri Clean Water Law provides that any person or who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than six (6) months, or by both. Second and successive convictions for violation under this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.

### Section B – Reporting Requirements

1. **Planned Changes.**
  - a. The permittee shall give notice to the Department as soon as possible of any planned physical alterations or additions to the permitted facility when:
    - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b); or
    - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements under 40 CFR 122.42(a)(1);
    - iii. The alteration or addition results in a significant change in the permittee’s sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan;
    - iv. Any facility expansions, production increases, or process modifications which will result in a new or substantially different discharge or sludge characteristics must be reported to the Department 60 days before the facility or process modification begins. Notification may be accomplished by application for a new permit. If the discharge does not violate effluent limitations specified in the permit, the facility is to submit a notice to the Department of the changed discharge at least 30 days before such changes. The Department may require a construction permit and/or permit modification as a result of the proposed changes at the facility.
2. **Non-compliance Reporting.**
  - a. The permittee shall report any noncompliance which may endanger health or the environment. Relevant information shall be provided orally or via the current electronic method approved by the Department, within 24 hours from the time the permittee becomes aware of the circumstances, and shall be reported to the appropriate Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. A written submission shall also be provided within five (5) business days of the time the permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.



STANDARD CONDITIONS FOR NPDES PERMITS  
ISSUED BY  
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES  
MISSOURI CLEAN WATER COMMISSION  
REVISED  
AUGUST 1, 2014

- b. The following shall be included as information which must be reported within 24 hours under this paragraph.
    - i. Any unanticipated bypass which exceeds any effluent limitation in the permit.
    - ii. Any upset which exceeds any effluent limitation in the permit.
    - iii. Violation of a maximum daily discharge limitation for any of the pollutants listed by the Department in the permit required to be reported within 24 hours.
  - c. The Department may waive the written report on a case-by-case basis for reports under paragraph 2. b. of this section if the oral report has been received within 24 hours.
3. **Anticipated Noncompliance.** The permittee shall give advance notice to the Department of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements. The notice shall be submitted to the Department 60 days prior to such changes or activity.
  4. **Compliance Schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date. The report shall provide an explanation for the instance of noncompliance and a proposed schedule or anticipated date, for achieving compliance with the compliance schedule requirement.
  5. **Other Noncompliance.** The permittee shall report all instances of noncompliance not reported under paragraphs 2, 3, and 6 of this section, at the time monitoring reports are submitted. The reports shall contain the information listed in paragraph 2. a. of this section.
  6. **Other Information.** Where the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Department, it shall promptly submit such facts or information.
  7. **Discharge Monitoring Reports.**
    - a. Monitoring results shall be reported at the intervals specified in the permit.
    - b. Monitoring results must be reported to the Department via the current method approved by the Department, unless the permittee has been granted a waiver from using the method. If the permittee has been granted a waiver, the permittee must use forms provided by the Department.
    - c. Monitoring results shall be reported to the Department no later than the 28<sup>th</sup> day of the month following the end of the reporting period.
- b. Notice.
    - i. Anticipated bypass. If the permittee knows in advance of the need for a bypass, it shall submit prior notice, if possible at least 10 days before the date of the bypass.
    - ii. Unanticipated bypass. The permittee shall submit notice of an unanticipated bypass as required in Section B – Reporting Requirements, paragraph 5 (24-hour notice).
  - c. Prohibition of bypass.
    - i. Bypass is prohibited, and the Department may take enforcement action against a permittee for bypass, unless:
      1. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
      2. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and
      3. The permittee submitted notices as required under paragraph 2. b. of this section.
    - ii. The Department may approve an anticipated bypass, after considering its adverse effects, if the Department determines that it will meet the three (3) conditions listed above in paragraph 2. c. i. of this section.
3. **Upset Requirements.**
    - a. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of paragraph 3. b. of this section are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.
    - b. Conditions necessary for a demonstration of upset. A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
      - i. An upset occurred and that the permittee can identify the cause(s) of the upset;
      - ii. The permitted facility was at the time being properly operated; and
      - iii. The permittee submitted notice of the upset as required in Section B – Reporting Requirements, paragraph 2. b. ii. (24-hour notice).
      - iv. The permittee complied with any remedial measures required under Section D – Administrative Requirements, paragraph 4.
    - c. Burden of proof. In any enforcement proceeding, the permittee seeking to establish the occurrence of an upset has the burden of proof.

## Section C – Bypass/Upset Requirements

1. **Definitions.**
  - a. *Bypass*: the intentional diversion of waste streams from any portion of a treatment facility, except in the case of blending.
  - b. *Severe Property Damage*: substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
  - c. *Upset*: an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
2. **Bypass Requirements.**
  - a. Bypass not exceeding limitations. The permittee may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of paragraphs 2. b. and 2. c. of this section.

## Section D – Administrative Requirements

1. **Duty to Comply.** The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Missouri Clean Water Law and Federal Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.
  - a. The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
  - b. The Federal Clean Water Act provides that any person who violates section 301, 302, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any such sections in a permit issued under section 402, or any requirement imposed in a pretreatment program approved under sections 402(a)(3) or 402(b)(8) of the Act, is subject to a civil penalty not to exceed \$25,000 per day for each violation. The Federal Clean Water Act provides that any person who negligently violates sections 301, 302, 306, 307, 308, 318, or 405 of the Act, or any condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, or any requirement



STANDARD CONDITIONS FOR NPDES PERMITS  
ISSUED BY  
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES  
MISSOURI CLEAN WATER COMMISSION  
REVISED  
AUGUST 1, 2014

- imposed in a pretreatment program approved under section 402(a)(3) or 402(b)(8) of the Act, is subject to criminal penalties of \$2,500 to \$25,000 per day of violation, or imprisonment of not more than one (1) year, or both. In the case of a second or subsequent conviction for a negligent violation, a person shall be subject to criminal penalties of not more than \$50,000 per day of violation, or by imprisonment of not more than two (2) years, or both. Any person who knowingly violates such sections, or such conditions or limitations is subject to criminal penalties of \$5,000 to \$50,000 per day of violation, or imprisonment for not more than three (3) years, or both. In the case of a second or subsequent conviction for a knowing violation, a person shall be subject to criminal penalties of not more than \$100,000 per day of violation, or imprisonment of not more than six (6) years, or both. Any person who knowingly violates section 301, 302, 303, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, and who knows at that time that he thereby places another person in imminent danger of death or serious bodily injury, shall, upon conviction, be subject to a fine of not more than \$250,000 or imprisonment of not more than 15 years, or both. In the case of a second or subsequent conviction for a knowing endangerment violation, a person shall be subject to a fine of not more than \$500,000 or by imprisonment of not more than 30 years, or both. An organization, as defined in section 309(c)(3)(B)(iii) of the CWA, shall, upon conviction of violating the imminent danger provision, be subject to a fine of not more than \$1,000,000 and can be fined up to \$2,000,000 for second or subsequent convictions.
- c. Any person may be assessed an administrative penalty by the EPA Director for violating section 301, 302, 306, 307, 308, 318 or 405 of this Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of this Act. Administrative penalties for Class I violations are not to exceed \$10,000 per violation, with the maximum amount of any Class I penalty assessed not to exceed \$25,000. Penalties for Class II violations are not to exceed \$10,000 per day for each day during which the violation continues, with the maximum amount of any Class II penalty not to exceed \$125,000.
- d. It is unlawful for any person to cause or permit any discharge of water contaminants from any water contaminant or point source located in Missouri in violation of sections 644.006 to 644.141 of the Missouri Clean Water Law, or any standard, rule or regulation promulgated by the commission. In the event the commission or the director determines that any provision of sections 644.006 to 644.141 of the Missouri Clean Water Law or standard, rules, limitations or regulations promulgated pursuant thereto, or permits issued by, or any final abatement order, other order, or determination made by the commission or the director, or any filing requirement pursuant to sections 644.006 to 644.141 of the Missouri Clean Water Law or any other provision which this state is required to enforce pursuant to any federal water pollution control act, is being, was, or is in imminent danger of being violated, the commission or director may cause to have instituted a civil action in any court of competent jurisdiction for the injunctive relief to prevent any such violation or further violation or for the assessment of a penalty not to exceed \$10,000 per day for each day, or part thereof, the violation occurred and continues to occur, or both, as the court deems proper. Any person who willfully or negligently commits any violation in this paragraph shall, upon conviction, be punished by a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than one year, or both. Second and successive convictions for violation of the same provision of this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.
2. **Duty to Reapply.**
- a. If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and obtain a new permit.
- b. A permittee with a currently effective site-specific permit shall submit an application for renewal at least 180 days before the expiration date of the existing permit, unless permission for a later date has been granted by the Department. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
- c. A permittees with currently effective general permit shall submit an application for renewal at least 30 days before the existing permit expires, unless the permittee has been notified by the Department that an earlier application must be made. The Department may grant permission for a later submission date. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
3. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.
4. **Duty to Mitigate.** The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.
5. **Proper Operation and Maintenance.** The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems which are installed by a permittee only when the operation is necessary to achieve compliance with the conditions of the permit.
6. **Permit Actions.**
- a. Subject to compliance with statutory requirements of the Law and Regulations and applicable Court Order, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:
- i. Violations of any terms or conditions of this permit or the law;
- ii. Having obtained this permit by misrepresentation or failure to disclose fully any relevant facts;
- iii. A change in any circumstances or conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge; or
- iv. Any reason set forth in the Law or Regulations.
- b. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.
7. **Permit Transfer.**
- a. Subject to 10 CSR 20-6.010, an operating permit may be transferred upon submission to the Department of an application to transfer signed by the existing owner and the new owner, unless prohibited by the terms of the permit. Until such time the permit is officially transferred, the original permittee remains responsible for complying with the terms and conditions of the existing permit.
- b. The Department may require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the Missouri Clean Water Law or the Federal Clean Water Act.
- c. The Department, within 30 days of receipt of the application, shall notify the new permittee of its intent to revoke or reissue or transfer the permit.
8. **Toxic Pollutants.** The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the Federal Clean Water Act within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
9. **Property Rights.** This permit does not convey any property rights of any sort, or any exclusive privilege.



STANDARD CONDITIONS FOR NPDES PERMITS  
ISSUED BY  
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES  
MISSOURI CLEAN WATER COMMISSION  
REVISED  
AUGUST 1, 2014

10. **Duty to Provide Information.** The permittee shall furnish to the Department, within a reasonable time, any information which the Department may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The permittee shall also furnish to the Department upon request, copies of records required to be kept by this permit.
11. **Inspection and Entry.** The permittee shall allow the Department, or an authorized representative (including an authorized contractor acting as a representative of the Department), upon presentation of credentials and other documents as may be required by law, to:
  - a. Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of the permit;
  - b. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
  - c. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
  - d. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Federal Clean Water Act or Missouri Clean Water Law, any substances or parameters at any location.
12. **Closure of Treatment Facilities.**
  - a. Persons who cease operation or plan to cease operation of waste, wastewater, and sludge handling and treatment facilities shall close the facilities in accordance with a closure plan approved by the Department.
  - b. Operating Permits under 10 CSR 20-6.010 or under 10 CSR 20-6.015 are required until all waste, wastewater, and sludges have been disposed of in accordance with the closure plan approved by the Department and any disturbed areas have been properly stabilized. Disturbed areas will be considered stabilized when perennial vegetation, pavement, or structures using permanent materials cover all areas that have been disturbed. Vegetative cover, if used, shall be at least 70% plant density over 100% of the disturbed area.
13. **Signatory Requirement.**
  - a. All permit applications, reports required by the permit, or information requested by the Department shall be signed and certified. (See 40 CFR 122.22 and 10 CSR 20-6.010)
  - b. The Federal Clean Water Act provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or non-compliance shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than six (6) months per violation, or by both.
  - c. The Missouri Clean Water Law provides that any person who knowingly makes any false statement, representation or certification in any application, record, report, plan, or other document filed or required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than ten thousand dollars, or by imprisonment for not more than six months, or by both.
14. **Severability.** The provisions of the permit are severable, and if any provision of the permit, or the application of any provision of the permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of the permit, shall not be affected thereby.



STANDARD CONDITIONS FOR NPDES PERMITS  
ISSUED BY  
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES  
MISSOURI CLEAN WATER COMMISSION  
REVISED  
MAY 1, 2013

PART II - SPECIAL CONDITIONS – PUBLICLY OWNED  
TREATMENT WORKS  
SECTION A – INDUSTRIAL USERS

**1. Definitions**

Definitions as set forth in the Missouri Clean Water Laws and approved by the Missouri Clean Water Commission shall apply to terms used herein.

Significant Industrial User (SIU). Except as provided in the *General Pretreatment Regulation* 10 CSR 20-6.100, the term Significant Industrial User means:

1. All Industrial Users subject to Categorical Pretreatment Standards; and
2. Any other Industrial User that: discharges an average of 25,000 gallons per day or more of process wastewater to the Publicly-Owned Treatment Works (POTW) (excluding sanitary, noncontact cooling and boiler blowdown wastewater); contributes a process wastestream which makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the POTW treatment plant; or is designated as such by the Control Authority on the basis that the Industrial User has a reasonable potential for adversely affecting the POTW's or for violating any Pretreatment Standard or requirement.

Clean Water Act (CWA) is the the federal Clean Water Act of 1972, 33 U.S.C. § 1251 et seq. (2002).

**2. Identification of Industrial Discharges**

Pursuant to 40 CFR 122.44(j)(1), all POTWs shall identify, in terms of character and volume of pollutants, any Significant Industrial Users discharging to the POTW subject to Pretreatment Standards under section 307(b) of the CWA and 40 CFR 403.

**3. Application Information**

Applications for renewal or modification of this permit must contain the information about industrial discharges to the POTW pursuant to 40 CFR 122.21(j)(6)

**4. Notice to the Department**

Pursuant to 40 CFR 122.42(b), all POTWs must provide adequate notice of the following:

1. Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to section 301 or 306 of CWA if it were directly discharging these pollutants; and
2. Any substantial change into the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit.
3. For purposes of this paragraph, adequate notice shall include information on:
  - i. the quality and quantity of effluent introduced into the POTW, and
  - ii. any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

For POTWs without an approved pretreatment program, the notice of industrial discharges which was not included in the permit application shall be made as soon as practicable. For POTWs with an approved pretreatment program, notice is to be included in the annual pretreatment report required in the special conditions of this permit. Notice may be sent to:

Missouri Department of Natural Resources  
Water Protection Program  
Attn: Pretreatment Coordinator  
P.O. Box 176  
Jefferson City, MO 65102

**STANDARD CONDITIONS FOR NPDES PERMITS**  
**ISSUED BY**  
**THE MISSOURI DEPARTMENT OF NATURAL RESOURCES**  
**MISSOURI CLEAN WATER COMMISSION**  
**March 1, 2014**

**PART III – SLUDGE AND BIOSOLIDS FROM DOMESTIC AND  
INDUSTRIAL WASTEWATER TREATMENT FACILITIES**

**SECTION A – GENERAL REQUIREMENTS**

1. This permit pertains to sludge requirements under the Missouri Clean Water Law and regulation for domestic wastewater and industrial process wastewater. This permit also incorporates applicable federal sludge disposal requirements under 40 CFR 503 for domestic wastewater. The Environmental Protection Agency (EPA) has principal authority for permitting and enforcement of the federal sludge regulations under 40 CFR 503 for domestic wastewater. EPA has reviewed and accepted these standard sludge conditions. EPA may choose to issue a separate sludge addendum to this permit or a separate federal sludge permit at their discretion to further address the federal requirements.
2. These Part III Standard Conditions apply only to sludge and biosolids generated at domestic wastewater treatment facilities, including public owned treatment works (POTW), privately owned facilities and sludge or biosolids generated at industrial facilities.
3. Sludge and Biosolids Use and Disposal Practices:
  - a. The permittee is authorized to operate the sludge and biosolids treatment, storage, use, and disposal facilities listed in the facility description of this permit.
  - b. The permittee shall not exceed the design sludge volume listed in the facility description and shall not use sludge disposal methods that are not listed in the facility description, without prior approval of the permitting authority.
  - c. The permittee is authorized to operate the storage, treatment or generating sites listed in the Facility Description section of this permit.
4. Sludge Received from other Facilities:
  - a. Permittees may accept domestic wastewater sludge from other facilities including septic tank pumpings from residential sources as long as the design sludge volume is not exceeded and the treatment facility performance is not impaired.
  - b. The permittee shall obtain a signed statement from the sludge generator or hauler that certifies the type and source of the sludge
5. These permit requirements do not supersede nor remove liability for compliance with county and other local ordinances.
6. These permit requirements do not supersede nor remove liability for compliance with other environmental regulations such as odor emissions under the Missouri Air Pollution Control Law and regulations.
7. This permit may (after due process) be modified, or alternatively revoked and reissued, to comply with any applicable sludge disposal standard or limitation issued or approved under Section 405(d) of the Clean Water Act under Chapter 644 RSMo.
8. In addition to STANDARD CONDITIONS, the Department may include sludge limitations in the special conditions portion or other sections of a site specific permit.
9. Alternate Limits in the Site Specific Permit.

Where deemed appropriate, the Department may require an individual site specific permit in order to authorize alternate limitations:

  - a. A site specific permit must be obtained for each operating location, including application sites.
  - b. To request a site specific permit, an individual permit application, permit fee, and supporting documents shall be submitted for each operating location. This shall include a detailed sludge/biosolids management plan or engineering report.
10. Exceptions to these Standard Conditions may be authorized on a case-by-case basis by the Department, as follows:
  - a. The Department will prepare a permit modification and follow permit notice provisions as applicable under 10 CSR 20-6.020, 40 CFR 124.10, and 40 CFR 501.15(a)(2)(ix)(E). This includes notification of the owner of the property located adjacent to each land application site, where appropriate.
  - b. Exceptions cannot be granted where prohibited by the federal sludge regulations under 40 CFR 503.

## **SECTION B – DEFINITIONS**

1. Best Management Practices include agronomic loading rates, soil conservation practices and other site restrictions.
2. Biosolids means organic fertilizer or soil amendment produced by the treatment of domestic wastewater sludge.
3. Biosolids land application facility is a facility where biosolids are spread onto the land at agronomic rates for production of food or fiber. The facility includes any structures necessary to store the biosolids until soil, weather, and crop conditions are favorable for land application.
4. Class A biosolids means a material that has met the Class A pathogen reduction requirements or equivalent treatment by a Process to Further Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
5. Class B biosolids means a material that has met the Class B pathogen reduction requirements or equivalent treatment by a Process to Significantly Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
6. Domestic wastewater means wastewater originating from the sanitary conveniences of residences, commercial buildings, factories and institutions; or co-mingled sanitary and industrial wastewater processed by a (POTW) or a privately owned facility.
7. Industrial wastewater means any wastewater, also known as process water, not defined as domestic wastewater. Per 40 CFR Part 122, process water means any water which, during manufacturing or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct, or waste product.
8. Mechanical treatment plants are wastewater treatment facilities that use mechanical devices to treat wastewater, including septic tanks, sand filters, extended aeration, activated sludge, contact stabilization, trickling filters, rotating biological discs, and other similar facilities. It does not include wastewater treatment lagoons and constructed wetlands for wastewater treatment.
9. Operating location as defined in 10 CSR 20-2.010 is all contiguous lands owned, operated or controlled by one (1) person or by two (2) or more persons jointly or as tenants in common.
10. Plant Available Nitrogen (PAN) is the nitrogen that will be available to plants during the growing seasons after biosolids application.
11. Public contact site is land with a high potential for contact by the public. This includes, but is not limited to, public parks, ball fields, cemeteries, plant nurseries, turf farms, and golf courses.
12. Sludge is the solid, semisolid, or liquid residue removed during the treatment of wastewater. Sludge includes septage removed from septic tanks or equivalent facilities. Sludge does not include carbon coal byproducts (CCBs)
13. Sludge lagoon is part of a mechanical wastewater treatment facility. A sludge lagoon is an earthen basin that receives sludge that has been removed from a wastewater treatment facility. It does not include a wastewater treatment lagoon or sludge treatment units that are not a part of a mechanical wastewater treatment facility.
14. Septage is the material pumped from residential septic tanks and similar treatment works (with a design population of less than 150 people). The standard for biosolids from septage is different from other sludges.

## **SECTION C – MECHANICAL WASTEWATER TREATMENT FACILITIES**

1. Sludge shall be routinely removed from wastewater treatment facilities and handled according to the permit facility description and sludge conditions of this permit.
2. The permittee shall operate the facility so that there is no sludge discharged to waters of the state.
3. Mechanical treatment plants shall have separate sludge storage compartments in accordance with 10 CSR 20, Chapter 8. Failure to remove sludge from these storage compartments on the required design schedule is a violation of this permit.

## **SECTION D – SLUDGE DISPOSED AT OTHER TREATMENT FACILITY OR CONTRACT HAULER**

1. This section applies to permittees that haul sludge to another treatment facility for disposal or use contract haulers to remove and dispose of sludge.
2. Permittees that use contract haulers are responsible for compliance with all the terms of this permit including final disposal, unless the hauler has a separate permit for sludge or biosolids disposal issued by the Department; or the hauler transports the sludge to another permitted treatment facility.
3. Haulers who land apply septage must obtain a state permit.
4. Testing of sludge, other than total solids content, is not required if sludge is hauled to a municipal wastewater treatment facility or other permitted wastewater treatment facility, unless it is required by the accepting facility.

## **SECTION E – INCINERATION OF SLUDGE**

1. Sludge incineration facilities shall comply with the requirements of 40 CFR 503 Subpart E; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
2. Permittee may be authorized under the facility description of this permit to store incineration ash in lagoons or ash ponds. This permit does not authorize the disposal of incineration ash. Incineration ash shall be disposed in accordance with 10 CSR 80; or if the ash is determined to be hazardous with 10 CSR 25.
3. In addition to normal sludge monitoring, incineration facilities shall report the following as part of the annual report, quantity of sludge incinerated, quantity of ash generated, quantity of ash stored, and ash used or disposal method, quantity, and location. Permittee shall also provide the name of the disposal facility and the applicable permit number.

## **SECTION F – SURFACE DISPOSAL SITES AND SLUDGE LAGOONS**

1. Surface disposal sites of domestic facilities shall comply with the requirements in 40 CFR 503 Subpart C; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
2. Sludge storage lagoons are temporary facilities and are not required to obtain a permit as a solid waste management facility under 10 CSR 80. In order to maintain sludge storage lagoons as storage facilities, accumulated sludge must be removed routinely, but not less than once every two years unless an alternate schedule is approved in the permit. The amount of sludge removed will be dependent on sludge generation and accumulation in the facility. Enough sludge must be removed to maintain adequate storage capacity in the facility.
  - a. In order to avoid damage to the lagoon seal during cleaning, the permittee may leave a layer of sludge on the bottom of the lagoon, upon prior approval of the Department; or
  - b. Permittee shall close the lagoon in accordance with Section H.

## **SECTION G – LAND APPLICATION**

1. The permittee shall not land apply sludge or biosolids unless land application is authorized in the facility description or the special conditions of the issued NPDES permit.
2. Land application sites within a 20 miles radius of the wastewater treatment facility are authorized under this permit when biosolids are applied for beneficial use in accordance with these standard conditions unless otherwise specified in a site specific permit. If the permittee's land application site is greater than a 20 mile radius of the wastewater treatment facility, approval must be granted from the Department.
3. Land application shall not adversely affect a threatened or endangered species or its designated critical habitat.
4. Biosolids shall not be applied unless authorized in this permit or exempted under 10 CSR 20, Chapter 6.
  - a. This permit does not authorize the land application of domestic sludge except for when sludge meets the definition of biosolids.
  - b. This permit authorizes "Class A or B" biosolids derived from domestic wastewater and/or process water sludge to be land applied onto grass land, crop land, timber or other similar agricultural or silviculture lands at rates suitable for beneficial use as organic fertilizer and soil conditioner.
5. Public Contact Sites:

Permittees who wish to apply Class A biosolids to public contact sites must obtain approval from the Department after two years of proper operation with acceptable testing documentation that shows the biosolids meet Class A criteria. A shorter length of testing will be allowed with prior approval from the Department. Authorization for land applications must be provided in the special conditions section of this permit or in a separate site specific permit.

  - a. After Class B biosolids have been land applied, public access must be restricted for 12 months.
  - b. Class B biosolids are only land applied to root crops, home gardens or vegetable crops whose edible parts will not be for human consumption.

6. Agricultural and Silvicultural Sites:

Septage – Based on Water Quality guide 422(WQ422) published by the University of Missouri

- a. Haulers that land apply septage must obtain a state permit
- b. Do not apply more than 30,000 gallons of septage per acre per year.
- c. Septage tanks are designed to retain sludge for one to three years which will allow for a larger reduction in pathogens and vectors, as compared to other mechanical type treatment facilities.
- d. To meet Class B sludge requirements, maintain septage at 12 pH for at least thirty (30) minutes before land application. 50 pounds of hydrated lime shall be added to each 1,000 gallons of septage in order to meet pathogen and vector stabilization for septage biosolids applied to crops, pastures or timberland.
- e. Lime is to be added to the pump truck and not directly to the septic tanks, as lime would harm the beneficial bacteria of the septic tank.

Biosolids - Based on Water Quality guide 423, 424, and 425 (WQ423, WQ424, WQ425) published by the University of Missouri;

- a. Biosolids shall be monitored to determine the quality for regulated pollutants
- b. The number of samples taken is directly related to the amount of sludge produced by the facility (See Section I of these Standard Conditions). Report as dry weight unless otherwise specified in the site specific permit. Samples should be taken only during land application periods. When necessary, it is permissible to mix biosolids with lower concentrations of biosolids as well as other suitable Department approved material to reach the maximum concentration of pollutants allowed.
- c. Table 1 gives the maximum concentration allowable to protect water quality standards

**TABLE 1**

Biosolids Ceiling Concentration <sup>1</sup>	
Pollutant	Milligrams per kilogram dry weight
Arsenic	75
Cadmium	85
Copper	4,300
Lead	840
Mercury	57
Molybdenum	75
Nickel	420
Selenium	100
Zinc	7,500

<sup>1</sup> Land application is not allowed if the sludge concentration exceeds the maximum limits for any of these pollutants

- d. The low metal concentration biosolids has reduced requirements because of its higher quality and can safely be applied for 100 years or longer at typical agronomic loading rates. (See Table 2)

**TABLE 2**

Biosolids Low Metal Concentration <sup>1</sup>	
Pollutant	Milligrams per kilogram dry weight
Arsenic	41
Cadmium	39
Copper	1,500
Lead	300
Mercury	17
Nickel	420
Selenium	36
Zinc	2,800

<sup>1</sup> You may apply low metal biosolids without tracking cumulative metal limits, provided the cumulative application of biosolids does not exceed 500 dry tons per acre.

- e. Each pollutant in Table 3 has an annual and a total cumulative loading limit, based on the allowable pounds per acre for various soil categories.

**TABLE 3**

Pollutant	CEC 15+		CEC 5 to 15		CEC 0 to 5	
	Annual	Total <sup>1</sup>	Annual	Total <sup>1</sup>	Annual	Total <sup>1</sup>
Arsenic	1.8	36.0	1.8	36.0	1.8	36.0
Cadmium	1.7	35.0	0.9	9.0	0.4	4.5
Copper	66.0	1,335.0	25.0	250.0	12.0	125.0
Lead	13.0	267.0	13.0	267.0	13.0	133.0
Mercury	0.7	15.0	0.7	15.0	0.7	15.0
Nickel	19.0	347.0	19.0	250.0	12.0	125.0
Selenium	4.5	89.0	4.5	44.0	1.6	16.0
Zinc	124.0	2,492.0	50.0	500.0	25.0	250.0

<sup>1</sup> Total cumulative loading limits for soils with equal or greater than 6.0 pH (salt based test) or 6.5 pH (water based test)

**TABLE 4 - Guidelines for land application of other trace substances <sup>1</sup>**

Cumulative Loading	
Pollutant	Pounds per acre
Aluminum	4,000 <sup>2</sup>
Beryllium	100
Cobalt	50
Fluoride	800
Manganese	500
Silver	200
Tin	1,000
Dioxin	(10 ppt in soil) <sup>3</sup>
Other	<sup>4</sup>

<sup>1</sup> Design of land treatment systems for Industrial Waste, 1979. Michael Ray Overcash, North Carolina State University and Land Treatment of Municipal Wastewater, EPA 1981.)

<sup>2</sup> This applies for a soil with a pH between 6.0 and 7.0 (salt based test) or a pH between 6.5 to 7.5 (water based test). Case-by-case review is required for higher pH soils.

<sup>3</sup> Total Dioxin Toxicity Equivalents (TEQ) in soils, based on a risk assessment under 40 CFR 744, May 1998.

<sup>4</sup> Case by case review. Concentrations in sludge should not exceed the 95<sup>th</sup> percentile of the National Sewage Sludge Survey, EPA, January 2009.

Best Management Practices – Based on Water Quality guide 426 (WQ426) published by the University of Missouri

- a. Use best management practices when applying biosolids.
- b. Biosolids cannot discharge from the land application site
- c. Biosolid application is subject to the Missouri Department of Agriculture State Milk Board concerning grazing restrictions of lactating dairy cattle.
- d. Biosolid application must be in accordance with section 4 of the Endangered Species Act.
- e. Do not apply more than the agronomic rate of nitrogen needed.
- f. The applicator must document the Plant Available Nitrogen (PAN) loadings, available nitrogen in the soil and crop removals unless the nitrogen content of the biosolids does not exceed 50,000 milligrams per kilogram of total nitrogen on a dry weight basis and biosolids application rate is less than two dry tons per acre per year.
  - i. PAN can be determined as follows and is in accordance with WQ426  
 $(\text{Nitrate} + \text{nitrite nitrogen}) + (\text{organic nitrogen} \times 0.2) + (\text{ammonia nitrogen} \times \text{volatilization factor}^1)$ .
 

<sup>1</sup> Volatilization factor is 0.7 for surface application and 1 for subsurface application.

- g. Buffer zones are as follows:
  - i. 300 feet of a water supply well, sinkhole, lake, pond, water supply reservoir or water supply intake in a stream;
  - ii. 300 feet of a losing stream, no discharge stream, stream stretches designated for whole body contact recreation, wild and scenic rivers, Ozark National Scenic Riverways or outstanding state resource waters as listed in the Water Quality Standards, 10 CSR 20-7.031;
  - iii. 150 feet if dwellings;
  - iv. 100 feet of wetlands or permanent flowing streams;
  - v. 50 feet of a property line or other waters of the state, including intermittent flowing streams.
- h. Slope limitation for application sites are as follows:
  - i. A slope 0 to 6 percent has no rate limitation
  - ii. Applied to a slope 7 to 12 percent, the applicator may apply biosolids when soil conservation practices are used to meet the minimum erosion levels
  - iii. Slopes > 12, apply biosolids only when grass is vegetated and maintained with at least 80 percent ground cover at a rate of two dry tons per acre per year or less.
- i. No biosolids may be land applied in an area that it is reasonably certain that pollutants will be transported into waters of the state.
- j. Do not apply biosolids to sites with soil that is snow covered, frozen or saturated with liquid without prior approval by the Department.
- k. Biosolids / sludge applicators must keep detailed records up to five years.

## SECTION H – CLOSURE REQUIREMENTS

1. This section applies to all wastewater facilities (mechanical, industrial, and lagoons) and sludge or biosolids storage and treatment facilities and incineration ash ponds. It does not apply to land application sites.
2. Permittees of a domestic wastewater facility who plan to cease operation must obtain Department approval of a closure plan which addresses proper removal and disposal of all residues, including sludge, biosolids. Mechanical plants, sludge lagoons, ash ponds and other storage structures must obtain approval of a closure plan from the Department. Permittee must maintain this permit until the facility is closed in accordance with the approved closure plan per 10 CSR 20 – 6. 010 and 10 CSR 20 – 6.015.
3. Residuals that are left in place during closure of a lagoon or earthen structure or ash pond shall not exceed the agricultural loading rates as follows:
  - a. Residuals shall meet the monitoring and land application limits for agricultural rates as referenced in Section H of these standard conditions.
  - b. If a wastewater treatment lagoon has been in operation for 15 years or more without sludge removal, the sludge in the lagoon qualifies as a Class B biosolids with respect to pathogens due to anaerobic digestion, and testing for fecal coliform is not required. For other lagoons, testing for fecal coliform is required to show compliance with Class B biosolids limitations. In order to reach Class B biosolids requirements, fecal coliform must be less than 2,000,000 colony forming units or 2,000,000 most probable number. All fecal samples must be presented as geometric mean per gram.
  - c. The allowable nitrogen loading that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. For a grass cover crop, the allowable PAN is 300 pounds/acre.
    - i. PAN can be determined as follows:  

$$(\text{Nitrate} + \text{nitrite nitrogen}) + (\text{organic nitrogen} \times 0.2) + (\text{ammonia nitrogen} \times \text{volatilization factor}^1).$$

<sup>1</sup> Volatilization factor is 0.7 for surface application and 1 for subsurface application.
4. When closing a domestic wastewater treatment lagoon with a design treatment capacity equal or less than 150 persons, the residuals are considered “septage” under the similar treatment works definition. See Section B of these standard conditions. Under the septage category, residuals may be left in place as follows:
  - a. Testing for metals or fecal coliform is not required
  - b. If the wastewater treatment lagoon has been in use for less than 15 years, mix lime with the sludge at a rate of 50 pounds of hydrated lime per 1000 gallons (134 cubic feet) of sludge.
  - c. The amount of sludge that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. 100 dry tons/acre of sludge may be left in the basin without testing for nitrogen. If 100 dry tons/acre or more will be left in the lagoon, test for nitrogen and determine the PAN using the calculation above. Allowable PAN loading is 300 pounds/acre.

5. Residuals left within the domestic lagoon shall be mixed with soil on at least a 1 to 1 ratio, the lagoon berm shall be demolished, and the site shall be graded and contain  $\geq 70\%$  vegetative density over 100% of the site so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
6. Lagoons and/or earthen structure and/or ash pond closure activities shall obtain a storm water permit for land disturbance activities that equal or exceed one acre in accordance with 10 CSR 20-6.200
7. When closing a mechanical wastewater and/or industrial process wastewater plant; all sludge must be cleaned out and disposed of in accordance with the Department approved closure plan before the permit for the facility can be terminated.
  - a. Land must be stabilized which includes any grading, alternate use or fate upon approval by the Department, remediation, or other work that exposes sediment to stormwater per 10 CSR 20-6.200. The site shall be graded and contain  $\geq 70\%$  vegetative density over 100% of the site, so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
  - b. Per 10 CSR 20-6.015(4)(B)6, Hazardous Waste shall not be land applied or disposed during industrial and mechanical plant closures unless in accordance with Missouri Hazardous Waste Management Law and Regulations under 10 CSR 25.
  - c. After demolition of the mechanical plant / industrial plant, the site must only contain clean fill defined in RSMo 260.200 (5) as uncontaminated soil, rock, sand, gravel, concrete, asphaltic concrete, cinderblocks, brick, minimal amounts of wood and metal, and inert solids as approved by rule or policy of the Department for fill or other beneficial use. Other solid wastes must be removed.
8. If sludge from the domestic lagoon or mechanical treatment plant exceeds agricultural rates under Section G and/or H, a landfill permit or solid waste disposal permit must be obtained if the permittee chooses to seek authorization for on-site sludge disposal under the Missouri Solid Waste Management Law and regulations per 10 CSR 80, and the permittee must comply with the surface disposal requirements under 40 CFR 503, Subpart C.

**SECTION I – MONITORING FREQUENCY**

1. At a minimum, sludge or biosolids shall be tested for volume and percent total solids on a frequency that will accurately represent sludge quantities produced and disposed. Please see the table below.

**TABLE 5**

Design Sludge Production (dry tons per year)	Monitoring Frequency (See Notes 1 and 2)			
	Metals, Pathogens and Vectors	Nitrogen TKN <sup>1</sup>	Nitrogen PAN <sup>2</sup>	Priority Pollutants and TCLP <sup>3</sup>
0 to 100	1 per year	1 per year	1 per month	1 per year
101 to 200	biannual	biannual	1 per month	1 per year
201 to 1,000	quarterly	quarterly	1 per month	1 per year
1,001 to 10,000	1 per month	1 per month	1 per week	-- <sup>4</sup>
10,001 +	1 per week	1 per week	1 per day	-- <sup>4</sup>

<sup>1</sup> Test total Kjeldahl nitrogen, if biosolids application is 2 dry tons per acre per year or less

<sup>2</sup> Calculate plant available nitrogen, if biosolids application is more than 2 dry tons per acre per year.

<sup>3</sup> Priority pollutants (40 CFR 122.21, Appendix D, Tables II and III) and toxicity characteristic leaching procedure (40 CFR 261.24) is required only for permit holders that must have a pre-treatment program.

<sup>4</sup> One sample for each 1,000 dry tons of sludge.

Note 1: Total solids: A grab sample of sludge shall be tested one per day during land application periods for percent total solids. This data shall be used to calculate the dry tons of sludge applied per acre.

Note 2: Total Phosphorus: Total phosphorus and total potassium shall be tested at the same monitoring frequency as metals.

2. If you own a wastewater treatment lagoon or sludge lagoon that is cleaned out once a year or less, you may choose to sample only when the sludge is removed or the lagoon is closed. Test one composite sample for each 100 dry tons of sludge or biosolids removed from the lagoon during the year within the lagoon at closing. Composite sample must represent various areas at one-foot depth.
3. Additional testing may be required in the special conditions or other sections of the permit. Permittees receiving industrial wastewater may be required to conduct additional testing upon request from the Department.
4. At this time, the Department recommends monitoring requirements shall be performed in accordance with, "POTW Sludge Sampling and Analysis Guidance Document," United States Environmental Protection Agency, August 1989, and the subsequent revisions.

**SECTION J – RECORD KEEPING AND REPORTING REQUIREMENTS**

1. The permittee shall maintain records on file at the facility for at least five years for the items listed in these standard conditions and any additional items in the Special Conditions section of this permit. This shall include dates when the sludge facility is checked for proper operation, records of maintenance and repairs and other relevant information.
2. Reporting period
  - a. By January 28<sup>th</sup> of each year, an annual report shall be submitted for the previous calendar year period for all mechanical wastewater treatment facilities, sludge lagoons, and sludge or biosolids disposal facilities.
  - b. Permittees with wastewater treatment lagoons shall submit the above annual report only when sludge or biosolids are removed from the lagoon during the report period or when the lagoon is closed.
3. Report Forms. The annual report shall be submitted on report forms provided by the Department or equivalent forms approved by the Department.
4. Reports shall be submitted as follows:

Major facilities (those serving 10,000 persons or 1 million gallons per day) shall report to both the Department and EPA. Other facilities need to report only to the Department. Reports shall be submitted to the addresses listed as follows:

DNR regional office listed in your permit  
(see cover letter of permit)  
ATTN: Sludge Coordinator

EPA Region VII  
Water Compliance Branch (WACM)  
Sludge Coordinator  
11201 Renner Blvd.  
Lenexa, KS 66219


5. Annual Report Contents. The annual report shall include the following:
  - a. Sludge and biosolids testing performed. Include a copy or summary of all test results, even if not required by the permit.
  - b. Sludge or biosolids quantity shall be reported as dry tons for quantity generated by the wastewater treatment facility, the quantity stored on site at the end of the year, and the quantity used or disposed.
  - c. Gallons and % solids data used to calculate the dry ton amounts.
  - d. Description of any unusual operating conditions.
  - e. Final disposal method, dates, and location, and person responsible for hauling and disposal.
    - i. This must include the name, address for the hauler and sludge facility. If hauled to a municipal wastewater treatment facility, sanitary landfill, or other approved treatment facility, give the name of that facility.
    - ii. Include a description of the type of hauling equipment used and the capacity in tons, gallons, or cubic feet.

f. Contract Hauler Activities

If contract hauler, provide a copy of a signed contract from the contractor. Permittee shall require the contractor to supply information required under this permit for which the contractor is responsible. The permittee shall submit a signed statement from the contractor that he has complied with the standards contained in this permit, unless the contract hauler has a separate sludge or biosolids use permit.

g. Land Application Sites:

- i. Report the location of each application site, the annual and cumulative dry tons/acre for each site, and the landowners name and address. The location for each spreading site shall be given as a legal description for nearest  $\frac{1}{4}$ ,  $\frac{1}{4}$ , Section, Township, Range, and county, or UTM coordinates. If biosolids application exceeds 2 dry tons/acre/year, reports biosolids nitrogen results, Plant Available Nitrogen (PAN) in pounds/acre, crop nitrogen requirement.
- ii. If the "Low Metals" criteria are exceeded, report the annual and cumulative pollutant loading rates in pounds per acre for each applicable pollutant, and report the percent of cumulative pollutant loading which has been reached at each site.
- iii. Report the method used for compliance with pathogen and vector attraction requirements.
- iv. Report soil test results for pH, CEC, and phosphorus. If none was tested during the year, report the last date when tested and results.


 MISSOURI DEPARTMENT OF NATURAL RESOURCES  
 WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL PROGRAM

**FORM B2 – APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS PER DAY**

FACILITY NAME MSD, Fenton Wastewater Treatment Facility	
PERMIT NO. MO-0086126	COUNTY Saint Louis

**APPLICATION OVERVIEW**

Form B2 has been developed in a modular format and consists of Parts A, B and C and a Supplemental Application Information (Parts D, E, F and G) packet. All applicants must complete Parts A, B and C. Some applicants must also complete parts of the Supplemental Application Information packet. The following items explain which parts of Form B2 you must complete. Submittal of an incomplete application may result in the application being returned.

**BASIC APPLICATION INFORMATION**

- A. Basic Application Information for all Applicants. All applicants must complete Part A.
- B. Additional Application Information for all Applicants. All applicants must complete Part B.
- C. Certification. All applicants must complete Part C.

**SUPPLEMENTAL APPLICATION INFORMATION**


- D. Expanded Effluent Testing Data. A treatment works that discharges effluent to surface water of the United States and meets one or more of the following criteria must complete *Part D - Expanded Effluent Testing Data*:
  1. Has a design flow rate greater than or equal to 1 million gallons per day.
  2. Is required to have or currently has a pretreatment program.
  3. Is otherwise required by the permitting authority to provide the information.
- E. Toxicity Testing Data. A treatment works that meets one or more of the following criteria must complete *Part E - Toxicity Testing Data*:
  1. Has a design flow rate greater than or equal to 1 million gallons per day.
  2. Is required to have or currently has a pretreatment program.
  3. Is otherwise required by the permitting authority to provide the information.
- F. Industrial User Discharges and Resource Conservation and Recovery Act / Comprehensive Environmental Response, Compensation and Liability Act Wastes. A treatment works that accepts process wastewater from any significant industrial users, also known as SIUs, or receives a Resource Conservation and Recovery Act or CERCLA wastes must complete *Part F - Industrial User Discharges and Resource Conservation and Recovery Act /CERCLA Wastes*.  
 SIUs are defined as:
  1. All Categorical Industrial Users, or CIUs, subject to Categorical Pretreatment Standards under 40 Code of Federal Regulations 403.6 and 40 Code of Federal Regulations 403.6 and 40 CFR Chapter 1, Subchapter N.
  2. Any other industrial user that meets one or more of the following:
    - i. Discharges an average of 25,000 gallons per day or more of process wastewater to the treatment works (with certain exclusions).
    - ii. Contributes a process waste stream that makes up five percent or more of the average dry weather hydraulic or organic capacity of the treatment plant.
    - iii. Is designated as an SIU by the control authority.
- G. Combined Sewer Systems. A treatment works that has a combined sewer system must complete *Part G - Combined Sewer Systems*.

**ALL APPLICANTS MUST COMPLETE PARTS A, B and C**

RECEIVED

MAY 30 2012

AP 11810



MISSOURI DEPARTMENT OF NATURAL RESOURCES  
WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH  
**FORM B2 - APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS PER DAY**

FOR AGENCY USE ONLY	
CHECK NUMBER	NO Fee Required
DATE RECEIVED	FEE SUBMITTED
5/30/12	∅

(P)

**PART A - BASIC APPLICATION INFORMATION**

1. This application is for:

- An operating permit and antidegradation review public notice.
- A construction permit following an appropriate operating permit and antidegradation review public notice.
- A construction permit, a concurrent operating permit and antidegradation review public notice.
- A construction permit (submitted before Aug. 30, 2008 or antidegradation review is not required).
- An operating permit for a new or unpermitted facility. Construction Permit # \_\_\_\_\_
- An operating permit renewal: Permit #MO- 0086126 Expiration Date November 29, 2012
- An operating permit modification: Permit #MO- \_\_\_\_\_ Reason: \_\_\_\_\_

1.1 Is this a Federal/State Funded Project?  Yes  No Funding Agency/Project #: \_\_\_\_\_

1.2 Is the appropriate fee included with the application (See instructions for appropriate fee)?  Yes  No

**2. FACILITY**

NAME		TELEPHONE NUMBER WITH AREA CODE	
MSD, Fenton Wastewater Treatment Facility		(636) 861-6700	
ADDRESS (PHYSICAL)	CITY	STATE	ZIP
75 Opps Lane	Fenton	Missouri	63026

2.1 **LEGAL DESCRIPTION** (Plant Site): NE ¼, SE ¼, NW ¼, Sec. 35, T 44n, R SE County St. Louis

2.2 UTM Coordinates Easting (X): \_\_\_\_\_ Northing (Y): \_\_\_\_\_ 723,917 E, 4,265,495 N  
For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)

**3. OWNER**

NAME		TITLE		TELEPHONE NUMBER WITH AREA CODE	
Metropolitan Saint Louis Sewer District				(314) 768-6260	
ADDRESS	CITY	STATE	ZIP		
2350 Market Street	Saint Louis	Missouri	63103-2555		

3.1 Request review of draft permit prior to Public Notice?  Yes  No

**4. CONTINUING AUTHORITY:** Permanent organization which will serve as the continuing authority for the operation, maintenance and modernization of the facility.

NAME		CITY	
Metropolitan Saint Louis Sewer District		Valley Park	
ADDRESS	CERTIFICATE NUMBER (IF APPLICABLE)	STATE	ZIP
1000 Grand Glaize Parkway	A3882	Missouri	63088

**5. OPERATOR**

NAME	TITLE	TELEPHONE NUMBER WITH AREA CODE
Todd V. Heller	Operations Division Manager	(636) 861-6701

**6. FACILITY CONTACT**

NAME	TITLE
Todd V. Heller	Operations Division Manager

MO 780-1805 (09-08)

FACILITY NAME MSD, Fenton WWTF		PERMIT NO. MO- 0086126	OUTFALL NO. 001
<b>PART A – BASIC APPLICATION INFORMATION</b>			
<b>7. ADDITIONAL FACILITY INFORMATION</b>			
7.1 BRIEF DESCRIPTION OF FACILITIES See Attachment 7.1			
7.2 TOPOGRAPHIC MAP. ATTACH TO THIS APPLICATION A TOPOGRAPHIC MAP OF THE AREA EXTENDING AT LEAST ONE MILE BEYOND FACILITY PROPERTY BOUNDARIES. THIS MAP MUST SHOW THE OUTLINE OF THE FACILITY AND THE FOLLOWING INFORMATION. (YOU MAY SUBMIT MORE THAN ONE MAP IF ONE MAP DOES NOT SHOW THE ENTIRE AREA.) a. The area surrounding the treatment plant, including all unit processes. b. The location of the downstream landowner(s). (See Item 10.) c. The major pipes or other structures through which wastewater enters the treatment works and the pipes or other structures through which treated wastewater is discharged from the treatment plant. Include outfalls from bypass piping, if applicable. d. The actual point of discharge. e. Wells, springs, other surface water bodies and drinking water wells that are: 1) within ¼ mile of the property boundaries of the treatment works, and 2) listed in public record or otherwise known to the applicant. f. Any areas where the sewage sludge produced by the treatment works is stored, treated or disposed. g. If the treatment works receives waste that is classified as hazardous under the Resource Conservation and Recovery Act, or RCRA, by truck, rail or special pipe, show on the map where that hazardous waste enters the treatment works and where it is treated, stored or disposed.			
7.3 PROCESS FLOW DIAGRAM OR SCHEMATIC. PROVIDE A DIAGRAM SHOWING THE PROCESSES OF THE TREATMENT PLANT. ALSO, PROVIDE A WATER BALANCE SHOWING ALL TREATMENT UNITS, INCLUDING DISINFECTION (E.G. CHLORINATION AND DECHLORINATION). THE WATER BALANCE MUST SHOW DAILY AVERAGE FLOW RATES AT INFLUENT AND DISCHARGE POINTS AND APPROXIMATE DAILY FLOW RATES BETWEEN TREATMENT UNITS. INCLUDE A BRIEF NARRATIVE DESCRIPTION OF THE DIAGRAM.			
7.4 FACILITY SIC CODE 4952	DISCHARGE SIC CODE: 4952	FACILITY NAICS CODE: _____	DISCHARGE NAICS CODE: _____
7.5 NUMBER OF SEPARATE DISCHARGE POINTS 1 - Outfall #001			
7.6 NUMBER OF PEOPLE PRESENTLY CONNECTED OR POPULATION EQUIVALENT 39,000		DESIGN POPULATION EQUIVALENT 67,500	
NUMBER OF UNITS PRESENTLY CONNECTED HOMES _____ APARTMENTS _____ TRAILERS _____ OTHER _____			
TOTAL DESIGN FLOW (ALL OUTFALLS) 6.75 MGD		ACTUAL FLOW 4.97	
7.7 DOES ANY BYPASSING OCCUR ANYWHERE IN THE COLLECTION SYSTEM OR AT THE TREATMENT FACILITY? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> (If Yes, attach an explanation.) See Attachment 7.7			
7.8 LENGTH OF THE SANITARY SEWER COLLECTION SYSTEM IN MILES Gravity = 155.7, Force = 10.6, Total Sanitary Collection System = 166.3			
7.9 IS INDUSTRIAL WASTE DISCHARGED TO THE FACILITY IDENTIFIED IN ITEM 2? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>			
7.10 WILL THE DISCHARGE BE CONTINUOUS THROUGH THE YEAR? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>			
A. DISCHARGE WILL OCCUR DURING THE FOLLOWING MONTHS January - December		B. HOW MANY DAYS OF THE WEEK WILL THE DISCHARGE OCCUR? Seven (7)	
7.11 IS WASTEWATER LAND APPLIED? (If Yes, Attach Form I) Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		7.12 DOES THIS FACILITY DISCHARGE TO A LOSING STREAM OR SINKHOLE? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
7.13 HAS A WASTE LOAD ALLOCATION STUDY BEEN COMPLETED FOR THIS FACILITY? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			
7.14 LIST ALL PERMIT VIOLATIONS, INCLUDING EFFLUENT LIMIT EXCEEDANCES IN THE LAST FIVE YEARS. ATTACH A SEPARATE SHEET IF NECESSARY. IF NONE, WRITE NONE. None			
<b>8. LABORATORY CONTROL INFORMATION</b>			
8.1 LABORATORY WORK CONDUCTED BY PLANT PERSONNEL			
Lab work conducted outside of plant. MSD		BOTH	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Push-button or visual methods for simple test such as pH, settleable solids.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Additional procedures such as Dissolved Oxygen, Chemical Oxygen Demand, Biological Oxygen Demand, titrations, solids, volatile content.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. MO-0086126
<b>PART A – BASIC APPLICATION INFORMATION</b>		
<b>9. SLUDGE HANDLING, USE AND DISPOSAL</b>		
9.1 IS THE SLUDGE A HAZARDOUS WASTE AS DEFINED BY 10 CSR 25? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		
9.2 SLUDGE PRODUCTION, INCLUDING SLUDGE RECEIVED FROM OTHERS Design Dry Tons/Year 2,500		Actual Dry Tons/Year 1,021
9.3 CAPACITY OF SLUDGE HOLDING STRUCTURES		
9.4 SLUDGE STORAGE PROVIDED Cubic Feet 0 Days of Storage 0 Average Percent Solids of Sludge 23.9% <input checked="" type="checkbox"/> No Sludge Storage is Provided		
9.5 TYPE OF STORAGE <input type="checkbox"/> Holding Tank <input type="checkbox"/> Basin <input type="checkbox"/> Building <input type="checkbox"/> Concrete Pad <input type="checkbox"/> Other (Describe) <u>n/a</u>		
9.6 SLUDGE TREATMENT <input type="checkbox"/> Anaerobic Digester <input type="checkbox"/> Storage Tank <input type="checkbox"/> Lime Stabilization <input type="checkbox"/> Lagoon <input type="checkbox"/> Aerobic Digester <input type="checkbox"/> Air or Heat Drying <input type="checkbox"/> Composting <input checked="" type="checkbox"/> Other Belt Filter Press		
9.7 SLUDGE USE OR DISPOSAL <input checked="" type="checkbox"/> Land Application <input checked="" type="checkbox"/> Contract Hauler <input checked="" type="checkbox"/> Hauled to Another Treatment Facility <input checked="" type="checkbox"/> Solid Waste Landfill <input type="checkbox"/> Surface Disposal (Sludge Disposal Lagoon, Sludge Held For More Than Two Years) <input checked="" type="checkbox"/> Incineration <input type="checkbox"/> Other (Attach Explanation Sheet) _____		
9.8 PERSON RESPONSIBLE FOR HAULING SLUDGE TO DISPOSAL FACILITY		
NAME See Attachment 9.8		
ADDRESS	CITY	STATE ZIP
CONTACT PERSON	TELEPHONE NUMBER WITH AREA CODE	PERMIT NO. MO-
9.9 SLUDGE USE OR DISPOSAL FACILITY <input type="checkbox"/> By Applicant <input type="checkbox"/> By Others (Complete Below)		
NAME See Attachment 9.9		
ADDRESS	CITY	STATE ZIP
CONTACT PERSON	TELEPHONE NUMBER WITH AREA CODE	PERMIT NO. MO-
9.10 DO THE SLUDGE OR BIOSOLIDS DISPOSAL COMPLY WITH FEDERAL SLUDGE REGULATIONS UNDER 40 CFR 503? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Attach Explanation)		
<b>10. DOWNSTREAM LANDOWNER(S). (ATTACH ADDITIONAL SHEETS AS NECESSARY.)</b>		
NAME See Attachment 10 and Downstream Land Owner Map		
ADDRESS	CITY	STATE ZIP
<b>11. DRINKING WATER SUPPLY INFORMATION</b>		
11.1 SOURCE OF YOUR DRINKING WATER SUPPLY		
A. PUBLIC SUPPLY (MUNICIPAL OR WATER DISTRICT WATER) (IF PUBLIC, PLEASE GIVE NAME OF PUBLIC SUPPLY) Missouri American		
B. PRIVATE WELL		
C. SURFACE WATER (LAKE, POND OR STREAM)		
11.2 DOES YOUR DRINKING WATER SOURCE SERVE AT LEAST 25 PEOPLE AT LEAST 60 DAYS PER YEAR (NOT NECESSARILY CONSECUTIVE DAYS)? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
11.3 DOES YOUR SUPPLY SERVE HOUSING THAT IS OCCUPIED YEAR ROUND BY THE SAME PEOPLE? THIS DOES NOT INCLUDE HOUSING THAT IS OCCUPIED SEASONALLY? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
<b>END OF PART A</b>		

**MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL**

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART B – ADDITIONAL APPLICATION INFORMATION**

**20. INFLOW AND INFILTRATION**

ESTIMATE THE AVERAGE NUMBER OF GALLONS PER DAY THAT FLOW INTO THE TREATMENT WORKS FROM INFLOW AND INFILTRATION.

Gallons Per Day See Attachment 20.

BRIEFLY EXPLAIN ANY STEPS UNDERWAY OR PLANNED TO MINIMIZE INFLOW AND INFILTRATION.

See Attachment 20.

**20.1 OPERATION AND MAINTENANCE PERFORMED BY CONTRACTOR(S)**

ARE ANY OPERATIONAL OR MAINTENANCE ASPECTS (RELATED TO WASTEWATER TREATMENT AND EFFLUENT QUALITY) OF THE TREATMENT WORKS THE RESPONSIBILITY OF A CONTRACTOR?

Yes  No  If Yes, list the name, address, telephone number and status of each contractor and describe the contractor's responsibilities. (Attach additional pages if necessary.)

NAME

MAILING ADDRESS

TELEPHONE NUMBER WITH AREA CODE

RESPONSIBILITIES OF CONTRACTOR

**20.2 SCHEDULED IMPROVEMENTS AND SCHEDULES OF IMPLEMENTATION. PROVIDE INFORMATION ABOUT ANY UNCOMPLETED IMPLEMENTATION SCHEDULE OR UNCOMPLETED PLANS FOR IMPROVEMENTS THAT WILL AFFECT THE WASTEWATER TREATMENT, EFFLUENT QUALITY OR DESIGN CAPACITY OF THE TREATMENT WORKS. IF THE TREATMENT WORKS HAS SEVERAL DIFFERENT IMPLEMENTATION SCHEDULES OR IS PLANNING SEVERAL IMPROVEMENTS, SUBMIT SEPARATE RESPONSES FOR EACH. (IF NONE, GO TO QUESTION B-20.3.)**

A. List the outfall number that is covered by this implementation schedule  
Outfall No.

B. Indicate whether the planned improvements or implementation schedule are required by local, state or federal agencies.  
Yes  No  N/A

**20.3 WASTEWATER DISCHARGES:**

COMPLETE QUESTIONS 20.4 THROUGH 20.7 ONCE FOR EACH OUTFALL (INCLUDING BYPASS POINTS) THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION ON COMBINED SEWER OVERFLOWS IN THIS SECTION.

**20.4 DESCRIPTION OF OUTFALL**

OUTFALL NUMBER #001

**A. LOCATION**

¼ NE ¼ SE ¼ NW Section 35 Township 44N Range 5E  E  W

UTM Coordinates Easting (X): \_\_\_\_\_ Northing (Y): \_\_\_\_\_ Easting (x): 724,247, Northing (y): 4,265,584  
For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)

B. Distance from Shore (If Applicable)  
\_\_\_\_\_ ft.

C. Depth Below Surface (If Applicable)  
\_\_\_\_\_ ft.

D. Average Daily Flow Rate  
4.97 mgd

E. Does this outfall have either an intermittent or periodic discharge?  
 Yes  No If Yes, Provide the following information:

Number of Days Per Year Discharge Occurs: 365

Average Duration of Each Discharge: 24 hours per day

Average Flow Per Discharge: 4.97 mgd

Months in Which Discharge Occurs: January - December

Is Outfall Equipped with a Diffuser?  Yes  No

**20.5 DESCRIPTION OF RECEIVING WATER**

B. Name of Receiving Water  
Meramec River

B. Name of Watershed (If Known)  
Lower Meramec

U.S. Soil Conservation Service 14-Digit Watershed Code (If Known)  
07140102-080003

B. Name of State Management/River Basin (If Known)  
Lower Meramec

U.S. Geological Survey 8-Digit Hydrologic Cataloging Unit Code (If Known)  
07140102

B. Critical Flow of Receiving Stream (If Applicable)  
Acute 322 cfs Chronic 372 cfs

B. Total Hardness of Receiving Stream at Critical Low Flow (If Applicable)  
mg/L of CaCO<sub>3</sub> n/a

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART B – ADDITIONAL APPLICATION INFORMATION (CONTINUED)**

20.6 DESCRIPTION OF TREATMENT

A. WHAT LEVELS OF TREATMENT ARE PROVIDED? Check All That Apply

Primary       Secondary       Advanced       Other (Describe) Disinfection

B. INDICATE THE FOLLOWING REMOVAL RATES (AS APPLICABLE)

Design BOD<sub>5</sub> Removal Or Design CBOD<sub>5</sub> Removal      > 85 %      Design SS Removal      > 85 %  
 Design P Removal      \_\_\_ %      Design N Removal      \_\_\_ %      Other      \_\_\_ %

C. What type of disinfection is used for the effluent from this outfall? If disinfection varies by season, please describe:

UV, April 1 - October 31

If disinfection is by chlorination, is dechlorination used for this outfall?       Yes       No

Does the treatment plant have post aeration?       Yes       No

20.7 EFFLUENT TESTING DATA. ALL APPLICANTS THAT DISCHARGE TO WATERS OF THE U.S. MUST PROVIDE EFFLUENT TESTING DATA FOR THE FOLLOWING PARAMETERS. PROVIDE THE INDICATED EFFLUENT DATA FOR EACH OUTFALL THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION OF COMBINED SEWER OVERFLOWS IN THIS SECTION. ALL INFORMATION REPORTED MUST BE BASED ON DATA COLLECTED THROUGH ANALYSIS CONDUCTED USING 40 CFR PART 136 METHODS. IN ADDITION, THIS DATA MUST COMPLY WITH QA/QC REQUIREMENTS OF 40 CFR PART 136 AND OTHER APPROPRIATE QA/QC REQUIREMENTS FOR STANDARD METHODS FOR ANALYTES NOT ADDRESSED BY 40 CFR PART 136.

OUTFALL NUMBER      See Attachment 20.7

PARAMETER	MAXIMUM DAILY VALUE		AVERAGE DAILY VALUE		
	VALUE	UNITS	VALUE	UNITS	NO. OF SAMPLES
pH (Minimum)		S.U.		S.U.	
pH (Maximum)		S.U.		S.U.	
FLOW RATE		MGD		MGD	
TEMPERATURE (Winter)		°C		°C	
TEMPERATURE (Summer)		°C		°C	

\*For pH report a minimum and a maximum daily value.

POLLUTANT	MAXIMUM DAILY DISCHARGE		AVERAGE DAILY DISCHARGE			ANALYTICAL METHOD	ML/MDL
	CONC.	UNITS	CONC.	UNITS	NO. OF SAMPLES		

Conventional and Nonconventional Compounds

BIOCHEMICAL OXYGEN DEMAND (Report One)	BOD <sub>5</sub>		mg/L		mg/L		
	CBOD <sub>5</sub>		mg/L		mg/L		
FECAL COLIFORM			#/100 mL		#/100 mL		
TOTAL SUSPENDED SOLIDS (TSS)			mg/L		mg/L		
AMMONIA (AS N)			mg/L		mg/L		
CHLORINE (TOTAL RESIDUAL, TRC)			mg/L		mg/L		
DISSOLVED OXYGEN			mg/L		mg/L		
TOTAL KJELDAHL NITROGEN (TKN)			mg/L		mg/L		
NITRATE PLUS NITRITE NITROGEN			mg/L		mg/L		
OIL AND GREASE			mg/L		mg/L		
PHOSPHORUS (TOTAL)			mg/L		mg/L		
TOTAL DISSOLVE SOLIDS (TDS)			mg/L		mg/L		
OTHER			mg/L		mg/L		

**END OF PART B**

**PART C - CERTIFICATION**

**30. CERTIFICATION**

All applicants must complete the Certification Section. This certification must be signed by an officer of the company or city official. All applicants must complete all applicable sections as explained in the Application Overview. By signing this certification statement, applicants confirm that they have reviewed the entire form and have completed all sections that apply to the facility for which this application is submitted.

ALL APPLICANTS MUST COMPLETE THE FOLLOWING CERTIFICATION.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

PRINTED NAME AND OFFICIAL TITLE (MUST BE AN OFFICER OF THE COMPANY OR CITY OFFICIAL)

Todd V. Heller

SIGNATURE



TELEPHONE NUMBER WITH AREA CODE

(636) 861-6701

DATE SIGNED

5-29-12

Upon request of the permitting authority, you must submit any other information necessary to assess wastewater treatment practices at the treatment works or identify appropriate permitting requirements.

For Design Flows Less than 1 Million Gallons Per Day,  
Send Completed Form to:

**Appropriate Regional Office**

Map of regional offices with addresses and phone numbers is available on the Web at [www.dnr.mo.gov/regions/ro-map.pdf](http://www.dnr.mo.gov/regions/ro-map.pdf).

For Design Flows of 1 Million Gallons Per Day or Greater,  
Send Completed Form to:

Department of Natural Resources  
Water Protection Program  
ATTN: NPDES Permits and Engineering Section  
P.O. Box 176  
Jefferson City, MO 65102

**END OF PART C.**

**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.**

Do not complete the remainder of this application, unless:

1. Your facility design flow is equal to or greater than 1,000,000 gallons per day.
2. Your facility is a pretreatment treatment works.
3. Your facility is a combined sewer system.

Submittal of an incomplete application may result in the application being returned. Permit fees for returned applications shall be forfeited. Permit fees for applications being processed by the department that are withdrawn by the applicant shall be forfeited.

<b>MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL.</b>		
FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001

**PART D – EXPANDED EFFLUENT TESTING DATA**

**40. EXPANDED EFFLUENT TESTING DATA**

Refer to the supplemental application information to determine whether Part D applies to the treatment works.

40.1 EFFLUENT TESTING: IF THE TREATMENT WORKS HAS A DESIGN FLOW GREATER THAN OR EQUAL TO 1 MILLION GALLONS PER DAY OR IT HAS (OR IS REQUIRED TO HAVE) A PRETREATMENT PROGRAM, OR IS OTHERWISE REQUIRED BY THE PERMITTING AUTHORITY TO PROVIDE THE DATA, THEN PROVIDE EFFLUENT TESTING DATA FOR THE FOLLOWING POLLUTANTS. PROVIDE THE INDICATED EFFLUENT TESTING INFORMATION FOR EACH OUTFALL THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION ON COMBINED SEWER OVERFLOWS IN THIS SECTION. ALL INFORMATION REPORTED MUST BE BASED ON DATA COLLECTED THROUGH ANALYSIS CONDUCTED USING 40 CFR PART 136 METHODS. IN ADDITION, THIS DATA MUST COMPLY WITH QA/QC REQUIREMENTS OF 40 CFR PART 136 AND OTHER APPROPRIATE QA/QC REQUIREMENTS FOR STANDARD METHODS FOR ANALYTES NOT ADDRESSED BY 40 CFR PART 136. INDICATE IN THE BLANK ROWS PROVIDED BELOW ANY DATA YOU MAY HAVE ON POLLUTANTS NOT SPECIFICALLY LISTED IN THIS FORM. EFFLUENT TESTING MUST NOT BE MORE THAN FOUR AND ONE-HALF YEARS OLD.

OUTFALL NUMBER (Complete Once for Each Outfall Discharging Effluent to Waters of the State.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES		
METALS (TOTAL RECOVERABLE), CYANIDE, PHENOLS AND HARDNESS											
ANTIMONY											
ARSENIC											
BERYLLIUM											
CADMIUM											
CHROMIUM											
COPPER											
LEAD											
MERCURY											
NICKEL											
SELENIUM											
SILVER											
THALLIUM											
ZINC											
CYANIDE											
TOTAL PHENOLIC COMPOUNDS											
HARDNESS (as CaCO <sub>3</sub> )											

See Attachment 40.1

USE THIS SPACE (OR A SEPARATE SHEET) TO PROVIDE INFORMATION ON OTHER METALS REQUESTED BY THE PERMIT WRITER.


FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART D – EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

40.1 EXPANDED EFFLUENT TESTING DATA (CONTINUED)

Complete Once for Each Outfall Discharging Effluent to Waters of the State.

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL	
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES			
VOLATILE ORGANIC COMPOUNDS												
ACROLEIN												
ACRYLONITRILE												
BENZENE												
BROMOFORM												
CARBON TETRACHLORIDE												
CHLOROBENZENE												
CHLORODIBROMO-METHANE												
CHLOROETHANE												
2-CHLORO-ETHYL VINYL ETHER												
CHLOROFORM												
DICHLOROBROMO-METHANE												
1,1-DICHLORO-ETHANE												
1,2-DICHLORO-ETHANE												
TRANS-1,2-DICHLOROETHYLENE												
1,1-DICHLORO-ETHYLENE												
1,2-DICHLORO-PROPANE												
1,3-DICHLORO-PROPYLENE												
ETHYLBENZENE												
METHYL BROMIDE												
METHYL CHLORIDE												
METHYLENE CHLORIDE												
1,1,2,2-TETRACHLOROETHANE												
TETRACHLORO-ETHANE												
TOLUENE												
3,4-BENZO-FLUORANTHENE												
BENZO(GH) PHERYLENE												
BENZO(K) FLUORANTHENE												

See Attachment 40.1


 MISSOURI DEPARTMENT OF NATURAL RESOURCES  
 WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL PROGRAM


**FORM B2 – APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS PER DAY**

FACILITY NAME MSD, Fenton Wastewater Treatment Facility	
PERMIT NO. MO-0086126	COUNTY Saint Louis
<b>APPLICATION OVERVIEW</b>	
<p>Form B2 has been developed in a modular format and consists of Parts A, B and C and a Supplemental Application Information (Parts D, E, F and G) packet. All applicants must complete Parts A, B and C. Some applicants must also complete parts of the Supplemental Application Information packet. The following items explain which parts of Form B2 you must complete. Submittal of an incomplete application may result in the application being returned.</p>	
<b>BASIC APPLICATION INFORMATION</b>	
<p>A. Basic Application Information for all Applicants. All applicants must complete Part A.</p> <p>B. Additional Application Information for all Applicants. All applicants must complete Part B.</p> <p>C. Certification. All applicants must complete Part C.</p>	
<b>SUPPLEMENTAL APPLICATION INFORMATION</b>	
<p>D. Expanded Effluent Testing Data. A treatment works that discharges effluent to surface water of the United States and meets one or more of the following criteria must complete <i>Part D - Expanded Effluent Testing Data</i>:</p> <ol style="list-style-type: none"> <li>Has a design flow rate greater than or equal to 1 million gallons per day.</li> <li>Is required to have or currently has a pretreatment program.</li> <li>Is otherwise required by the permitting authority to provide the information.</li> </ol> <p>E. Toxicity Testing Data. A treatment works that meets one or more of the following criteria must complete <i>Part E - Toxicity Testing Data</i>:</p> <ol style="list-style-type: none"> <li>Has a design flow rate greater than or equal to 1 million gallons per day.</li> <li>Is required to have or currently has a pretreatment program.</li> <li>Is otherwise required by the permitting authority to provide the information.</li> </ol> <p>F. Industrial User Discharges and Resource Conservation and Recovery Act / Comprehensive Environmental Response, Compensation and Liability Act Wastes. A treatment works that accepts process wastewater from any significant industrial users, also known as SIUs, or receives a Resource Conservation and Recovery Act or CERCLA wastes must complete <i>Part F - Industrial User Discharges and Resource Conservation and Recovery Act /CERCLA Wastes</i>.</p> <p>SIUs are defined as:</p> <ol style="list-style-type: none"> <li>All Categorical Industrial Users, or CIUs, subject to Categorical Pretreatment Standards under 40 Code of Federal Regulations 403.6 and 40 Code of Federal Regulations 403.6 and 40 CFR Chapter 1, Subchapter N.</li> <li>Any other industrial user that meets one or more of the following:       <ol style="list-style-type: none"> <li>Discharges an average of 25,000 gallons per day or more of process wastewater to the treatment works (with certain exclusions).</li> <li>Contributes a process waste stream that makes up five percent or more of the average dry weather hydraulic or organic capacity of the treatment plant.</li> <li>Is designated as an SIU by the control authority.</li> </ol> </li> </ol> <p>G. Combined Sewer Systems. A treatment works that has a combined sewer system must complete <i>Part G - Combined Sewer Systems</i>.</p>	
<b>ALL APPLICANTS MUST COMPLETE PARTS A, B and C</b>	

RECEIVED

MAY 30 2012

AP 11810



MISSOURI DEPARTMENT OF NATURAL RESOURCES  
WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH  
**FORM B2 - APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS PER DAY**

FOR AGENCY USE ONLY	
CHECK NUMBER	NO FEE REQUIRED
DATE RECEIVED	FEE SUBMITTED
5/30/12	∅

(P)

**PART A - BASIC APPLICATION INFORMATION**

1. This application is for:

An operating permit and antidegradation review public notice.

A construction permit following an appropriate operating permit and antidegradation review public notice.

A construction permit, a concurrent operating permit and antidegradation review public notice.

A construction permit (submitted before Aug. 30, 2008 or antidegradation review is not required).

An operating permit for a new or unpermitted facility. Construction Permit # \_\_\_\_\_

An operating permit renewal: Permit #MO- 0086126 Expiration Date November 29, 2012

An operating permit modification: Permit #MO- \_\_\_\_\_ Reason: \_\_\_\_\_

1.1 Is this a Federal/State Funded Project?  Yes  No Funding Agency/Project #: \_\_\_\_\_

1.2 Is the appropriate fee included with the application (See instructions for appropriate fee)?  Yes  No

**2. FACILITY**

NAME MSD, Fenton Wastewater Treatment Facility		TELEPHONE NUMBER WITH AREA CODE (636) 861-6700	
ADDRESS (PHYSICAL) 75 Opps Lane	CITY Fenton	STATE Missouri	ZIP 63026

2.1 LEGAL DESCRIPTION (Plant Site): NE ¼, SE ¼, NW ¼, Sec. 35, T 44n, R SE County St. Louis

2.2 UTM Coordinates Easting (X): \_\_\_\_\_ Northing (Y): \_\_\_\_\_ 723,917 E, 4,265,495 N  
For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)

**3. OWNER**

NAME Metropolitan Saint Louis Sewer District		TELEPHONE NUMBER WITH AREA CODE (314) 768-6260	
ADDRESS 2350 Market Street	CITY Saint Louis	STATE Missouri	ZIP 63103-2555

3.1 Request review of draft permit prior to Public Notice?  Yes  No

**4. CONTINUING AUTHORITY:** Permanent organization which will serve as the continuing authority for the operation, maintenance and modernization of the facility.

NAME Metropolitan Saint Louis Sewer District		CITY Valley Park	
ADDRESS 1000 Grand Glaize Parkway	CERTIFICATE NUMBER (IF APPLICABLE) A3882	STATE Missouri	ZIP 63088

**5. OPERATOR**

NAME Todd V. Heller	TITLE Operations Division Manager	TELEPHONE NUMBER WITH AREA CODE (636) 861-6701
------------------------	--------------------------------------	---

**6. FACILITY CONTACT**

NAME Todd V. Heller	TITLE Operations Division Manager
------------------------	--------------------------------------

MO 780-1805 (09-08)

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. 001
-----------------------------------	---------------------------	--------------------

**PART A – BASIC APPLICATION INFORMATION**

**7. ADDITIONAL FACILITY INFORMATION**

7.1 BRIEF DESCRIPTION OF FACILITIES  
See Attachment 7.1

7.2 TOPOGRAPHIC MAP. ATTACH TO THIS APPLICATION A TOPOGRAPHIC MAP OF THE AREA EXTENDING AT LEAST ONE MILE BEYOND FACILITY PROPERTY BOUNDARIES. THIS MAP MUST SHOW THE OUTLINE OF THE FACILITY AND THE FOLLOWING INFORMATION. (YOU MAY SUBMIT MORE THAN ONE MAP IF ONE MAP DOES NOT SHOW THE ENTIRE AREA.)

- The area surrounding the treatment plant, including all unit processes.
- The location of the downstream landowner(s). (See Item 10.)
- The major pipes or other structures through which wastewater enters the treatment works and the pipes or other structures through which treated wastewater is discharged from the treatment plant. Include outfalls from bypass piping, if applicable.
- The actual point of discharge.
- Wells, springs, other surface water bodies and drinking water wells that are: 1) within ¼ mile of the property boundaries of the treatment works, and 2) listed in public record or otherwise known to the applicant.
- Any areas where the sewage sludge produced by the treatment works is stored, treated or disposed.
- If the treatment works receives waste that is classified as hazardous under the Resource Conservation and Recovery Act, or RCRA, by truck, rail or special pipe, show on the map where that hazardous waste enters the treatment works and where it is treated, stored or disposed.

7.3 PROCESS FLOW DIAGRAM OR SCHEMATIC. PROVIDE A DIAGRAM SHOWING THE PROCESSES OF THE TREATMENT PLANT. ALSO, PROVIDE A WATER BALANCE SHOWING ALL TREATMENT UNITS, INCLUDING DISINFECTION (E.G. CHLORINATION AND DECHLORINATION). THE WATER BALANCE MUST SHOW DAILY AVERAGE FLOW RATES AT INFLUENT AND DISCHARGE POINTS AND APPROXIMATE DAILY FLOW RATES BETWEEN TREATMENT UNITS. INCLUDE A BRIEF NARRATIVE DESCRIPTION OF THE DIAGRAM.

7.4 FACILITY SIC CODE 4952	DISCHARGE SIC CODE: 4952	FACILITY NAICS CODE: _____	DISCHARGE NAICS CODE: _____
-------------------------------	-----------------------------	-------------------------------	--------------------------------

7.5 NUMBER OF SEPARATE DISCHARGE POINTS  
1 - Outfall #001

7.6 NUMBER OF PEOPLE PRESENTLY CONNECTED OR POPULATION EQUIVALENT 39,000	DESIGN POPULATION EQUIVALENT 67,500
---	--

NUMBER OF UNITS PRESENTLY CONNECTED			
HOMES _____	APARTMENTS _____	TRAILERS _____	OTHER _____

TOTAL DESIGN FLOW (ALL OUTFALLS) 6.75 MGD	ACTUAL FLOW 4.97
--	---------------------

7.7 DOES ANY BYPASSING OCCUR ANYWHERE IN THE COLLECTION SYSTEM OR AT THE TREATMENT FACILITY?  
Yes  No  (If Yes, attach an explanation.) See Attachment 7.7

7.8 LENGTH OF THE SANITARY SEWER COLLECTION SYSTEM IN MILES  
Gravity = 155.7, Force = 10.6, Total Sanitary Collection System = 166.3

7.9 IS INDUSTRIAL WASTE DISCHARGED TO THE FACILITY IDENTIFIED IN ITEM 2? Yes  No

7.10 WILL THE DISCHARGE BE CONTINUOUS THROUGH THE YEAR? Yes  No

A. DISCHARGE WILL OCCUR DURING THE FOLLOWING MONTHS January - December	B. HOW MANY DAYS OF THE WEEK WILL THE DISCHARGE OCCUR? Seven (7)
---	---

7.11 IS WASTEWATER LAND APPLIED? (If Yes, Attach Form I) Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	7.12 DOES THIS FACILITY DISCHARGE TO A LOSING STREAM OR SINKHOLE? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
---	--

7.13 HAS A WASTE LOAD ALLOCATION STUDY BEEN COMPLETED FOR THIS FACILITY?  
Yes  No

7.14 LIST ALL PERMIT VIOLATIONS, INCLUDING EFFLUENT LIMIT EXCEEDANCES IN THE LAST FIVE YEARS. ATTACH A SEPARATE SHEET IF NECESSARY. IF NONE, WRITE NONE. None

**8. LABORATORY CONTROL INFORMATION**

8.1 LABORATORY WORK CONDUCTED BY PLANT PERSONNEL			
Lab work conducted outside of plant.	MSD	BOTH	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Push-button or visual methods for simple test such as pH, settleable solids.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Additional procedures such as Dissolved Oxygen, Chemical Oxygen Demand, Biological Oxygen Demand, titrations, solids, volatile content.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph.			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. MO-0086126
<b>PART A – BASIC APPLICATION INFORMATION</b>		
<b>9. SLUDGE HANDLING, USE AND DISPOSAL</b>		
9.1 IS THE SLUDGE A HAZARDOUS WASTE AS DEFINED BY 10 CSR 25? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		
9.2 SLUDGE PRODUCTION, INCLUDING SLUDGE RECEIVED FROM OTHERS Design Dry Tons/Year 2,500 <span style="float:right">Actual Dry Tons/Year 1,021</span>		
9.3 CAPACITY OF SLUDGE HOLDING STRUCTURES		
9.4 SLUDGE STORAGE PROVIDED Cubic Feet 0 Days of Storage 0 Average Percent Solids of Sludge 23.9% <input checked="" type="checkbox"/> No Sludge Storage is Provided		
9.5 TYPE OF STORAGE <input type="checkbox"/> Holding Tank <input type="checkbox"/> Basin <input type="checkbox"/> Building <input type="checkbox"/> Concrete Pad <input type="checkbox"/> Other (Describe) <u>n/a</u>		
9.6 SLUDGE TREATMENT <input type="checkbox"/> Anaerobic Digester <input type="checkbox"/> Storage Tank <input type="checkbox"/> Lime Stabilization <input type="checkbox"/> Lagoon <input type="checkbox"/> Aerobic Digester <input type="checkbox"/> Air or Heat Drying <input type="checkbox"/> Composting <input checked="" type="checkbox"/> Other Belt Filter Press		
9.7 SLUDGE USE OR DISPOSAL <input checked="" type="checkbox"/> Land Application <input checked="" type="checkbox"/> Contract Hauler <input checked="" type="checkbox"/> Hauled to Another Treatment Facility <input checked="" type="checkbox"/> Solid Waste Landfill <input type="checkbox"/> Surface Disposal (Sludge Disposal Lagoon, Sludge Held For More Than Two Years) <input checked="" type="checkbox"/> Incineration <input type="checkbox"/> Other (Attach Explanation Sheet) _____		
9.8 PERSON RESPONSIBLE FOR HAULING SLUDGE TO DISPOSAL FACILITY		
NAME See Attachment 9.8		
ADDRESS	CITY	STATE ZIP
CONTACT PERSON	TELEPHONE NUMBER WITH AREA CODE	PERMIT NO MO-
9.9 SLUDGE USE OR DISPOSAL FACILITY		
<input type="checkbox"/> By Applicant <input type="checkbox"/> By Others (Complete Below)		
NAME See Attachment 9.9		
ADDRESS	CITY	STATE ZIP
CONTACT PERSON	TELEPHONE NUMBER WITH AREA CODE	PERMIT NO MO-
9.10 DO THE SLUDGE OR BIOSOLIDS DISPOSAL COMPLY WITH FEDERAL SLUDGE REGULATIONS UNDER 40 CFR 503? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Attach Explanation)		
<b>10. DOWNSTREAM LANDOWNER(S). (ATTACH ADDITIONAL SHEETS AS NECESSARY.)</b>		
NAME See Attachment 10 and Downstream Land Owner Map		
ADDRESS	CITY	STATE ZIP
<b>11. DRINKING WATER SUPPLY INFORMATION</b>		
11.1 SOURCE OF YOUR DRINKING WATER SUPPLY		
A. PUBLIC SUPPLY (MUNICIPAL OR WATER DISTRICT WATER) (IF PUBLIC, PLEASE GIVE NAME OF PUBLIC SUPPLY) Missouri American		
B. PRIVATE WELL		
C. SURFACE WATER (LAKE, POND OR STREAM)		
11.2 DOES YOUR DRINKING WATER SOURCE SERVE AT LEAST 25 PEOPLE AT LEAST 60 DAYS PER YEAR (NOT NECESSARILY CONSECUTIVE DAYS)? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
11.3 DOES YOUR SUPPLY SERVE HOUSING THAT IS OCCUPIED YEAR ROUND BY THE SAME PEOPLE? THIS DOES NOT INCLUDE HOUSING THAT IS OCCUPIED SEASONALLY? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
<b>END OF PART A</b>		

MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL			
FACILITY NAME MSD, Fenton WWTF		PERMIT NO. MO- 0086126	OUTFALL NO. #001
<b>PART B – ADDITIONAL APPLICATION INFORMATION</b>			
<b>20. INFLOW AND INFILTRATION</b>			
ESTIMATE THE AVERAGE NUMBER OF GALLONS PER DAY THAT FLOW INTO THE TREATMENT WORKS FROM INFLOW AND INFILTRATION. Gallons Per Day See Attachment 20.			
BRIEFLY EXPLAIN ANY STEPS UNDERWAY OR PLANNED TO MINIMIZE INFLOW AND INFILTRATION. See Attachment 20.			
20.1 OPERATION AND MAINTENANCE PERFORMED BY CONTRACTOR(S)			
ARE ANY OPERATIONAL OR MAINTENANCE ASPECTS (RELATED TO WASTEWATER TREATMENT AND EFFLUENT QUALITY) OF THE TREATMENT WORKS THE RESPONSIBILITY OF A CONTRACTOR? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> If Yes, list the name, address, telephone number and status of each contractor and describe the contractor's responsibilities. (Attach additional pages if necessary.)			
NAME			
MAILING ADDRESS			
TELEPHONE NUMBER WITH AREA CODE			
RESPONSIBILITIES OF CONTRACTOR			
20.2 SCHEDULED IMPROVEMENTS AND SCHEDULES OF IMPLEMENTATION. PROVIDE INFORMATION ABOUT ANY UNCOMPLETED IMPLEMENTATION SCHEDULE OR UNCOMPLETED PLANS FOR IMPROVEMENTS THAT WILL AFFECT THE WASTEWATER TREATMENT, EFFLUENT QUALITY OR DESIGN CAPACITY OF THE TREATMENT WORKS. IF THE TREATMENT WORKS HAS SEVERAL DIFFERENT IMPLEMENTATION SCHEDULES OR IS PLANNING SEVERAL IMPROVEMENTS, SUBMIT SEPARATE RESPONSES FOR EACH. (IF NONE, GO TO QUESTION B-20.3.)			
A. List the outfall number that is covered by this implementation schedule Outfall No.		B. Indicate whether the planned improvements or implementation schedule are required by local, state or federal agencies. Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input checked="" type="checkbox"/>	
20.3 WASTEWATER DISCHARGES: COMPLETE QUESTIONS 20.4 THROUGH 20.7 ONCE FOR EACH OUTFALL (INCLUDING BYPASS POINTS) THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION ON COMBINED SEWER OVERFLOWS IN THIS SECTION.			
20.4 DESCRIPTION OF OUTFALL			
OUTFALL NUMBER #001			
A. LOCATION ¼ <u>NE</u> ¼ <u>SE</u> ¼ <u>NW</u> Section <u>35</u> Township <u>44N</u> Range <u>5E</u> <input type="checkbox"/> E <input type="checkbox"/> W UTM Coordinates Easting (X): _____ Northing (Y): _____ Easting (x): 724,247, Northing (y): 4,265,584 For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)			
B. Distance from Shore (If Applicable) _____ ft.		C. Depth Below Surface (If Applicable) _____ ft.	D. Average Daily Flow Rate <u>4.97</u> mgd
E. Does this outfall have either an intermittent or periodic discharge? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, Provide the following information:			
Number of Days Per Year Discharge Occurs: <u>365</u>	Average Duration of Each Discharge: <u>24 hours per day</u>	Average Flow Per Discharge: <u>4.97</u> mgd	Months in Which Discharge Occurs: <u>January - December</u>
Is Outfall Equipped with a Diffuser? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
20.5 DESCRIPTION OF RECEIVING WATER			
B. Name of Receiving Water Meramec River			
B. Name of Watershed (If Known) Lower Meramec		U.S. Soil Conservation Service 14-Digit Watershed Code (If Known) 07140102-080003	
B. Name of State Management/River Basin (If Known) Lower Meramec		U.S. Geological Survey 8-Digit Hydrologic Cataloging Unit Code (If Known) 07140102	
B. Critical Flow of Receiving Stream (If Applicable) Acute <u>322</u> cfs Chronic <u>372</u> cfs		B. Total Hardness of Receiving Stream at Critical Low Flow (If Applicable) mg/L of CaCO <sub>3</sub> n/a	

MO 780-1805 (09-08)

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART B – ADDITIONAL APPLICATION INFORMATION (CONTINUED)**

20.6 DESCRIPTION OF TREATMENT

A. WHAT LEVELS OF TREATMENT ARE PROVIDED? Check All That Apply  
 Primary     Secondary     Advanced     Other (Describe) Disinfection

B. INDICATE THE FOLLOWING REMOVAL RATES (AS APPLICABLE)  
 Design BOD<sub>5</sub> Removal Or Design CBOD<sub>5</sub> Removal    > 85 %    Design SS Removal    > 85 %  
 Design P Removal    \_\_\_\_%    Design N Removal    \_\_\_\_%    Other    \_\_\_\_%

C. What type of disinfection is used for the effluent from this outfall? If disinfection varies by season, please describe:  
 UV, April 1 - October 31

If disinfection is by chlorination, is dechlorination used for this outfall?     Yes     No

Does the treatment plant have post aeration?     Yes     No

20.7 EFFLUENT TESTING DATA. ALL APPLICANTS THAT DISCHARGE TO WATERS OF THE U.S. MUST PROVIDE EFFLUENT TESTING DATA FOR THE FOLLOWING PARAMETERS. PROVIDE THE INDICATED EFFLUENT DATA FOR EACH OUTFALL THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION OF COMBINED SEWER OVERFLOWS IN THIS SECTION. ALL INFORMATION REPORTED MUST BE BASED ON DATA COLLECTED THROUGH ANALYSIS CONDUCTED USING 40 CFR PART 136 METHODS. IN ADDITION, THIS DATA MUST COMPLY WITH QA/QC REQUIREMENTS OF 40 CFR PART 136 AND OTHER APPROPRIATE QA/QC REQUIREMENTS FOR STANDARD METHODS FOR ANALYTES NOT ADDRESSED BY 40 CFR PART 136.

OUTFALL NUMBER    **See Attachment 20.7**

PARAMETER	MAXIMUM DAILY VALUE		AVERAGE DAILY VALUE		
	VALUE	UNITS	VALUE	UNITS	NO. OF SAMPLES
pH (Minimum)		S.U.		S.U.	
pH (Maximum)		S.U.		S.U.	
FLOW RATE		MGD		MGD	
TEMPERATURE (Winter)		°C		°C	
TEMPERATURE (Summer)		°C		°C	

\*For pH report a minimum and a maximum daily value.

POLLUTANT	MAXIMUM DAILY DISCHARGE		AVERAGE DAILY DISCHARGE			ANALYTICAL METHOD	ML/MDL
	CONC.	UNITS	CONC.	UNITS	NO. OF SAMPLES		

Conventional and Nonconventional Compounds

BIOCHEMICAL OXYGEN DEMAND (Report One)	BOD <sub>5</sub>		mg/L		mg/L		
	CBOD <sub>5</sub>		mg/L		mg/L		
FECAL COLIFORM			#/100 mL		#/100 mL		
TOTAL SUSPENDED SOLIDS (TSS)			mg/L		mg/L		
AMMONIA (AS N)			mg/L		mg/L		
CHLORINE (TOTAL RESIDUAL, TRC)			mg/L		mg/L		
DISSOLVED OXYGEN			mg/L		mg/L		
TOTAL KJELDAHL NITROGEN (TKN)			mg/L		mg/L		
NITRATE PLUS NITRITE NITROGEN			mg/L		mg/L		
OIL AND GREASE			mg/L		mg/L		
PHOSPHORUS (TOTAL)			mg/L		mg/L		
TOTAL DISSOLVE SOLIDS (TDS)			mg/L		mg/L		
OTHER			mg/L		mg/L		

**END OF PART B**

**PART C - CERTIFICATION****30. CERTIFICATION**

All applicants must complete the Certification Section. This certification must be signed by an officer of the company or city official. All applicants must complete all applicable sections as explained in the Application Overview. By signing this certification statement, applicants confirm that they have reviewed the entire form and have completed all sections that apply to the facility for which this application is submitted.


ALL APPLICANTS MUST COMPLETE THE FOLLOWING CERTIFICATION.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

PRINTED NAME AND OFFICIAL TITLE (MUST BE AN OFFICER OF THE COMPANY OR CITY OFFICIAL)

Todd V. Heller

SIGNATURE



TELEPHONE NUMBER WITH AREA CODE

(636) 861-6701

DATE SIGNED

5-29-12

Upon request of the permitting authority, you must submit any other information necessary to assess wastewater treatment practices at the treatment works or identify appropriate permitting requirements.

For Design Flows Less than 1 Million Gallons Per Day,  
Send Completed Form to:

**Appropriate Regional Office**

Map of regional offices with addresses and phone numbers is available on the Web at [www.dnr.mo.gov/regions/ro-map.pdf](http://www.dnr.mo.gov/regions/ro-map.pdf).

For Design Flows of 1 Million Gallons Per Day or Greater,  
Send Completed Form to:

Department of Natural Resources  
Water Protection Program  
ATTN: NPDES Permits and Engineering Section  
P.O. Box 176  
Jefferson City, MO 65102

**END OF PART C.**

**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.**

Do not complete the remainder of this application, unless:

1. Your facility design flow is equal to or greater than 1,000,000 gallons per day.
2. Your facility is a pretreatment treatment works.
3. Your facility is a combined sewer system.

Submittal of an incomplete application may result in the application being returned. Permit fees for returned applications shall be forfeited. Permit fees for applications being processed by the department that are withdrawn by the applicant shall be forfeited.

**MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL.**

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART D – EXPANDED EFFLUENT TESTING DATA**

**40. EXPANDED EFFLUENT TESTING DATA**

Refer to the supplemental application information to determine whether Part D applies to the treatment works.

40.1 EFFLUENT TESTING: IF THE TREATMENT WORKS HAS A DESIGN FLOW GREATER THAN OR EQUAL TO 1 MILLION GALLONS PER DAY OR IT HAS (OR IS REQUIRED TO HAVE) A PRETREATMENT PROGRAM, OR IS OTHERWISE REQUIRED BY THE PERMITTING AUTHORITY TO PROVIDE THE DATA, THEN PROVIDE EFFLUENT TESTING DATA FOR THE FOLLOWING POLLUTANTS. PROVIDE THE INDICATED EFFLUENT TESTING INFORMATION FOR EACH OUTFALL THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION ON COMBINED SEWER OVERFLOWS IN THIS SECTION. ALL INFORMATION REPORTED MUST BE BASED ON DATA COLLECTED THROUGH ANALYSIS CONDUCTED USING 40 CFR PART 136 METHODS. IN ADDITION, THIS DATA MUST COMPLY WITH QA/QC REQUIREMENTS OF 40 CFR PART 136 AND OTHER APPROPRIATE QA/QC REQUIREMENTS FOR STANDARD METHODS FOR ANALYTES NOT ADDRESSED BY 40 CFR PART 136. INDICATE IN THE BLANK ROWS PROVIDED BELOW ANY DATA YOU MAY HAVE ON POLLUTANTS NOT SPECIFICALLY LISTED IN THIS FORM. EFFLUENT TESTING MUST NOT BE MORE THAN FOUR AND ONE-HALF YEARS OLD.

OUTFALL NUMBER (Complete Once for Each Outfall Discharging Effluent to Waters of the State.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL	
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES			
METALS (TOTAL RECOVERABLE), CYANIDE, PHENOLS AND HARDNESS												
ANTIMONY												
ARSENIC												
BERYLLIUM												
CADMIUM												
CHROMIUM												
COPPER												
LEAD												
MERCURY												
NICKEL												
SELENIUM												
SILVER												
THALLIUM												
ZINC												
CYANIDE												
TOTAL PHENOLIC COMPOUNDS												
HARDNESS (as CaCO <sub>3</sub> )												

See Attachment 40.1

USE THIS SPACE (OR A SEPARATE SHEET) TO PROVIDE INFORMATION ON OTHER METALS REQUESTED BY THE PERMIT WRITER.


FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART D – EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

**40.1 EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

Complete Once for Each Outfall Discharging Effluent to Waters of the State.

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL	
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES			
<b>VOLATILE ORGANIC COMPOUNDS</b>												
ACROLEIN												
ACRYLONITRILE												
BENZENE												
BROMOFORM												
CARBON TETRACHLORIDE												
CHLOROBENZENE												
CHLORODIBROMO-METHANE												
CHLOROETHANE												
2-CHLORO-ETHYLVINYL ETHER												
CHLOROFORM												
DICHLOROBROMO-METHANE												
1,1-DICHLORO-ETHANE												
1,2-DICHLORO-ETHANE												
TRANS-1,2-DICHLOROETHYLENE												
1,1-DICHLORO-ETHYLENE												
1,2-DICHLORO-PROPANE												
1,3-DICHLORO-PROPYLENE												
ETHYLBENZENE												
METHYL BROMIDE												
METHYL CHLORIDE												
METHYLENE CHLORIDE												
1,1,2,2-TETRA-CHLOROETHANE												
TETRACHLORO-ETHANE												
TOLUENE												
3,4-BENZO-FLUORANTHENE												
BENZO(GH) PHERYLENE												
BENZO(K) FLUORANTHENE												

See Attachment 40.1

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART D – EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

**40.1 EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

Complete Once for Each Outfall Discharging Effluent to Waters of the State.

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL	
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES			
BIS (2-CHLOROTHOXY) METHANE												
BIS (2-CHLOROETHYL) – ETHER												
BIS (2-ETHYLHEXYL) PHTHALATE												
4-BROMOPHENYL PHENYL ETHER												
BUTYL BENZYL PHTHALATE												
2-CHLORONAPHTHALENE												
4-CHLORPHENYL PHENYL ETHER												
CHRYSENE												
DI-N-BUTYL PHTHALATE												
DEBENZO (A,H) ANTHRACENE												
1,2-DICHLORO-BENZENE												
1,3-DICHLORO-BENZENE												
1,4-DICHLORO-BENZENE												
3,3-DICHLORO-BENZIDINE												
DIETHYL PHTHALATE												
DIMETHYL PHTHALATE												
2,4-DINITRO-TOLUENE												
2,6-DINITRO-TOLUENE												
1,2-DIPHENYL-HYDRAZINE												
1,1,1-TRICHLORO-ETHANE												
1,1,2-TRICHLORO-ETHANE												
TRICHLORETHYLENE												
VINYL CHLORIDE												
USE THIS SPACE (OR A SEPARATE SHEET) TO PROVIDE INFORMATION ON OTHER VOLATILE ORGANIC COMPOUNDS REQUESTED BY THE PERMIT WRITER												

See Attachment 40.1



FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART D – EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

**40.1 EXPANDED EFFLUENT TESTING DATA (CONTINUED)**

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/MDL	
	CONC	UNITS	MASS	UNITS	CONC	UNITS	MASS	UNITS	NO. OF SAMPLES			
<b>BASE-NEUTRAL COMPOUNDS</b>												
ACENAPHTHENE												
ACENAPHTHYLENE												
ANTHRACENE												
BENZIDINE												
BENZO(A)ANTHRACENE												
BENZO(A)PYRENE												
FLUORANTHENE												
FLUORENE												
HEXACHLOROBENZENE												
HEXACHLOROCYCLO-PENTADIENE												
HEXACHLOROETHANE												
INDENO (1,2,3-CD) PYRENE												
ISOPHORONE												
NAPHTHALENE												
NITROBENZENE												
N-NITROSODI-PROPYLAMINE												
N-NITROSODI-METHYLAMINE												
N-NITROSODI-PHENYLAMINE												
PHENANTHRENE												
PYRENE												
1,2,4-TRICHLOROBENZENE												

See Attachment 40.1

USE THIS SPACE (OR SEPARATE SHEET) TO PROVIDE INFORMATION ON OTHER BASE-NEUTRAL COMPOUNDS REQUESTED BY THE PERMIT WRITER.


**END OF PART D**  
**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.**

MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL.			
FACILITY NAME MSD, Fenton WWTF		PERMIT NO. MO- 0086126	OUTFALL NO. #001
PART E – TOXICITY TESTING DATA			
50. TOXICITY TESTING DATA			
Refer to the Supplemental Application Information to determine whether Part E applies to the treatment works.			
Publicly owned treatment works, or POTWS, meeting one or more of the following criteria must provide the results of whole effluent toxicity tests for acute or chronic toxicity for each of the facility's discharge points.			
<p>A. POTWS with a design flow rate greater than or equal to 1 million gallons per day.</p> <p>B. POTWS with a pretreatment program (or those that are required to have one under 40 CFR Part 403).</p> <p>C. POTWS required by the permitting authority to submit data for these parameters</p> <ul style="list-style-type: none"> <li>◆ At a minimum, these results must include quarterly testing for a 12-month period within the past one year using multiple species (minimum of two species), or the results from four tests performed at least annually in the four and one-half years prior to the application, provided the results show no appreciable toxicity, and testing for acute or chronic toxicity, depending on the range of receiving water dilution. Do not include information about combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136.</li> <li>◆ If EPA methods were not used, report the reason for using alternative methods. If test summaries are available that contain all of the information requested below, they may be submitted in place of Part E. If no biomonitoring data is required, do not complete Part E. Refer to the application overview for directions on which other sections of the form to complete.</li> </ul>			
50.1 REQUIRED TESTS. INDICATE THE NUMBER OF WHOLE EFFLUENT TOXICITY TESTS CONDUCTED IN THE PAST FOUR AND ONE-HALF YEARS.			
CHRONIC		ACUTE 18 (performed quarterly)	
INDIVIDUAL TEST DATA. Complete the following chart for the last three whole effluent toxicity tests. Allow one column per test (where each species constitutes a test). Copy this page if more than three tests are being reported.			
	MOST RECENT	2 <sup>ND</sup> MOST RECENT	3 <sup>RD</sup> MOST RECENT
A. TEST INFORMATION			
TEST NUMBER EAS Log #	1408113	1401805	1313718
TEST SPECIES AND TEST METHOD NUMBER	2000.0 / 2002.0	2000.0 / 2002.0	2000.0 / 2002.0
AGE AT INITIATION OF TEST	1 - 14 d/ < 24 h	1 - 14 d/ < 24 h	1 - 14 d/ < 24 h
OUTFALL NUMBER	#001	#001	#001
DATES SAMPLE COLLECTED	1/30 - 1/31/12	10/3 - 10/4/11	7/18 - 7/19/11
DATE TEST STARTED	2/1/12	10/5/11	7/19/11
DURATION	48 hours	48 hours	48 hours
B. GIVE TOXICITY TEST METHODS FOLLOWED			
MANUAL TITLE	Std Methods for Examination of Water & Wastewater	Std Methods for Examination of Water & Wastewater	Std Methods for Examination of Water & Wastewater
EDITION NUMBER AND YEAR OF PUBLICATION	18th Ed. (1992)	18th Ed. (1992)	18th Ed. (1992)
PAGE NUMBER(S)			
C. GIVE THE SAMPLE COLLECTION METHOD(S) USED. FOR MULTIPLE GRAB SAMPLES, INDICATE THE NUMBER OF GRAB SAMPLES USED.			
24-HOUR COMPOSITE	x	x	x
GRAB			
D. INDICATE WHERE THE SAMPLE WAS TAKEN IN RELATION TO DISINFECTION. (CHECK ALL THAT APPLY FOR EACH)			
BEFORE DISINFECTION	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
AFTER DISINFECTION	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
AFTER DECHLORINATION	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
E. DESCRIBE THE POINT IN THE TREATMENT PROCESS AT WHICH THE SAMPLE WAS COLLECTED			
SAMPLE WAS COLLECTED	Post disinfection	Post disinfection	Post disinfection
F. FOR EACH TEST, INCLUDE WHETHER THE TEST WAS INTENDED TO ASSESS CHRONIC TOXICITY, ACUTE TOXICITY OR BOTH.			
CHRONIC TOXICITY	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ACUTE TOXICITY	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
G. PROVIDE THE TYPE OF TEST PERFORMED			
STATIC	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
STATIC STATIC-RENEWAL	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
FLOW-THROUGH	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
H. SOURCE OF DILUTION WATER. IF LABORATORY WATER, SPECIFY TYPE; IF RECEIVING WATER, SPECIFY SOURCE			
LABORATORY WATER			
RECEIVING WATER	Up stream	Up stream	Up stream

FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
-----------------------------------	---------------------------	---------------------

**PART E – TOXICITY TESTING DATA (CONTINUED)**

**50.1 WHOLE EFFLUENT TOXICITY TESTS DATA (CONTINUED)**

	MOST RECENT	2 <sup>ND</sup> MOST RECENT	3 <sup>RD</sup> MOST RECENT
I. TYPE OF DILUTION WATER, IF SALT WATER, SPECIFY "NATURAL" OR TYPE OF ARTIFICIAL SEA SALTS OR BRINE USED.			
FRESH WATER	x	x	x
SALT WATER			
J. GIVE THE PERCENTAGE EFFLUENT USED FOR ALL CONCENTRATIONS IN THE TEST SERIES.			
	100, 79.5, 50, 25, 12.5, 6.25	100, 79.5, 50, 25, 12.5, 6.25	100, 79.5, 50, 25, 12.5, 6.25

**K. PARAMETERS MEASURED DURING THE TEST. (STATE WHETHER PARAMETER MEETS TEST METHOD SPECIFICATIONS)**

pH	7.59 s.u.	8.38 s.u.	7.43 s.u.
SALINITY	948 umhos/cm	823 umhos/cm	785 umhos/cm
TEMPERATURE	12 deg C	1 deg C	20 deg C
AMMONIA	< 0.010 mg/L	< 0.010 mg/L	< 0.010 mg/L
DISSOLVED OXYGEN	7.9 mg/L	< 2 mg/L	4.7 mg/L

**L. TEST RESULTS**

**ACUTE:**

PERCENT IN SURVIVAL IN 100% EFFLUENT	100% / 100%	85% / 85%	100% / 100%
LC <sub>50</sub>	0.957 g/L / 0.474 g/L	1.021 g/L / 0.460 g/L	1.068 g/L / 0.463 g/L
95% C.I.	0.730-1.184 / 0.304-0.643g/l	0.708-1.334 / 0.297-0.623g/l	0.731-1.405 / 0.294-0.632g/l
CONTROL PERCENT SURVIVAL RC	100% / 100%	100% / 100%	100% / 100%
OTHER (DESCRIBE) UC	100% / 100%	90% / 90%	100% / 100%

**CHRONIC:**

NOEC			
IC <sub>25</sub>			
CONTROL PERCENT SURVIVAL			
OTHER (DESCRIBE)			

**M. QUALITY CONTROL ASSURANCE**

IS REFERENCE TOXICANT DATA AVAILABLE?	Yes / Yes	Yes / Yes	Yes / Yes
WAS REFERENCE TOXICANT TEST WITHIN ACCEPTABLE BOUNDS?	Yes / Yes	Yes / Yes	Yes / Yes
WHAT DATE WAS REFERENCED TOXICANT TEST RUN (MM/DD/YYYY)?	2/1/12	10/5/11	7/6/11
OTHER (DESCRIBE)			

**50.2 TOXICITY REDUCTION EVALUATION**

Is the treatment works involved in a toxicity reduction evaluation?  Yes  No  
 If yes, describe:

**50.3 SUMMARY OF SUBMITTED BIOMONITORING TEST INFORMATION**

If you have submitted biomonitoring test information, or information regarding the cause of toxicity, within the past four and one-half years, provide the dates the information was submitted to the permitting authority and a summary of the results.

Date Submitted (MM/DD/YYYY)

Summary of Results (See Instructions)

**END OF PART E**

**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.**

<b>MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL.</b>			
FACILITY NAME MSD, Fenton WWTF		PERMIT NO. MO- 0086126	OUTFALL NO. #001
<b>PART F – INDUSTRIAL USER DISCHARGES AND RCRA/CERCLA WASTES</b>			
<b>60. INDUSTRIAL USER DISCHARGES AND RCRA/CERCLA WASTES</b>			
Refer to the Supplemental Application Information to determine whether Part F applies to the treatment works.			
All treatment works receiving discharges from significant industrial users or which receive RCRA, CERCLA, or other remedial wastes must complete this form.			
<b>GENERAL INFORMATION</b>			
60.1 PRETREATMENT PROGRAM			
Does the treatment works have, or is it subject to, an approved pretreatment program?			
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
60.2 NUMBER OF NON-CATEGORICAL SIGNIFICANT INDUSTRIAL USERS, or SIUs AND CATEGORICAL INDUSTRIAL USERS, or CIUs. PROVIDE THE NUMBER OF EACH OF THE FOLLOWING TYPES OF INDUSTRIAL USERS THAT DISCHARGE TO THE TREATMENT WORKS.			
A.	Number of Non-Categorical SIUs 5	B.	Number of CIUs 3
60.3 SIGNIFICANT INDUSTRIAL USER INFORMATION			
Supply the following information for each SIU. If more than one SIU discharges to the treatment works, provide the information requested for each. Submit additional pages as necessary.			
NAME See Attachment 60			
MAILING ADDRESS		CITY	STATE    ZIP
60.4 INDUSTRIAL PROCESSES			
DESCRIBE ALL OF THE INDUSTRIAL PROCESSES THAT AFFECT OR CONTRIBUTE TO THE SIU's DISCHARGE. See Attachment 60			
60.5 PRINCIPAL PRODUCT(S) AND RAW MATERIAL (S)			
Describe all of the principle processes and raw materials that affect or contribute to the SIU's discharge.			
PRINCIPAL PRODUCT(S) See Attachment 60			
RAW MATERIAL(S) See Attachment 60			
60.6 FLOW RATE			
A.	PROCESS WASTEWATER FLOW RATE. Indicate the average daily volume of process wastewater discharged into the collection system in gallons per day, or gpd, and whether the discharge is continuous or intermittent. gpd <input type="checkbox"/> Continuous <input type="checkbox"/> Intermittent		
B.	NON-PROCESS WASTEWATER FLOW RATE. Indicate the average daily volume of non-process wastewater discharged into the collection system in gallons per day, or gpd, and whether the discharge is continuous or intermittent.		
C.	gpd <input type="checkbox"/> Continuous <input type="checkbox"/> Intermittent		
60.7 PRETREATMENT STANDARDS			
Indicate whether the SIU is subject to the following			
A.	Local Limits	<input type="checkbox"/> Yes	<input type="checkbox"/> No
B.	Categorical Pretreatment Standards	<input type="checkbox"/> Yes	<input type="checkbox"/> No
If subject to categorical pretreatment standards, which category and subcategory? See Attachment 60			
60.8 PROBLEMS AT THE TREATMENT WORKS ATTRIBUTED TO WASTE DISCHARGED BY THE SIU			
Has the SIU caused or contributed to any problems (e.g., upsets, interference) at the treatment works in the past three years? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No    If Yes, describe each episode  No problems noted at the plant for any of the SIU's or SIU/CIU's listed.			

<b>MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL.</b>		
FACILITY NAME MSD, Fenton WWTF	PERMIT NO. MO- 0086126	OUTFALL NO. #001
<b>PART F – INDUSTRIAL USER DISCHARGES AND RCRA/CERCLA WASTES (CONTINUED)</b>		
60.9 RCRA HAZARDOUS WASTE RECEIVED BY TRUCK, RAIL, OR DEDICATED PIPELINE		
RCRA WASTE. Does the treatment works receive or has it in the past three years received RCRA hazardous waste by truck, rail or dedicated pipe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
WASTE TRANSPORT. Method by which RCRA waste is received. (Check all that apply) <input type="checkbox"/> Truck <input type="checkbox"/> Rail <input type="checkbox"/> Dedicated Pipe		
WASTE DESCRIPTION. Give EPA hazardous waste number and amount (volume or mass, specify units).		
EPA HAZARDOUS WASTE NUMBER	AMOUNT	UNITS
60.10 CERCLA, OR SUPERFUND, WASTEWATER, RCRA REMEDIATION/CORRECTIVE ACTION WASTEWATER AND OTHER REMEDIAL ACTIVITY WASTEWATER		
REMEDIAL WASTE. Does the treatment works currently (or has it been notified that it will) receive waste from remedial activities? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No      Provide a list of sites and the requested information for each current and future site.		
60.11 WASTE ORIGIN		
Describe the site and type of facility at which the CERCLA/RCRA/or other remedial waste originates (or is expected to originate in the next five years). n/a		
60.12 POLLUTANTS		
List the hazardous constituents that are received (or are expected to be received). Included data on volume and concentration, if known. (Attach additional sheets if necessary) n/a		
60.13 WASTE TREATMENT		
A. Is this waste treated (or will it be treated) prior to entering the treatment works? <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, describe the treatment (provide information about the removal efficiency): n/a		
B. Is the discharge (or will the discharge be) continuous or intermittent? <input type="checkbox"/> Continuous <input type="checkbox"/> Intermittent If intermittent, describe the discharge schedule: n/a		
<b>END OF PART F</b>		
<b>REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.</b>		

MO 780-1805 (09-08)

MSD, Fenton Wastewater Treatment Facility  
2012 NPDES Permit Renewal  
B2 Application Attachments

**7.1 Brief Description of Facilities**

Outfall #001 - POTW - SIC #4952 – NAICS #221320

Fine screens, lift station, grit removal, primary clarifier, aeration tank, final clarifiers, ultraviolet disinfection, sludge belt filter press, polymer system for sludge dewatering, ferrous chloride and biofilter for odor control, high water effluent pump station, sludge is hauled to other MSD facilities, landfilled, or land applied.

Design population equivalent is 67,500.

Design flow is 6.75 MGD per day.

Actual flow is 4.9 MGD per day.

Design sludge production is 2570 dry tons/year.


Outfall #S1

Instream monitoring, upstream of Outfall #001.

Outfall #S2

Instream monitoring, ¼ mile downstream of Outfall #001.


MSD, Fenton WWTF  
Topographic Map




☆ Outfall #001 (approximate location)  
~ Surface water  
There are no springs or drinking wells within 1/4 mile radius of the treatment plant property.

0.5 mi  
1 mi  
Scale

 **MSD, Fenton**  
**Wastewater Treatment Plant**  
Facility Diagram



**MSD, Fenton**  
**Wastewater Treatment Plant**  
 Process Flow Diagram



The average daily flow passes through the fine screen, grit chamber, and the primary clarifier. Flow is evenly split between the two parshall flumes and all flow passes through the aeration tank. All flow is evenly split between the two final clarifiers. Normal daily flow is evenly split between two of the three UV disinfection units. The third unit is kept for standby use and wet weather flows.

**7.7 Does any bypassing occur anywhere in the collection system or at the treatment facility?**

MSD is conducting SSES investigations, capacity investigations and master planning to evaluate feasible wet weather peak flow management alternatives pursuant to the consent decree entered in the matter titled United States et al. v. The Metropolitan St. Louis Sewer District, No. 4:07-CV-1120 (E.D. Mo.).

### **9.8 Person Responsible for Hauling Sludge to the Disposal Facility**

MSD, Grand Glaize Treatment Plant  
Todd Heller  
1000 Grand Glaize Parkway  
Valley Park, MO 63088  
(636) 861-6700

Merrell Bros. Inc.  
6400 McKissock Ave  
St. Louis, MO 63147-2828  
(314) 381-2600

### **9.9 Sludge Use or Disposal Facility**

IESI Champ Landfill  
Mitch Stepro  
PO Box 2501  
Maryland Heights, MO 63043  
(314) 344-0070  
MO-0097543

MSD, Lemay WWTF  
Neil Frankenberg  
201 Hoffmeister Avenue  
St. Louis, MO 63125  
(314) 638-5190  
MO-0025151

MSD, Bissell Point WWTF  
Cathy Arnold  
10 East Grand Avenue  
St. Louis, MO 63147  
(314) 436-8749  
MO-0025178

Milam Landfill  
Scott Cornell, Sr.  
601 E. Madison Ave  
E. St. Louis, IL 62201  
(618) 271-6788  
1630450001

### 10. Downstream Landowners

The following table lists the downstream landowners in order from first to furthest downstream of the WWTP effluent outfall (#001) on the south side and then north side of the Meramec River. Also see Attachment 10 – MSD, Fenton WWTF: Downstream Land Owners

No.	Property Owner	Property Address	Owner Mailing Address
1	St. Louis County	231 Allen Rd., Fenton, 63026	41 S Central Ave., Saint Louis, 63105
2	St. Louis County	401 Allen Rd., Fenton, 63026	41 S Central Ave., Saint Louis, 63105
3	St. Louis County	269 Allen Rd., Fenton, 63026	41 S Central Ave., Saint Louis, 63105
4	Winter Brothers Materialco Corp	13144 Gravois Rd., Saint Louis, 63127	13098 Gravois Rd Saint Louis, MO 63127
5	Winter, George, Jr., et al	13094 Gravois Rd Saint Louis, MO 63127	12663 Elnore Dr Saint Louis, MO 63128
6	Winter, George, Jr., Gloria, et al	13088 Gravois Rd Saint Louis, MO 63127	12663 Elnore Dr Saint Louis, MO 63128
7	Bush Family Properties LLC	12920 Gravois Rd Saint Louis, MO 63127	Po Box 29509 Saint Louis, MO 63126
8	Marlo, David & Jeanne	12719 Mentz Hill Rd Saint Louis, MO 63128	11420 Gravois Rd Saint Louis, MO 63126

Attachment 10  
(Fulfills part of mapping requirements of 7.2)

**MSD, Fenton WWTF  
Downstream Land Owners**



Base Map Courtesy of St. Louis County, MO Government

Refer to Attachment 10 for downstream property owners' information

## **20. INFLOW AND INFILTRATION**

**Estimate the average number of gallons per day that flow into the treatment works from inflow and Infiltration.**

**Gallons per day.**

MSD is currently performing flow monitoring to determine the amount of I/I in the sewer system pursuant to the consent decree entered in the matter titled United States et al. v. The Metropolitan St. Louis Sewer District, No. 4:07-CV-1120 (E.D. Mo.).

**Briefly explain any steps underway or planned to minimize inflow and infiltration.**

MSD is currently performing investigations to determine the sources and cost to reduce I/I pursuant to the consent decree entered in the matter titled United States et al. v. The Metropolitan St. Louis Sewer District, No. 4:07-CV-1120 (E.D. Mo.).

Attachment 20.7  
MSD, Fenton WWTF  
2011 Effluent Analytical Results

	Plant Flow	Winter Temperature	Summer Temperature	Effluent CBOD	Effluent TSS	Effluent Fecal Coliform	Effluent Oil & Grease	Effluent pH	Effluent D.O.	Effluent Ammonia
Date	MGD	deg C	deg C	mg/L	mg/L	#/100ML	mg/L	SU	mg/L	mg/L
# of Samples	363	37	40	157	150	91	12	156	365	154
Minimum	0.07	12	21	1.5	0.5	5	2	7	2.9	0.025
Maximum	16.87	17	26	19	42	82	2	7.5	9.1	13.9
Average	4.97	15	23	2.28	4.14	7.92	2.00		6.12	0.77
Method				5210B	9222D & B.5C	SM 9222D	1664A	EPA 150.1	360.10	SM 4500-NH3 C,D
Detection Limit				3.00	1.00	10.00	4.00		1.00	0.05

Attachment 40.1  
MSD, Fenton WWTF

2011 Effluent Metals Results

	Effluent Arsenic	Effluent Cadmium	Effluent Chromium III	Effluent Chromium VI	Effluent Total Copper	Effluent Lead	Effluent Mercury	Effluent Nickel	Effluent Silver	Effluent Zinc
Average Concentration (ug/L)	< 7	< 4.6	< 8	< 11	< 9	< 15	< 0.45	< 34	< 12	30
Average Loading (lb/d)	< 0.2	< 0.1	< 0.2	< 0.23	< 0.19	< 0.31	< 0.01	< 0.7	< 3	1.24
Analytical Method	SM 3120, 200.7	SM 3120, 200.7	SM 3120, 200.7	SM 3120, 200.7	SM 3120, 200.7	SM 3120, 200.7	245.2	SM 3120, 200.7	SM 3120, 200.7	SM 3120, 200.7
Detection Limit (ug/L)	7	4.6	8	11	9	15	0.45	34	18	30

Metals are sampled quarterly.

## Attachment 40.1 Continued

## MSD, Fenton WWTF

## September 8, 2011 Effluent TTO Results

Analysis	Result Data	Unit	Analysis	Result Data	Unit
1,1 - dichloroethane	<10	ug/L	Butyl Benzyl Phthalate	<10	ug/L
1,1 - dichloroethene	<10	ug/L	Carbon Tetrachloride	<10	ug/L
1,1,1 - trichloroethane	<10	ug/L	Chlordane	<4	ug/L
1,1,2 - trichloroethane	<10	ug/L	Chlorobenzene	<10	ug/L
1,1,2,2 - tetrachloroethane	<10	ug/L	Chloroethane	<10	ug/L
1,2 - dichlorobenzene	<10	ug/L	Chloroform	<10	ug/L
1,2 - dichlorobenzene	<10	ug/L	Chloromethane	<10	ug/L
1,2 - dichloroethane	<10	ug/L	Chrysene	<10	ug/L
1,2 - dichloropropane	<10	ug/L	delta - BHC	<.3	ug/L
1,2 - diphenylhydrazine	<10	ug/L	Dibenzo(a,h)anthracene	<10	ug/L
1,2,4 - trichlorobenzene	<10	ug/L	Dibromochloromethane	<10	ug/L
1,3 - dichlorobenzene	<10	ug/L	Dieldrin	<.1	ug/L
1,3 - dichlorobenzene	<10	ug/L	Diethyl Phthalate	<10	ug/L
1,4 - dichlorobenzene	<10	ug/L	Dimethyl Phthalate	<10	ug/L
1,4 - dichlorobenzene	<10	ug/L	Di-n-butyl phthalate	<10	ug/L
2 - chloroethyl vinyl ether	<10	ug/L	Di-n-octyl phthalate	<10	ug/L
2 - chloronaphthalene	<10	ug/L	Endosulfan Sulfate	<.1	ug/L
2 - chlorophenol	<10	ug/L	Endrin	<.1	ug/L
2 - nitrophenol	<10	ug/L	Endrin Aldehyde	<.1	ug/L
2,4 - dichlorophenol	<10	ug/L	Ethylbenzene	<10	ug/L
2,4 - dimethylphenol	<10	ug/L	Fluoranthene	<10	ug/L
2,4 - dinitrophenol	<200	ug/L	Fluorene	<10	ug/L
2,4 - dinitrotoluene	<10	ug/L	gamma - BHC	<.05	ug/L
2,4,6 - trichlorophenol	<10	ug/L	Heptachlor	<.5	ug/L
2,6 - dinitrotoluene	<10	ug/L	Heptachlor Epoxide	<.05	ug/L
3,3 - dichlorobenzidine	<10	ug/L	Hexachlorobenzene	<10	ug/L
4 - bromophenyl phenyl eth	<10	ug/L	Hexachlorobutadiene	<10	ug/L
4 - chloro-3-methylphenol	<10	ug/L	Hexachlorocyclopentadiene	<10	ug/L
4 - chlorophenyl phenyl eth	<10	ug/L	Hexachloroethane	<10	ug/L
4 - nitrophenol	<25	ug/L	Indeno (1,2,3-cd) pyrene	<10	ug/L
4,4 - DDD	<.1	ug/L	Isophorone	<10	ug/L
4,4 - DDE	<.1	ug/L	Methylene Chloride	<10	ug/L
4,4 - DDT	<.1	ug/L	N - Nitrosodimethylamine	<10	ug/L
4,6 - dinitro-2-methylphenol	<78	ug/L	N - Nitrosodi-n-propylamine	<10	ug/L
Acenaphthene	<10	ug/L	N - Nitrosodiphenylamine	<10	ug/L
Acenaphthylene	<10	ug/L	Naphthalene	<10	ug/L
Acrolein	<10	ug/L	Nitrobenzene	<10	ug/L
Acrylonitrile	<10	ug/L	PCB - 1016	<3	ug/L
Aldrin	<.05	ug/L	PCB - 1221	<2	ug/L
alpha - BHC	<.05	ug/L	PCB - 1232	<30	ug/L
alpha - Endosulfan	<.05	ug/L	PCB - 1242	<1	ug/L
Benzene	<10	ug/L	PCB - 1248	<1	ug/L
Benzidine	<80	ug/L	PCB - 1254	<1	ug/L
Benzo(a)anthracene	<10	ug/L	PCB - 1260	<2	ug/L
Benzo(a)pyrene	<10	ug/L	Pentachlorophenol	<25	ug/L
Benzo(b)fluoranthene	<10	ug/L	Phenanthrene	<10	ug/L
Benzo(g,h,i)perylene	<10	ug/L	Phenol	<10	ug/L
Benzo(k)fluoranthene	<10	ug/L	Pyrene	<10	ug/L
beta - BHC	<5	ug/L	Tetrachloroethene	<10	ug/L
beta - Endosulfan	<.1	ug/L	Toluene	<10	ug/L
Bis(2-chloroethoxy)methane	<10	ug/L	Toxaphene	<5	ug/L
Bis(2-chloroethyl)ether	<10	ug/L	trans - 1,2 - dichloroethene	<10	ug/L
Bis(2-chloroisopropyl)ether	<10	ug/L	Trichloroethene	<10	ug/L
Bis(2-ethylhexyl)phthalate	<10	ug/L	Trichlorofluoromethane	<10	ug/L
Bromodichloromethane	<10	ug/L	Vinyl Chloride	<.6	ug/L
Bromoform	<10	ug/L	Xylene (Total)	<10	ug/L
Bromomethane	<2	ug/L			

All parameters listed above are sampled annually.

Fenton  
 9000084402    FLEMING PHARMACEUTICALS    1733 Gilsinn Dr    Fenton    MO    63026    Manufacturer of pharmaceutical products    SIU    CIU

*Raw Materials:*  
 Water  
 Sugar  
 Sodium chloride

*Product/Service:*  
 Pharmaceuticals

*Discharge Component Info:*

SP	DISCHARGE COMPONENT	PROCESS DESCRIPTION	DISCHARGE IS	STREAM IS	AVG FLOW	UNIT DESC
001	Boiler Blowdown		BATCH	DILUTE	56	Gallons per Day
001	Categorical	439 Sub D PSES (CWF-no)	CONT	REGULATED	7,774	Gallons per Day
001	Plant & Equipment Washdown	warehouse cleaning	BATCH	DILUTE	5	Gallons per Day
001	Regeneration/Reject Water	softener regeneration	BATCH	DILUTE	76	Gallons per Day
002	Regeneration/Reject Water	RO reject	BATCH	DILUTE	1,568	Gallons per Day
002	Laboratory Waste		BATCH	DILUTE	50	Gallons per Day
002	Sanitary		CONT	DILUTE	1,260	Gallons per Day
003	Sanitary		CONT	DILUTE	198	Gallons per Day

**1047270700 RUG DOCTOR**    **MO 63026**    **Detergent Manufacturer/Floor Scrubber Assembler**

*Raw Materials:*  
 Non-ionic surfactant  
 Perfumes  
 Foam reducers  
 Component parts for floor scrubbers

*Product/Service:*  
 Floor and carpet cleaning products  
 Floor scrubbers

*Discharge Component Info:*

SP	DISCHARGE COMPONENT	PROCESS DESCRIPTION	DISCHARGE IS	STREAM IS	AVG FLOW	UNIT DESC
002	Categorical	417 Sub P PSNS	BATCH	REGULATED	600	Gallons per Day
002	Non Categorical Process Waste	Scrubber wash/pump test	BATCH	DILUTE	50	Gallons per Day
002	Regeneration/Reject Water	Softener regeneration	BATCH	DILUTE	400	Gallons per Day
001	Categorical	From 002	BATCH	DILUTE	600	Gallons per Day
001	Non Categorical Process Waste	From 002	BATCH	DILUTE	50	Gallons per Day
001	Regeneration/Reject Water	From 002	BATCH	DILUTE	400	Gallons per Day
001	Sanitary		BATCH	DILUTE	500	Gallons per Day
001	Wastewater From Other Tenants	Currently vacant	CONT	DILUTE	0	Gallons per Day

ACCOUNT NO    INDUSTRY NAME    MAILING ADDRESS    CITY    STATE    ZIP    BUSINESS DESC    SIU

1050699300    SSM ST CLARE HEALTH CENTER    1015 Bowles Ave.    Fenton    MO    63026    Surgery & health care center    SIU

*Raw Materials:*  
 Medical equipment  
 Pharmaceuticals  
 Food  
 Lab reagents  
 Diesel fuel (number 2 fuel oil)

*Product/Service:* Hospital

*Discharge Component Info:*

SP	DISCHARGE COMPONENT	PROCESS DESCRIPTION	DISCHARGE IS	STREAM IS	AVG FLOW	UNIT DESC
001	Sanitary		CONT	DILUTE	20,625	Gallons per Day
001	Non Contact Cooling Water		BATCH	DILUTE	1,330	Gallons per Day
001	Process Waste	surgery & laboratory	CONT	DILUTE	14,440	Gallons per Day
001	Plant & Equipment Washdown	hospital cleaning	CONT	DILUTE	18,175	Gallons per Day
001	Boiler Blowdown		BATCH	DILUTE	280	Gallons per Day
001	Regeneration/Reject Water		BATCH	DILUTE	540	Gallons per Day
001	Kitchen Waste		BATCH	DILUTE	11,700	Gallons per Day

1049750100    SURGICAL INSTRUMENT MANUFACTURERS INC    1533B Larkin Williams Road    Fenton    MO    63026    Surgical instrument manufacturers    SIU    CIU

*Raw Materials:* Stainless Steel    *Product/Service:* Surgical instruments

*Discharge Component Info:*

SP	DISCHARGE COMPONENT	PROCESS DESCRIPTION	DISCHARGE IS	STREAM IS	AVG FLOW	UNIT DESC
901	Categorical	433 Sub A PSNS	BATCH	REGULATED	60	Gallons per Day
001	Sanitary		CONT	DILUTE	520	Gallons per Day
001	Categorical	From SP 901	BATCH	DILUTE	60	Gallons per Day
001	Wastewater From Other Tenants	sanitary only	CONT	DILUTE	100	Gallons per Day

