

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES

MISSOURI CLEAN WATER COMMISSION



MISSOURI STATE OPERATING PERMIT

In compliance with the Missouri Clean Water Law, (Chapter 644 R.S. Mo. as amended, hereinafter, the Law), and the Federal Water Pollution Control Act (Public Law 92-500, 92nd Congress) as amended,

Permit No. MO-0100200

Owner: City of Richmond
Address: 205 Summit, Richmond, MO 64085

Continuing Authority: Same as above
Address: Same as above

Facility Name: Richmond South Wastewater Treatment Plant
Facility Address: South Wellington, Richmond, MO 64085

Legal Description: NW¼, SE¼, Sec. 6, T51N, R27W, Ray County
UTM Coordinates: X= 416526, Y= 4345601

Receiving Stream: tributary to Willow Creek (U)
First Classified Stream and ID: Willow Creek (C) (0381)
USGS Basin & Sub-watershed No.: (10300101-0801)

is authorized to discharge from the facility described herein, in accordance with the effluent limitations and monitoring requirements as set forth herein:


FACILITY DESCRIPTION

Outfall #001 – POTW – SIC #4952

The use or operation of this facility shall be by or under the supervision of a Certified “B” Operator.
Sequencing Batch Reactor/oxidation ditch/equalization basin/ultraviolet disinfection /sludge storage tanks/solids storage pad/belt filter press/sludge is land applied
Design population equivalent is 7,299
Design flow is 2.0 MGD
Actual flow is 1.382 MGD
Design sludge production is 215 dry tons/year

This permit authorizes only wastewater discharges under the Missouri Clean Water Law and the National Pollutant Discharge Elimination System; it does not apply to other regulated areas. This permit may be appealed in accordance with Section 621.250 RSMo, Section 640.013 RSMo and Section 644.051.6 of the Law.

January 1, 2014
Effective Date


Sara Parker Pauley, Director, Department of Natural Resources

September 30, 2018
Expiration Date


John Madros, Director, Water Protection Program

OUTFALL #001	TABLE A-1 INTERIM EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS			PAGE NUMBER 2 of 8		
				PERMIT NUMBER MO-0100200		
The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The interim effluent limitations shall become effective upon issuance and remain in effect through December 31, 2015 . Such discharges shall be controlled, limited and monitored by the permittee as specified below:						
EFFLUENT PARAMETER(S)	UNITS	INTERIM EFFLUENT LIMITATIONS			MONITORING REQUIREMENTS	
		DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Flow	MGD	*		*	once/weekday***	24 hr. total
Biochemical Oxygen Demand ₅	mg/L		45	30	once/week	24 hr. composite**
Total Suspended Solids	mg/L		45	30	once/week	24 hr. composite**
<i>E. coli</i> (Note 1, Page 2)	#/100 ml		1030	206	once/week	grab
pH – Units	SU	****		****	once/week	grab
Ammonia as N	mg/L	*		*	once/week	grab
Oil & Grease	mg/L	15		10	once/week	grab
MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u> ; THE FIRST REPORT IS DUE <u>FEBRUARY 28, 2014</u> . THERE SHALL BE NO DISCHARGE OF FLOATING SOLIDS OR VISIBLE FOAM IN OTHER THAN TRACE AMOUNTS.						
Whole Effluent Toxicity (WET) test	% Survival	See Special Condition #19		once/year	24-hr Composite**	
<u>WET TEST</u> REPORTS SHALL BE SUBMITTED <u>ANNUALLY</u> ; THE FIRST REPORT IS DUE <u>OCTOBER 28, 2014</u> .						

* Monitoring requirement only.

** A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

*** Once each weekday means: Monday, Tuesday, Wednesday, Thursday, and Friday.

**** pH is measured in pH units and is not to be averaged. The pH is limited to the range of 6.5-9.0 pH units.

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a 30-day geometric mean. The Weekly Average for *E. coli* will be expressed as a 7-day geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

OUTFALL #001	TABLE A-2 FINAL EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS				PAGE NUMBER 3 of 8	
					PERMIT NUMBER MO-0100200	
The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The final effluent limitations shall become effective upon January 1, 2016 , and remain in effect until expiration of the permit. Such discharges shall be controlled, limited and monitored by the permittee as specified below:						
EFFLUENT PARAMETER(S)	UNITS	FINAL EFFLUENT LIMITATIONS			MONITORING REQUIREMENTS	
		DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Flow	MGD	*		*	once/weekday***	24 hr. total
Biochemical Oxygen Demand ₅	mg/L		30	20	once/week	24 hr. composite**
Total Suspended Solids	mg/L		30	20	once/week	24 hr. composite**
<i>E. coli</i> (Note 1, Page 3)	#/100 ml		1030	206	once/week	grab
pH – Units	SU	****		****	once/week	grab
Ammonia as N (April 1 – Sept 30)	mg/L	5.6		1.3	once/week	grab
(Oct 1 – March 31)		12.1		2.4		
Oil & Grease	mg/L	15		10	once/week	grab
MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u> ; THE FIRST REPORT IS DUE <u>FEBRUARY 28, 2016</u> . THERE SHALL BE NO DISCHARGE OF FLOATING SOLIDS OR VISIBLE FOAM IN OTHER THAN TRACE AMOUNTS.						
Whole Effluent Toxicity (WET) test	% Survival	See Special Condition #19			once/year	24 hr. composite**
<u>WET TEST</u> REPORTS SHALL BE SUBMITTED <u>ANNUALLY</u> ; THE FIRST REPORT IS DUE <u>OCTOBER 28, 2014</u> .						

* Monitoring requirement only.

** A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.

*** Once each weekday means: Monday, Tuesday, Wednesday, Thursday, and Friday.

**** pH is measured in pH units and is not to be averaged. The pH is limited to the range of 6.5-9.0 pH units.

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a 30-day geometric mean. The Weekly Average for *E. coli* will be expressed as a 7-day geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

<p style="text-align: center;">TABLE B INFLUENT MONITORING REQUIREMENTS</p>		PAGE NUMBER 4 of 8	
		PERMIT NUMBER MO-0100200	
<p>The facility is required to meet a removal efficiency of 85% or more as a monthly average. The monitoring requirements shall become effective upon issuance and remain in effect until expiration of the permit. To determine removal efficiencies, the influent wastewater shall be monitored by the permittee as specified below:</p>			
SAMPLING LOCATION AND PARAMETER(S)	UNITS	MONITORING REQUIREMENTS	
		MEASUREMENT FREQUENCY	SAMPLE TYPE
Biochemical Oxygen Demand ₅	mg/L	once/week*****	grab
Total Suspended Solids	mg/L	once/week*****	grab
<p>MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u>; THE FIRST REPORT IS DUE <u>FEBRUARY 28, 2014</u>.</p>			

C. STANDARD CONDITIONS

In addition to specified conditions stated herein, this permit is subject to the attached Parts I, II, & III standard conditions dated November 1, 2013, May 1, 2013, and August 15, 1994, and hereby incorporated as though fully set forth herein.

D. SPECIAL CONDITIONS

1. This permit establishes final ammonia limitations based on Missouri’s current Water Quality Standard. On August 22, 2013, the U.S. Environmental Protection Agency (EPA) published a notice in the Federal Register announcing of the final national recommended ambient water quality criteria for protection of aquatic life from the effects of ammonia in freshwater. The EPA's guidance, Final Aquatic Life Ambient Water Quality Criteria for Ammonia – Fresh Water 2013, is not a rule, nor automatically part of a state's water quality standards. States must adopt new ammonia criteria consistent with EPA’s published ammonia criteria into their water quality standards that protect the designated uses of the water bodies. The Department of Natural Resources intends to adopt the new ammonia criteria during the next water quality standards triennial review. Also, refer to Section VI of this permit’s factsheet for further information including estimated future effluent limits for this facility. It is recommended the permittee view the Department’s 2013 EPA criteria Factsheet located at <http://dnr.mo.gov/pubs/pub2481.pdf>.
2. This permit may be reopened and modified, or alternatively revoked and reissued, to:
 - (a) Comply with any applicable effluent standard or limitation issued or approved under Sections 301(b)(2)(C) and (D), 304(b)(2), and 307(a) (2) of the Clean Water Act, if the effluent standard or limitation so issued or approved:
 - (1) contains different conditions or is otherwise more stringent than any effluent limitation in the permit; or
 - (2) controls any pollutant not limited in the permit.
 - (b) Incorporate new or modified effluent limitations or other conditions, if the result of a waste load allocation study, toxicity test or other information indicates changes are necessary to assure compliance with Missouri’s Water Quality Standards.
 - (c) Incorporate new or modified effluent limitations or other conditions if, as the result of a watershed analysis, a Total Maximum Daily Load (TMDL) limitation is developed for the receiving waters which are currently included in Missouri’s list of waters of the state not fully achieving the state’s water quality standards, also called the 303(d) list.
 - (d) Incorporate the requirement to develop a pretreatment program pursuant to 40 CFR 403.8(a) when the Director of the Water Protection Program determines that a pretreatment program is necessary due to any new introduction of pollutants into the Publically Owned Treatment Works or any substantial change in the volume or character of pollutants being introduced.

The permit as modified or reissued under this paragraph shall also contain any other requirements of the Clean Water Act then applicable.

3. All outfalls must be clearly marked in the field.
4. Permittee will cease discharge by connection to a facility with an area-wide management plan per 10 CSR 20-6.010(3)(B) within 90 days of notice of its availability.

D. SPECIAL CONDITIONS (continued)

5. Water Quality Standards

- (a) To the extent required by law, discharges to waters of the state shall not cause a violation of water quality standards rule under 10 CSR 20-7.031, including both specific and general criteria.
- (b) General Criteria. The following general water quality criteria shall be applicable to all waters of the state at all times including mixing zones. No water contaminant, by itself or in combination with other substances, shall prevent the waters of the state from meeting the following conditions:
 - (1) Waters shall be free from substances in sufficient amounts to cause the formation of putrescent, unsightly or harmful bottom deposits or prevent full maintenance of beneficial uses;
 - (2) Waters shall be free from oil, scum and floating debris in sufficient amounts to be unsightly or prevent full maintenance of beneficial uses;
 - (3) Waters shall be free from substances in sufficient amounts to cause unsightly color or turbidity, offensive odor or prevent full maintenance of beneficial uses;
 - (4) Waters shall be free from substances or conditions in sufficient amounts to result in toxicity to human, animal or aquatic life;
 - (5) There shall be no significant human health hazard from incidental contact with the water;
 - (6) There shall be no acute toxicity to livestock or wildlife watering;
 - (7) Waters shall be free from physical, chemical or hydrologic changes that would impair the natural biological community;
 - (8) Waters shall be free from used tires, car bodies, appliances, demolition debris, used vehicles or equipment and solid waste as defined in Missouri's Solid Waste Law, section 260.200, RSMo, except as the use of such materials is specifically permitted pursuant to section 260.200-260.247.

6. Changes in Discharges of Toxic Substances

The permittee shall notify the Director as soon as it knows or has reason to believe:

- (a) That any activity has occurred or will occur which would result in the discharge of any toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
 - (1) One hundred micrograms per liter (100 µg/L);
 - (2) Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,5 dinitrophenol and for 2-methyl-4, 6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
 - (3) Five (5) times the maximum concentration value reported for the pollutant in the permit application;
 - (4) The level established by the Director in accordance with 40 CFR 122.44(f).
- (b) That they have begun or expect to begin to use or manufacture as an intermediate or final product or byproduct any toxic pollutant, which was not reported in the permit application.

7. Report as no-discharge when a discharge does not occur during the report period.

8. It is a violation of the Missouri Clean Water Law to fail to pay fees associated with this permit (644.055 RSMo).

9. The permittee shall comply with any applicable requirements listed in 10 CSR 20-9, unless the facility has received written notification that the Department has approved a modification to the requirements. The monitoring frequencies contained in this permit shall not be construed by the permittee as a modification of the monitoring frequencies listed in 10 CSR 20-9. If a modification of the monitoring frequencies listed in 10 CSR 20-9 is needed, the permittee shall submit a written request to the department for review and, if deemed necessary, approval.

10. The permittee shall submit a report annually in January to the Kansas City Regional Office with the Discharge and Monitoring reports which address measures taken to locate and eliminate sources of infiltration and inflow into the collection system serving the facility for the previous year.

11. Bypasses are not authorized at this facility and are subject to 40 CFR 122.41(m). If a bypass occurs, the permittee shall report in accordance to 40 CFR 122.41(m)(3)(i), and with Standard Condition Part I, Section B, subsection 2.b. Bypasses are to be reported to the Kansas City Regional Office.

12. The facility must be sufficiently secured to restrict entry by children, livestock and unauthorized persons as well as to protect the facility from vandalism.

D. SPECIAL CONDITIONS (continued)

13. A least one gate must be provided to access the wastewater treatment facility and provide for maintenance and mowing. The gate shall remain closed except when temporarily opened by; the permittee to access the facility, perform operational monitoring, sampling, maintenance, mowing, or for inspections by the Department. The gate shall be closed and locked when the facility is not staffed.
14. At least one (1) warning sign shall be placed on each side of the facility enclosure in such positions as to be clearly visible from all directions of approach. There shall also be one (1) sign placed for every five hundred feet (500') (150 m) of the perimeter fence. A sign shall also be placed on each gate. Minimum wording shall be SEWAGE TREATMENT FACILITY—KEEP OUT. Signs shall be made of durable materials with characters at least two inches (2") high and shall be securely fastened to the fence, equipment or other suitable locations.
15. An Operation and Maintenance (O & M) manual shall be maintained by the permittee and made available to the operator. The O & M manual shall include key operating procedures and a brief summary of the operation of the facility.
16. An all-weather access road shall be provided to the treatment facility.
17. The discharge from the wastewater treatment facility shall be conveyed to the receiving stream via a closed pipe or a paved or rip-rapped open channel. Sheet or meandering drainage is not acceptable. The outfall sewer shall be protected against the effects of floodwater, ice or other hazards as to reasonably insure its structural stability and freedom from stoppage. The outfall shall be maintained so that a sample of the effluent can be obtained at a point after the final treatment process and before the discharge mixes with the receiving waters.
18. Land application of biosolids shall be conducted in accordance with Standard Conditions III and a Department approved biosolids management plan. Land application of biosolids during frozen, snow covered, or saturated soil conditions in accordance with the additional requirements specified in WQ426 shall occur only with prior notification to the Kansas City Regional Office.
19. Whole Effluent Toxicity (WET) Test shall be conducted as follows:

SUMMARY OF ACUTE WET TESTING FOR THIS PERMIT				
OUTFALL	AEC	FREQUENCY	SAMPLE TYPE	MONTH
001	100%	once/year	24 hr. composite*	September

* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampler.

DILUTION SERIES							
AEC%	100% effluent	50% effluent	25% effluent	12.5% effluent	6.25% effluent	(Control) 100% upstream, if available	(Control) 100% Lab Water, also called synthetic water

- (a) Test Schedule and Follow-Up Requirements
 - (1) Perform a MULTIPLE-dilution acute WET test in the months and at the frequency specified above. For tests which are successfully passed, submit test results using the Department's WET test report form #MO-780-1899 along with complete copies of the test reports as received from the laboratory, including copies of chain-of-custody forms within 30 calendar days of availability to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102. If the effluent passes the test, do not repeat the test until the next test period.
 - (i) Chemical and physical analysis of the upstream control and effluent sample shall occur immediately upon being received by the laboratory, prior to any manipulation of the effluent sample beyond preservation methods consistent with federal guidelines for WET testing that are required to stabilize the sample during shipping.
 - (ii) Any and all chemical or physical analysis of the effluent sample performed in conjunction with the WET test shall be performed at the 100% Effluent concentration in addition to analysis performed upon any other effluent concentration.
 - (iii) All chemical analyses included in the Missouri Department of Natural Resources WET test report form #MO-780-1899 shall be performed and results shall be recorded in the appropriate field of the report form.

D. SPECIAL CONDITIONS (continued)

- (2) The WET test will be considered a failure if mortality observed in effluent concentrations for either specie, equal to or less than the AEC, is significantly different (at the 95% confidence level; $p = 0.05$) than that observed in the upstream receiving-water control sample. Where upstream receiving water is not available, synthetic laboratory control water may be used.
 - (3) All failing test results along with complete copies of the test reports as received from the laboratory, INCLUDING THOSE TESTS CONDUCTED UNDER CONDITION (3) BELOW, shall be reported to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102 within 14 calendar days of the availability of the results.
 - (4) If the effluent fails the test for BOTH test species, a multiple dilution test shall be performed for BOTH test species within 30 calendar days and biweekly thereafter (for storm water, tests shall be performed on the next and subsequent storm water discharges as they occur, but not less than 7 days apart) until one of the following conditions are met: Note: Written request regarding single species multiple dilution accelerated testing will be address by THE WATER PROTECTION PROGRAM on a case by case basis.
 - (i) THREE CONSECUTIVE MULTIPLE-DILUTION TESTS PASS. No further tests need to be performed until next regularly scheduled test period.
 - (ii) A TOTAL OF THREE MULTIPLE-DILUTION TESTS FAIL.
 - (5) Follow-up tests do not negate an initial failed test.
 - (6) The permittee shall submit a summary of all test results for the test series along with complete copies of the test reports as received from the laboratory to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102 within 14 calendar days of the third failed test.
 - (7) Additionally, the following shall apply upon failure of the third follow up MULTIPLE DILUTION test The permittee should contact THE WATER PROTECTION PROGRAM within 14 calendar days from availability of the test results to ascertain as to whether a TIE or TRE is appropriate. If the permittee does not contact THE WATER PROTECTION PROGRAM upon the third follow up test failure, a toxicity identification evaluation (TIE) or toxicity reduction evaluation (TRE) is automatically triggered. The permittee shall submit a plan for conducting a TIE or TRE to the WATER PROTECTION PROGRAM within 60 calendar days of the date of the automatic trigger or DNR's direction to perform either a TIE or TRE. This plan must be approved by DNR before the TIE or TRE is begun. A schedule for completing the TIE or TRE shall be established in the plan approval.
 - (8) Upon DNR's approval, the TIE/TRE schedule may be modified if toxicity is intermittent during the TIE/TRE investigations. A revised WET test schedule may be established by DNR for this period.
 - (9) If a previously completed TIE has clearly identified the cause of toxicity, additional TIEs will not be required as long as effluent characteristics remain essentially unchanged and the permittee is proceeding according to a DNR approved schedule to complete a TRE and reduce toxicity. Regularly scheduled WET testing as required in the permit, without the follow-up requirements, will be required during this period.
 - (10) When WET test sampling is required to run over one DMR period, each DMR report shall contain a copy of the Department's WET test report form that was generated during the reporting period.
 - (11) Submit a concise summary in tabular format of all WET test results with the annual report.
- (b) Test Conditions
- (1) Test Type: Acute Static non-renewal
 - (2) All tests, including repeat tests for previous failures, shall include both test species listed below unless approved by the department on a case by case basis.
 - (3) Test species: Ceriodaphnia dubia and Pimephales promelas (fathead minnow). Organisms used in WET testing shall come from cultures reared for the purpose of conducting toxicity tests and cultured in a manner consistent with the most current USEPA guidelines. All test animals shall be cultured as described in the most current edition of Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms.
 - (4) Test period: 48 hours at the "Allowable Effluent Concentration" (AEC) specified above.
 - (5) Upstream receiving stream water shall be used as dilution water. If upstream water is unavailable or if mortality in the upstream water exceeds 10%, "reconstituted" water will be used as dilution water. Procedures for generating reconstituted water will be supplied by the MDNR upon request.
 - (6) Tests will be run with 100% receiving-stream water (if available), collected upstream of the outfall at a point beyond any influence of the effluent, and reconstituted water.
 - (7) If reconstituted-water control mortality for a test species exceeds 10%, the entire test will be rerun.

D. SPECIAL CONDITIONS (continued)

- (8) If upstream control mortality exceeds 10%, the entire test will be rerun using reconstituted water as the dilutant.
- (9) Whole-effluent-toxicity test shall be consistent with the most current edition of Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms

E. SCHEDULE OF COMPLIANCE

The facility shall attain compliance with final effluent limitations as soon as reasonably achievable or no later than **2 years** of the effective date of this permit. The **2 year SOC** is given to allow the facility to complete the construction of the combined sewer system.

1. The permittee shall submit interim progress reports detailing progress made in attaining compliance with the final effluent limits every 12 months from issuance date.
2. Within **2 years** of the effective date of this permit, the permittee shall attain compliance with the final effluent limits.

Please submit progress reports to the Missouri Department of Natural Resources, Kansas City, Regional Office, 500 NE Colburn Road, Lee's Summit, Missouri, 64086.

**MISSOURI DEPARTMENT OF NATURAL RESOURCES
FACT SHEET
FOR THE PURPOSE OF RENEWAL
OF
MO-0100200
RICHMOND SOUTH WWTF**

The Federal Water Pollution Control Act ("Clean Water Act" Section 402 Public Law 92-500 as amended) established the National Pollution Discharge Elimination System (NPDES) permit program. This program regulates the discharge of pollutants from point sources into the waters of the United States, and the release of storm water from certain point sources. All such discharges are unlawful without a permit (Section 301 of the "Clean Water Act"). After a permit is obtained, a discharge not in compliance with all permit terms and conditions is unlawful. Missouri State Operating Permits (MSOPs) are issued by the Director of the Missouri Department of Natural Resources (Department) under an approved program, operating in accordance with federal and state laws (Federal "Clean Water Act" and "Missouri Clean Water Law" Section 644 as amended). MSOPs are issued for a period of five (5) years unless otherwise specified.

As per [40 CFR Part 124.8(a)] and [10 CSR 20-6.020(1)2.] a Factsheet shall be prepared to give pertinent information regarding the applicable regulations, rationale for the development of effluent limitations and conditions, and the public participation process for the Missouri State Operating Permit (operating permit) listed below.

A Factsheet is not an enforceable part of an operating permit.

This Factsheet is for:

Major

Part I – Facility Information

Facility Type: POTW - SIC #4952

Facility Description:

Sequencing Batch Reactor/oxidation ditch/equalization basin/ultraviolet disinfection /sludge storage tanks/solids storage pad/belt filter press/sludge is land applied

Have any changes occurred at this facility or in the receiving water body that effects effluent limit derivation?

Yes; This facility will replace the Richmond North WWTP. The North facility has installed new screening structure, a new pump station and force main to the Richmond South WWTF. The South WWTP has installed a bar screen, flow equalization basin, pump station, flow splitter, sequencing batch reactor, UV system, sludge holding tank, and sludge dewatering equipment.

Application Date: 01/23/2012

Expiration Date: 07/19/2012

OUTFALL(S) TABLE:

OUTFALL	DESIGN FLOW (CFS)	TREATMENT LEVEL	EFFLUENT TYPE
#001	3.09	Secondary	Domestic

Facility Performance History:

This facility was last inspected on July 27, 2011. The conditions of the facility at the time of inspection were found to be satisfactory.

Comments:

No comments received during the Public Notice period.

Part II – Operator Certification Requirements

Applicable; This facility is required to have a certified operator.

As per [10 CSR 20-6.010(8) Terms and Conditions of a Permit], permittees shall operate and maintain facilities to comply with the Missouri Clean Water Law and applicable permit conditions and regulations. Operators or supervisors of operations at regulated wastewater treatment facilities shall be certified in accordance with [10 CSR 20-9.020(2)] and any other applicable state law or regulation. As per [10 CSR 20-9.020(2)(A)], requirements for operation by certified personnel shall apply to all wastewater treatment systems, if applicable, as listed below:

Check boxes below that are applicable to the facility;

Owned or operated by or for:

Municipalities

Each of the above entities are only applicable if they have a Population Equivalent greater than two hundred (200) and/or fifty (50) or more service connections.

The Department requires this facility to retain the services of a certified operator due to status as a POTW

This facility currently requires an operator with a B Certification Level. Please see **Appendix A - Classification Worksheet**. Modifications made to the wastewater treatment facility may cause the classification to be modified.

Operator’s Name: Dale A. Shipp
 Certification Number: 9852
 Certification Level: A

The listing of the operator above only signifies that staff drafting this operating permit have reviewed appropriate Department records and determined that the name listed on the operating permit application has the correct and applicable Certification Level.

Part III– Operational Monitoring

As per [10 CSR 20-9.010(4)], the facility is required to conduct operational monitoring.

Part IV – Receiving Stream Information

10 CSR 20-7.031 Missouri Water Quality Standards, the Department defines the Clean Water Commission water quality objectives in terms of "water uses to be maintained and the criteria to protect those uses." The receiving stream and/or 1st classified receiving stream’s beneficial water uses to be maintained are located in the Receiving Stream Table located below in accordance with [10 CSR 20-7.031(3)].

RECEIVING STREAM(S) TABLE: OUTFALL #001

WATER-BODY NAME	CLASS	WBID	DESIGNATED USES*	12-DIGIT HUC	DISTANCE TO CLASSIFIED SEGMENT (MI)
tributary to Willow Creek	U	-	General Criteria	10300101-0801	
Willow Creek	C	381	LLW, AQL, WBC(B)		

* - Irrigation (IRR), Livestock & Wildlife Watering (LWW), Protection of Warm Water Aquatic Life and Human Health-Fish Consumption (AQL), Cool Water Fishery(CLF), Cold Water Fishery (CDF), Whole Body Contact Recreation (WBC), Secondary Contact Recreation (SCR), Drinking Water Supply (DWS), Industrial (IND), Groundwater (GRW).

RECEIVING STREAM(S) LOW-FLOW VALUES:

RECEIVING STREAM (U, C, P)	LOW-FLOW VALUES (CFS)		
	1Q10	7Q10	30Q10
tributary to Willow Creek	0.0	0.0	0.0

MIXING CONSIDERATIONS

Mixing Zone: Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(a)].

Zone of Initial Dilution: Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(b)].

Receiving Water Body's Water Quality

No water quality issues were found.

Part V – Rationale and Derivation of Effluent Limitations & Permit Conditions

ALTERNATIVE EVALUATIONS FOR NEW FACILITIES:

As per [10 CSR 20-7.015(4)(A)], discharges to losing streams shall be permitted only after other alternatives including land application, discharges to a gaining stream and connection to a regional wastewater treatment facility have been evaluated and determined to be unacceptable for environmental and/or economic reasons.

Not Applicable; The facility does not discharge to a Losing Stream as defined by [10 CSR 20-2.010(36)] & [10 CSR 20-7.031(1)(N)], or is an existing facility.

ANTI-BACKSLIDING:

A provision in the Federal Regulations [CWA §303(d)(4); CWA §402(c); 40 CFR Part 122.44(I)] that requires a reissued permit to be as stringent as the previous permit with some exceptions.

All limits in this operating permit are at least as protective as those previously established; therefore, backsliding does not apply.

ANTIDegradation:

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(2)], the Department is to document by means of Antidegradation Review that the use of a water body's available assimilative capacity is justified. Degradation is justified by documenting the socio-economic importance of a discharging activity after determining the necessity of the discharge.

New and/or expanded discharge, please see **APPENDIX B – ANTIDegradation ANALYSIS**.

AREA-WIDE WASTE TREATMENT MANAGEMENT & CONTINUING AUTHORITY:

As per [10 CSR 20-6.010(3)(B)], ...An applicant may utilize a lower preference continuing authority by submitting, as part of the application, a statement waiving preferential status from each existing higher preference authority, providing the waiver does not conflict with any area-wide management plan approved under section 208 of the Federal Clean Water Act or any other regional sewage service and treatment plan approved for higher preference authority by the Department.

BIOSOLIDS & SEWAGE SLUDGE:

Biosolids are solid materials resulting from domestic wastewater treatment that meet federal and state criteria for beneficial uses (i.e. fertilizer). Sewage sludge is solids, semi-solids, or liquid residue generated during the treatment of domestic sewage in a treatment works; including but not limited to, domestic septage; scum or solids removed in primary, secondary, or advanced wastewater treatment process; and a material derived from sewage sludge. Sewage sludge does not include ash generated during the firing of sewage sludge in a sewage sludge incinerator or grit and screening generated during preliminary treatment of domestic sewage in a treatment works. Additional information regarding biosolids and sludge is located at the following web address: <http://dnr.mo.gov/env/wpp/pub/index.html>, items WQ422 through WQ449.

Permittee land applies biosolids in accordance with Standard Conditions III and a Department approved biosolids management plan.

COMPLIANCE AND ENFORCEMENT:

Enforcement is the action taken by the Water Protection Program (WPP) to bring an entity into compliance with the Missouri Clean Water Law, its implementing regulations, and/or any terms and conditions of an operating permit. The primary purpose of the enforcement activity in the WPP is to resolve violations and return the entity to compliance.

Not Applicable; The permittee/facility is not currently under Water Protection Program enforcement action.

PRETREATMENT PROGRAM:

The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to or in lieu of discharging or otherwise introducing such pollutants into a Publicly Owned Treatment Works [40 CFR Part 403.3(q)].

Not Applicable; The permittee, at this time, is not required to have a Pretreatment Program or does not have an approved pretreatment program.

REASONABLE POTENTIAL ANALYSIS (RPA):

Federal regulation [40 CFR Part 122.44(d)(1)(i)] requires effluent limitations for all pollutants that are or may be discharged at a level that will cause or have the reasonable potential to cause or contribute to an in-stream excursion above narrative or numeric water quality standard.

In accordance with [40 CFR Part 122.44(d)(iii)] if the permit writer determines that any given pollutant has the reasonable potential to cause, or contribute to an in-stream excursion above the WQS, the permit must contain effluent limits for that pollutant.

Applicable; A RPA was conducted on appropriate parameters. Please see **APPENDIX B – RPA RESULTS**.

REMOVAL EFFICIENCY:

Removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD₅) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals.

Applicable; Secondary Treatment is 85% removal [40 CFR Part 133.102(a)(3) & (b)(3)].

SANITARY SEWER OVERFLOWS (SSO) AND INFLOW AND INFILTRATION (I&I):

Sanitary Sewer Overflows (SSOs) are defined as an untreated or partially treated sewage release are considered bypassing under state regulation [10 CSR 20-2.010(11)] and should not be confused with the federal definition of bypass. SSO's have a variety of causes including blockages, line breaks, and sewer defects that allow excess storm water and ground water to (1) enter and overload the collection system, and (2) overload the treatment facility. Additionally, SSO's can be also be caused by lapses in sewer system operation and maintenance, inadequate sewer design and construction, power failures, and vandalism. SSOs also include overflows out of manholes and onto city streets, sidewalks, and other terrestrial locations.

Additionally, Missouri RSMo §644.026.1 mandates that the Department require proper maintenance and operation of treatment facilities and sewer systems and proper disposal of residual waste from all such facilities.

In accordance with Missouri RSMo §644.026.1.(15) and 40 CFR Part 122.41(e), the permittee is required to develop and/or implement a program for maintenance and repair of the collection system and shall be required in this operating permit by either means of a Special Condition or Schedule of Compliance. In addition, the Department considers the development of this program as an implementation of this condition. Additionally, 40 CFR Part 403.3(o) defines a POTW to include any device and systems used in the storage, treatment, recycling and reclamation of municipal sewage or industrial wastes of liquid nature. It also includes sewers, pipes, and other conveyances only if they convey wastewater to a POTW Treatment Plant.

At this time, the Department recommends the US EPA's Guide for Evaluating Capacity, Management, Operation and Maintenance (CMOM) Programs At Sanitary Sewer Collection Systems (Document # EPA 305-B-05-002). The CMOM identifies some of the criteria used by the EPA to evaluate a collection system's management, operation, and maintenance and was intended for use by the EPA, state, regulated community, and/or third party entities. The CMOM is applicable to small, medium, and large systems; both public and privately owned; and both regional and satellite collection systems. The CMOM does not substitute for the Clean Water Act, the Missouri Clean Water Law, and both federal and state regulations, as it is not a regulation.

SCHEDULE OF COMPLIANCE (SOC):

A schedule of remedial measures included in a permit, including an enforceable sequence of interim requirements (actions, operations, or milestone events) leading to compliance with the Missouri Clean Water Law, its implementing regulations, and/or the terms and conditions of an operating permit.

A SOC is not allowed:

- For effluent limitations based on technology-based standards established in accordance with federal requirements, if the deadline for compliance established in federal regulations has passed. 40 CFR § 125.3.
- For a newly constructed facility in most cases. Newly constructed facilities must meet applicable effluent limitations when discharge begins, because the facility has installed the appropriate control technology as specified in a permit or antidegradation review. A SOC is allowed for a new water quality based effluent limit that was not included in a previously public noticed permit or antidegradation review, which may occur if a regulation changes during construction.
- To develop a TMDL, UAA, or other study associated with development of a site specific criterion. A facility is not prohibited from conducting these activities, but a SOC may not be granted for conducting these activities.

In order to provide guidance to Permit Writers in developing SOCs, and attain a greater level of consistency, on October 25, 2012 the department issued a policy on development of SOCs. This policy provides guidance to Permit Writers on the standard time frames for schedules for common activities, and guidance on factors that may modify the length of the schedule such as an affordability analysis.

Applicable; The time given for effluent limitations of this permit listed under Interim Effluent Limitation and Final Effluent Limitations were established in accordance with [10 CSR 20-7.031(10)]. The facility has been given a schedule of compliance to meet final effluent limits for Ammonia.

STORM WATER POLLUTION PREVENTION PLAN (SWPPP):

In accordance with 40 CFR 122.44(k) *Best Management Practices (BMPs)* to control or abate the discharge of pollutants when:

(1) Authorized under section 304(e) of the Clean Water Act (CWA) for the control of toxic pollutants and hazardous substances from ancillary industrial activities; (2) Authorized under section 402(p) of the CWA for the control of storm water discharges; (3) Numeric effluent limitations are infeasible; or (4) the practices are reasonably necessary to achieve effluent limitations and standards or to carry out the purposes and intent of the CWA.

Not Applicable; At this time, the permittee is not required to develop and implement a SWPPP.

VARIANCE:

As per the Missouri Clean Water Law § 644.061.4, variances shall be granted for such period of time and under such terms and conditions as shall be specified by the commission in its order. The variance may be extended by affirmative action of the commission. In no event shall the variance be granted for a period of time greater than is reasonably necessary for complying with the Missouri Clean Water Law §§644.006 to 644.141 or any standard, rule or regulation promulgated pursuant to Missouri Clean Water Law §§644.006 to 644.141.

Not Applicable; This operating permit is not drafted under premises of a petition for variance.

WASTELOAD ALLOCATIONS (WLA) FOR LIMITS:

As per [10 CSR 20-2.010(78)], the amount of pollutant each discharger is allowed by the Department to release into a given stream after the Department has determined total amount of pollutant that may be discharged into that stream without endangering its water quality.

Applicable; Wasteload allocations were calculated where applicable using water quality criteria or water quality model results and the dilution equation below:

$$C_e = \frac{(Q_e + Q_s)C - (C_s \times Q_s)}{Q_e} \quad (\text{EPA/505/2-90-001, Section 4.5.5})$$

- Where
- C = downstream concentration
 - C_s = upstream concentration
 - Q_s = upstream flow
 - C_e = effluent concentration
 - Q_e = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

Number of Samples "n":

Additionally, in accordance with the TSD for water quality-based permitting, effluent quality is determined by the underlying distribution of daily values, which is determined by the Long Term Average (LTA) associated with a particular Wasteload Allocation (WLA) and by the Coefficient of Variation (CV) of the effluent concentrations. Increasing or decreasing the monitoring frequency does not affect this underlying distribution or treatment performance, which should be, at a minimum, be targeted to comply with the values dictated by the WLA. Therefore, it is recommended that the actual planned frequency of monitoring normally be used to determine the value of "n" for calculating the AML. However, in situations where monitoring frequency is once per month or less, a higher value for "n" must be assumed for AML derivation purposes. Thus, the statistical procedure being employed using an assumed number of samples is "n = 4" at a minimum. For Total Ammonia as Nitrogen, "n = 30" is used.

WLA MODELING:

There are two general types of effluent limitations, technology-based effluent limits (TBELs) and water quality based effluent limits (WQBELs). If TBELs do not provide adequate protection for the receiving waters, then WQBEL must be used.

Not Applicable; A WLA study was either not submitted or determined not applicable by Department staff.

WATER QUALITY STANDARDS:

Per [10 CSR 20-7.031(3)], General Criteria shall be applicable to all waters of the state at all times including mixing zones. Additionally, [40 CFR 122.44(d)(1)] directs the Department to establish in each NPDES permit to include conditions to achieve water quality established under Section 303 of the Clean Water Act, including State narrative criteria for water quality.

WHOLE EFFLUENT TOXICITY (WET) TEST:

A WET test is a quantifiable method of determining if a discharge from a facility may be causing toxicity to aquatic life by itself, in combination with or through synergistic responses when mixed with receiving stream water.

Applicable; Under the federal Clean Water Act (CWA) §101(a)(3), requiring WET testing is reasonably appropriate for site-specific Missouri State Operating Permits for discharges to waters of the state issued under the National Pollutant Discharge Elimination System (NPDES). WET testing is also required by 40 CFR 122.44(d)(1). WET testing ensures that the provisions in the 10 CSR 20-6.010(8)(A)7. and the Water Quality Standards 10 CSR 20-7.031(3)(D),(F),(G),(I)2.A & B are being met. Under [10 CSR 20-6.010(8)(A)4], the Department may require other terms and conditions that it deems necessary to assure compliance with the Clean Water Act and related regulations of the Missouri Clean Water Commission. In addition the following MCWL apply: §§644.051.3 requires the Department to set permit conditions that comply with the MCWL and CWA; 644.051.4 specifically references toxicity as an item we must consider in writing permits (along with water quality-based effluent limits, pretreatment, etc...); and 644.051.5 is the basic authority to require testing conditions. WET test will be required by facilities meeting the following criteria:

Facility is a designated Major.

Facility is a municipality or domestic discharger with a Design Flow \geq 22,500 gpd.

40 CFR 122.41(M) - BYPASSES:

The federal Clean Water Act (CWA), Section 402 prohibits wastewater dischargers from "bypassing" untreated or partially treated sewage (wastewater) beyond the headworks. A bypass is defined as an intentional diversion of waste streams from any portion of a treatment facility, [40 CFR 122.41(m)(1)(i)]. Additionally, Missouri regulation 10 CSR 20-2.010(11) defines a bypass as the diversion of wastewater from any portion of wastewater treatment facility or sewer system to waters of the state. Only under exceptional and specified limitations do the federal regulations allow for a facility to bypass some or all of the flow from its treatment process. Bypasses are prohibited by the CWA unless a permittee can meet all of the criteria listed in 40 CFR 122.41(m)(4)(i)(A), (B), & (C). Any bypasses from this facility are subject to the reporting required in 40 CFR 122.41(l)(6) and per Missouri's Standard Conditions I, Section B, part 2.b. Additionally, Anticipated Bypasses include bypasses from peak flow basins or similar devices designed for peak wet weather flows.

Applicable; Bypasses occur or have occurred at this facility.

303(d) LIST & TOTAL MAXIMUM DAILY LOAD (TMDL):

Section 303(d) of the federal Clean Water Act requires that each state identify waters that are not meeting water quality standards and for which adequate water pollution controls have not been required. Water quality standards protect such beneficial uses of water as whole body contact (such as swimming), maintaining fish and other aquatic life, and providing drinking water for people, livestock and wildlife. The 303(d) list helps state and federal agencies keep track of waters that are impaired but not addressed by normal water pollution control programs.

A TMDL is a calculation of the maximum amount of a given pollutant that a body of water can absorb before its water quality is affected. If a water body is determined to be impaired as listed on the 303(d) list, then a watershed management plan will be developed that shall include the TMDL calculation

Not Applicable; This facility does not discharge to a 303(d) listed stream.

Part VI –2013 Water Quality Criteria for Ammonia

Upcoming changes to the Water Quality Standard for ammonia may require significant upgrades to wastewater treatment facilities.

On August 22, 2013, the U.S. Environmental Protection Agency (EPA) finalized new water quality criteria for ammonia, based on toxicity studies of mussels. Missouri's current ammonia criteria are based on toxicity testing of several species, but did not include data from mussels. Missouri is home to 65 of North America's mussel species, which are spread across the state. According to the Missouri Department of Conservation nearly two-thirds of the mussel species in Missouri are considered to be "of conservation concern". Nine species are listed as federally endangered, with an additional species currently proposed as endangered and another species proposed as threatened.

The adult forms of mussels that are seen in rivers, lakes, and streams are sensitive to pollutants because they are sedentary filter feeders. They vacuum up many pollutants with the food they bring in and cannot escape to new habitats, so they can accumulate toxins in their bodies and die. But very young mussels, called glochidia, are exceptionally sensitive to ammonia in water. As a result of a citizen suit, the EPA was compelled to conduct toxicity testing and develop ammonia water quality criteria that would be protective if young mussels may be present in a waterbody. These new criteria will apply to any discharge with ammonia levels that may pose a reasonable potential to violate the standards. Nearly all discharging domestic wastewater treatment facilities (cities, subdivisions, mobile home parks, etc.), as well as certain industrial and stormwater dischargers with ammonia in their effluent, will be affected by this change in the regulations.

When new water quality criteria are established by the EPA, states must adopt them into their regulations in order to keep their authorization to issue permits under the National Pollutant Discharge Elimination System (NPDES). States are required to review their water quality standards every three years, and if new criteria have been developed they must be adopted. States may be more protective than the Federal requirements, but not less protective. Missouri does not have the resources to conduct the studies necessary for developing new water quality standards, and therefore our standards mirror those developed by the EPA; however, we will utilize any available flexibility based on actual species of mussels that are native to Missouri and their sensitivity to ammonia.

Many treatment facilities in Missouri are currently scheduled to be upgraded to comply with the current water quality standards. But these new ammonia standards may require a different treatment technology than the one being considered by the permittee. It is important that permittee discuss any new and upcoming requirements with their consulting engineers to ensure that their treatment systems are capable of complying with the new requirements. The Department encourages permittee to construct treatment technologies that can attain effluent quality that supports the EPA ammonia criteria.

Ammonia toxicity varies by temperature and by pH of the water. Assuming a stable pH value, but taking into account winter and summer temperatures, Missouri includes two seasons of ammonia effluent limitations. Current effluent limitations in this permit are:

Summer – 5.6 mg/L daily maximum, 1.3 mg/L monthly average.

Winter – 12.1 mg/L daily maximum, 2.4 mg/L monthly average.

Under the new EPA criteria, where mussels of the family Unionidae are present or expected to be present, your estimated effluent limitations will be:

Summer – 1.7 mg/L daily maximum, 0.6 mg/L monthly average.

Winter – 5.6 mg/L daily maximum, 2.1 mg/L monthly average.

Actual effluent limits will depend in part on the actual performance of the facility.

Operating permits for facilities in Missouri must be written based on current statutes and regulations. It is expected that the new WQS will be adopted in the next review of our standards. Therefore permits will be written with the existing effluent limitations until the new standards are adopted. To aid permittee in decision making, an advisory will be added to permit Fact Sheets notifying permittee of the expected effluent limitations for ammonia. When setting schedules of compliance for ammonia effluent limitations, consideration will be given to facilities that have recently constructed upgraded facilities to meet the current ammonia limitations.

For more information on this topic feel free to contact the Missouri Department of Natural Resources, Water Protection Program, Water Pollution Control Branch, Operating Permits Section at (573) 751-1300.

Part VII – Effluent Limits Determination

APPLICABLE DESIGNATIONS OF WATERS OF THE STATE:

As per Missouri’s Effluent Regulations [10 CSR 20-7.015], the waters of the state are divided into the below listed seven (7) categories. Each category lists effluent limitations for specific parameters, which are presented in each outfall’s Effluent Limitation Table and further discussed in the Derivation & Discussion of Limits section.

All Other Waters [10 CSR 20-7.015(8)]

OUTFALL #001 – MAIN FACILITY OUTFALL

Effluent limitations derived and established in the below Effluent Limitations Table are based on current operations of the facility. Future permit action due to facility modification may contain new operating permit terms and conditions that supersede the terms and conditions, including effluent limitations, of this operating permit.

EFFLUENT LIMITATIONS TABLE:

PARAMETER	Unit	Basis for Limits	Daily Maximum	Weekly Average	Monthly Average	Modified	Previous Permit Limitations
Flow	MGD	1	*		*	NO	*/*
BOD ₅	mg/L	1		30	20	YES	45/30
TSS	mg/L	1		30	20	YES	45/30
pH	SU	1	6.5 to 9.0			YES	6.0 to 9.0
Ammonia as N (April 1 – Sept 30) (Oct 1 – March 31)	mg/L	2, 3, 5	5.6 12.1		1.3 2.4	YES	*/* */*
Escherichia coli	**	1, 3		1030	206	NO	***
Oil & Grease (mg/L)	mg/L	1, 3	15		10	YES	***
Whole Effluent Toxicity (WET) Test	% Survival	11	Please see WET Test in the Derivation and Discussion Section below.				

* - Monitoring requirement only.

** - # of colonies/100mL; the Monthly Average for *E. coli* is a geometric mean.

*** - Parameter not previously established in previous state operating permit.

Basis for Limitations Codes:

- | | |
|--|------------------------------------|
| 1. State or Federal Regulation/Law | 7. Antidegradation Policy |
| 2. Water Quality Standard (includes RPA) | 8. Water Quality Model |
| 3. Water Quality Based Effluent Limits | 9. Best Professional Judgment |
| 4. Lagoon Policy | 10. TMDL or Permit in lieu of TMDL |
| 5. Ammonia Policy | 11. WET Test Policy |
| 6. Antidegradation Review | |

OUTFALL #001 – DERIVATION AND DISCUSSION OF LIMITS:

- **Flow.** In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the Department, which may require the submittal of an operating permit modification.
- **Biochemical Oxygen Demand (BOD₅).** 30 mg/L as a Weekly Average and 20 mg/L as a Monthly Average. Please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information**.
- **Total Suspended Solids (TSS).** 30 mg/L as a Weekly Average and 20 mg/L as a Monthly Average. Please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information**.

- **pH.** Effluent limitation range is 6.5 to 9.0 Standard pH Units (SU), as per the applicable section of 10 CSR 20-7.015. pH is not to be averaged.
- **Total Ammonia Nitrogen.** Early Life Stages Present Total Ammonia Nitrogen criteria apply [10 CSR 20-7.031(4)(B)7.C. & Table B3] default pH 7.8 SU Background total ammonia nitrogen = 0.01 mg/L.

Season	Temp (°C)	pH (SU)	Total Ammonia Nitrogen CCC (mg/L)	Total Ammonia Nitrogen CMC (mg/L)
Summer	26	7.8	1.5	12.1
Winter	6	7.8	3.1	12.1

Summer

$$C_e = (((Q_e + Q_s) * C) - (Q_s * C_s)) / Q_e$$

Chronic WLA: $C_e = 1.5 \text{ mg/L}$
Acute WLA: $C_e = 12.1 \text{ mg/L}$

$LTA_c = 1.5 \text{ mg/L} (0.576) = 0.86 \text{ mg/L}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L} (0.153) = 1.85 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

MDL = $0.86 \text{ mg/L} (6.54) = 5.6 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
AML = $0.86 \text{ mg/L} (1.46) = 1.3 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

Winter

Chronic WLA: $C_e = 3.1 \text{ mg/L}$
Acute WLA: $C_e = 12.1 \text{ mg/L}$

$LTA_c = 3.1 \text{ mg/L} (0.483) = 1.5 \text{ mg/L}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L} (0.121) = 1.46 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

MDL = $1.46 \text{ mg/L} (8.27) = 12.1 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
AML = $1.46 \text{ mg/L} (1.65) = 2.4 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

The proposed effluent limits provided in the Antidegradation Report were the same as the calculated water quality based effluent limits.

- **Escherichia coli (E. coli).** Monthly average of 206 per 100 ml as a 30-day geometric mean and Weekly Average of 1030 as a 7-day geometric mean during the recreational season (April 1 – October 31), to protect Whole Body Contact Recreation (B) designated use of the receiving stream, as per 10 CSR 20-7.031(4)(C). An effluent limit for both monthly average and weekly average is required by 40 CFR 122.45(d).
- **Oil & Grease.** Conventional pollutant, effluent limitation for protection of aquatic life; 10 mg/L monthly average, 15 mg/L daily maximum.
- **WET Test.** WET Testing schedules and intervals are established in accordance with the Department’s Permit Manual; Section 5.2 *Effluent Limits / WET Testing for Compliance Bio-monitoring*. It is recommended that WET testing be conducted during the period of lowest stream flow.

Acute

No less than **ONCE/YEAR:**

Facility is designated as a Major facility or has a design flow $\geq 1.0 \text{ MGD}$.

Acute and/or Chronic Allowable Effluent Concentrations (AECs) for facilities that discharge to unclassified, Class C, Class P (with default Mixing Considerations), or Lakes [10 CSR 20-7.031(4)(A)4.B.(IV)(b)] are 100%, 50%, 25%, 12.5%, & 6.25%.

Minimum Sampling and Reporting Frequency Requirements.

PARAMETER	SAMPLING FREQUENCY	REPORTING FREQUENCY
Flow	once/day	once/month
BOD ₅	once/week	once/month
TSS	once/week	once/month
pH	once/week	once/month
Ammonia as N	once/week	once/month
<i>E. coli</i>	once/week	once/month
Oil & Grease	once/week	once/month

Sampling Frequency Justification:

This facility is a new facility. Sampling is required to determine if the facility will be in compliance with the operating permit in accordance with Appendix U of Missouri's Water Pollution Control Permit Manual. Except for flow, weekly sampling is required per 10 CSR 20-7.015.

Sampling Type Justification

As per 10 CSR 20-7.015, samples collected for mechanical plants shall be 24 hour composite samples.

Sampling Type Justification

As per 10 CSR 20-7.015, BOD₅, TSS, and WET test samples collected for mechanical plants shall be a 24 hour composite sample. Grab samples, must be collected for pH, Ammonia as N, *E. coli*, and Oil & Grease.. This is due to the holding time restriction for *E. coli*, the volatility of Ammonia, and the fact that pH and DO cannot be preserved and must be sampled in the field. As Ammonia and Oil & Grease samples must be immediately preserved with acid, these samples are to be collected as a grab.

Part VIII – Finding of Affordability

Pursuant to Section 644.145, RSMo., the Department is required to determine whether a permit or decision is affordable and makes a finding of affordability for certain permitting and enforcement decisions. This requirement applies to discharges from combined or separate sanitary sewer systems or publically-owned treatment works.

Applicable; The Department is required to determine findings of affordability because the permit applies to a **combined or separate sanitary sewer system for a publically-owned treatment works.**

Finding of affordability - The department has made a reasonable search for empirical data indicating the permit is affordable. The search consisted of a review of department records that might contain economic data on the community, a review of information provided by the applicant as part of the application, and public comments received in response to public notices of this draft permit. If the empirical cost data was used by the permit writer, this data may consist of median household income, any other ongoing projects that the Department has knowledge, and other demographic financial information that the community provided as contemplated by Section 644. 145.3. See **Appendix C – Affordability Analysis**

Part IX – Administrative Requirements

On the basis of preliminary staff review and the application of applicable standards and regulations, the Department, as administrative agent for the Missouri Clean Water Commission, proposes to issue a permit(s) subject to certain effluent limitations, schedules, and special conditions contained herein and within the operating permit. The proposed determinations are tentative pending public comment.

PERMIT SYNCHRONIZATION:

The Department of Natural Resources is currently undergoing a synchronization process for operating permits. Permits are normally issued on a five-year term, but to achieve synchronization many permits will need to be issued for less than the full five years allowed by regulation. The intent is that all permits within a watershed will move through the Watershed Based Management (WBM) cycle together will all expire in the same fiscal year. This will allow further streamlining by placing multiple permits within a smaller geographic area on public notice simultaneously, thereby reducing repeated administrative efforts. This will also allow the department to explore a watershed based permitting effort at some point in the future.

PUBLIC NOTICE:

The Department shall give public notice that a draft permit has been prepared and its issuance is pending. Additionally, public notice will be issued if a public hearing is to be held because of a significant degree of interest in and water quality concerns related to a draft permit. No public notice is required when a request for a permit modification or termination is denied; however, the requester and permittee must be notified of the denial in writing.

The Department must issue public notice of a pending operating permit or of a new or reissued statewide general permit. The public comment period is the length of time not less than 30 days following the date of the public notice which interested persons may submit written comments about the proposed permit.

For persons wanting to submit comments regarding this proposed operating permit, then please refer to the Public Notice page located at the front of this draft operating permit. The Public Notice page gives direction on how and where to submit appropriate comments.

The Public Notice period for this operating permit was from August 23 to September 23, 2013. No responses received.

DATE OF FACT SHEET: JULY 9, 2013

COMPLETED BY:

JOHNNY E. O'DELL, ENVIRONMENTAL SPECIALIST III
MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM
OPERATING PERMITS SECTION - DOMESTIC WASTEWATER UNIT
(417) 891-4325
johnny.o'dell@dnr.mo.gov

Appendices

APPENDIX A - CLASSIFICATION WORKSHEET:

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
Maximum Population Equivalent (P.E.) served (Max 10 pts.)	1 pt./10,000 PE or major fraction thereof.	1
Maximum: 10 pt Design Flow (avg. day) or peak month; use greater (Max 10 pts.)	1 pt. / MGD or major fraction thereof.	2
EFFLUENT DISCHARGE RECEIVING WATER SENSITIVITY:		
Missouri or Mississippi River	0	
All other stream discharges except to losing streams and stream reaches supporting whole body contact	1	
Discharge to lake or reservoir outside of designated whole body contact recreational area	2	
Discharge to losing stream, or stream, lake or reservoir area supporting whole body contact recreation	3	3
PRELIMINARY TREATMENT – Headworks		
Screening and/or comminution	3	3
Grit removal	3	
Plant pumping of main flow (lift station at the headworks)	3	3
PRIMARY TREATMENT		
Primary clarifiers	5	
Combined sedimentation/digestion	5	
Chemical addition (except chlorine, enzymes)	4	
REQUIRED LABORATORY CONTROL – performed by plant personnel (highest level only)		
Push – button or visual methods for simple test such as pH, Settleable solids	3	
Additional procedures such as DO, COD, BOD, titrations, solids, volatile content	5	
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.	7	7
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph	10	
ALTERNATIVE FATE OF EFFLUENT		
Direct reuse or recycle of effluent	6	
Land Disposal – low rate	3	
High rate	5	
Overland flow	4	
Total from page ONE (1)	----	19

APPENDIX A - CLASSIFICATION WORKSHEET (CONTINUED):

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
VARIATION IN RAW WASTE (highest level only) (DMR exceedances and Design Flow exceedances)		
Variation do not exceed those normally or typically expected	0	
Recurring deviations or excessive variations of 100 to 200 % in strength and/or flow	2	
Recurring deviations or excessive variations of more than 200 % in strength and/or flow	4	
Raw wastes subject to toxic waste discharge	6	
SECONDARY TREATMENT		
Trickling filter and other fixed film media with secondary clarifiers	10	
Activated sludge with secondary clarifiers (including extended aeration and oxidation ditches)	15	15
Stabilization ponds without aeration	5	
Aerated lagoon	8	
Advanced Waste Treatment Polishing Pond	2	
Chemical/physical – without secondary	15	
Chemical/physical – following secondary	10	
Biological or chemical/biological	12	
Carbon regeneration	4	
DISINFECTION		
Chlorination or comparable	5	
Dechlorination	2	
On-site generation of disinfectant (except UV light)	5	
UV light	4	4
SOLIDS HANDLING – SLUDGE		
Solids Handling Thickening	5	
Anaerobic digestion	10	
Aerobic digestion	6	6
Evaporative sludge drying	2	2
Mechanical dewatering	8	8
Solids reduction (incineration, wet oxidation)	12	
Land application	6	6
Total from page TWO (2)	----	41
Total from page ONE (1)	---	19
Grand Total	---	60

- A: 71 points and greater
- B: 51 points – 70 points
- C: 26 points – 50 points
- D: 0 points – 25 points

APPENDIX B – RPA RESULTS:

Parameter	CMC	RWC Acute	CCC	RWC Chronic	n	Max/Min	CV	MF	Potential
Total Ammonia as Nitrogen (Summer) mg/L	12.1	9.94	1.5	9.94	32.00	2.8/0.0014	1.40	3.55	YES
Total Ammonia as Nitrogen (Winter) mg/L	12.1	60.93	3.1	60.93	33.00	13.79/0.0597	1.90	4.42	YES

N/A – Not Applicable

- * - Units are (µg/L) unless otherwise noted.
- ** - If the number of samples is 10 or greater, then the CV value must be used in the WQBEL for the applicable constituent. If the number of samples is < 10, then the default CV value must be used in the WQBEL for the applicable constituent.
- *** - Coefficient of Variation (CV) is calculated by dividing the Standard Deviation of the sample set by the Mean of the same sample set.

RWC – Receiving Water Concentration. It is the concentration of a toxicant or the parameter toxicity in the receiving water after mixing (if applicable).

n – Is the number of samples.

MF – Multiplying Factor. 99% Confidence Level and 99% Probability Basis.

RP – Reasonable Potential. It is where an effluent is projected or calculated to cause an excursion above a water quality standard based on a number of factors including, as a minimum, the four factors listed in 40 CFR 122.44(d)(1)(ii).

Reasonable Potential Analysis is conducted as per (TSD, EPA/505/2-90-001, Section 3.3.2). A more detailed version including calculations of this RPA is available upon request.

APPENDIX C – AFFORDABILITY ANALYSIS:

**Missouri Department of Natural Resources
Water Protection Program
Affordability Determination and Finding
(In accordance with RSMo 644.145)**

**Richmond South WWTF
City of Richmond
Missouri State Operating Permit #MO-0100200**

Section 644.145 RSMo requires DNR to make a “finding of affordability” when “issuing permits under” or “enforcing provisions of” state or federal clean water laws “pertaining to any portion of a combined or separate sanitary sewer system for publicly-owned treatment works.”

Facility Description:

Sequencing Batch Reactor/oxidation ditch/equalization basin/ultraviolet disinfection /sludge storage tanks/solids storage pad/belt filter press/sludge is land applied

Receiving Stream: tributary to Willow Creek (U)
First Classified Stream and ID: Willow Creek (C) (0381)
USGS Basin & Sub-watershed No.: (10300101-0801)

Residential Connections:	<u>2,926</u>
Commercial Connections:	<u>263</u>
Total Connections: ¹	<u>3,189</u>

New Permit Requirements or Requirements Now Being Enforced:

Permit No. #MO-0100200 expired on July 19, 2013. The department received an application for renewal on January 23, 2012. The proposed new permit requirements may require the design, construction and operation of new technology. The south facility is being required to; upgrade to meet effluent limitations for Ammonia as N, pH, Oil & Grease, and E. coli, conduct a Whole Effluent Toxicity Test once per year cycle, submit a written plan to reduce Inflow and Infiltration in the collection system, and submit an annual report that documents the findings of the work accomplished during the previous year for the targeted area(s) and note which inflow/infiltration problems were corrected. The north facility will be converted to a pump station to convey the flow to the south facility, thus eliminating a discharge point.

Range of Anticipated Costs Associated with Complying with the New Requirements:

As the facility will be required to upgrade to meet effluent limitations, estimated costs for four different treatment types to comply with the requirements, range from \$11,703,618 to \$17,405,502 ⁶. The estimated costs depend on the treatment type selected by the facility. Assumptions in these calculations include but are not limited to; interest rate, design life of the facility, inflation factor, administration labor costs, and laboratory labor costs. Other options that may be available to the facility but not reviewed during the review include no-discharge land application and connection to an available facility with an area-wide management plan.

(1) A community’s financial capability and ability to raise or secure necessary funding;

In April 2010 the City passed a \$5,100,000 bond and in 2011 a \$4,700,000 bond. The 2011 financial statement for Richmond also indicates the city has an estimated \$400,000-\$600,000 wastewater fund reserve fund. These funds along with a grant and loan from USDA Rural Development and an anticipated CDBG Grant will fund the South WWTP improvements, a lift station to replace the North WWTP and a force main to pump the waste collected at the North WWTP location to the South WWTP for processing. ¹

Current User Rates, inside City limits (base): ¹	<u>\$10.09</u>
Rate Capacity or Pay as You Go Option:	<u>\$7.98/1,000 gal. (prorated)</u>
	<u>\$49.99/5,000 gal.</u>
Current User Rates, outside City limits (base): ¹	<u>\$12.36/1,000 gal. (prorated)</u>
	<u>\$61.80/5,000 gal.</u>
Municipal Bond Rating (if applicable):	<u>A-</u>
Bonding Capacity:	<u>\$9,606,331</u>
<i>(General Obligation Bond capacity allowed by constitution: cities=up to 20% of taxable tangible property sewer districts=up to 5% of taxable tangible property)</i>	
Current outstanding debt:	<u>\$8,350,000</u>
Other indicators:	

In April 2010 the City passed a \$5,100,000 bond and in 2011 a \$4,700,000 bond. The 2011 financial statement for Richmond also indicates the city has an estimated \$400,000-\$600,000 wastewater fund reserve fund. These funds along with a grant and loan from USDA Rural Development and an anticipated CDBG Grant will fund the South WWTP improvements, a lift station to replace the North WWTP and a force main to pump the waste collected at the North WWTP location to the South WWTP for processing. ¹

(2) Affordability of pollution control options for the individuals or households of the community:

Current annual operating costs (exclude depreciation):	<u>\$300,000</u>
Current annual user rate ¹ :	<u>\$610.56</u>
Estimated capital cost of pollution control options:	<u>\$10,998,200</u>
Annual cost of additional <i>(operating costs and debt service)</i> :	<u>n/a</u>
Estimated resulting User Rate and/or Cost per Household:	<u>\$50.88</u>
Median Household Income:	<u>\$38,269</u>
Rate and/or Cost per Household as a Percent of Median Household Income:	<u>1.6%</u>

(Rate or Cost/MHI) Check Appropriate Box	Financial Impact	Residential Indicatory (Cost or Usage Rate as a percent of Median Household)
<input type="checkbox"/>	Low	Less than 1% MHI
<input checked="" type="checkbox"/>	Medium	Between 1% and 2% MHI
<input type="checkbox"/>	High	Greater than 2% MHI

The Department calculated that a 5,000 gallon per month residential user currently pays approximately \$50.88 per month, based on the sewer rate information contained on the Richmond website. With the additional costs of upgrading the facility to meet effluent limitations a rate increase would be necessary. The approximate monthly user rate would increase to \$55.25 depending on which treatment option is chosen by the facility, which is about 1.7% of the MHI. This would result in a medium financial impact to the users. ¹

(3) An evaluation of the overall costs and environmental benefits of the control technologies:

Ammonia (NH3) is toxic to aquatic life and can damage habitat for ammonia sensitive species. Removal of NH3 is beneficial to the environment because this can reduce damage to aquatic life in accordance with 10 CSR 20-7 and the Clean Water Act. Removal can enable the stream habitat to support a more healthy and diverse population of aquatic life. This facility has Ammonia as N final effluent limitations based on the Water Quality Standards (WQS) found in the above citation. The facility would be contributing to the reduction of damage to aquatic life by reducing effluent ammonia levels.

The expansion of the South WWTP will eliminate the outfall at the North WWTP by regionalizing the two existing treatment plants into one. The south plant is under enforcement due to illegal discharge and pollution to waters of the state. Eliminating this discharge will eliminate future permit violations. This project also includes upgrade to provide disinfection to protect the designated use of whole body contact.

(4) An inclusion of ways to reduce economic impacts on distressed populations in the community, including but not limited to, low and fixed income populations. This requirement includes but is not limited to:

(a) Allowing adequate time in implementation schedules to mitigate potential adverse impacts on distressed populations resulting from the costs of the improvements and taking into consideration local community economic considerations; and

(b) Allowing for reasonable accommodations for regulated entities when inflexible standards and fines would impose a disproportionate financial hardship in light of the environmental benefits to be gained.

Potentially Distressed Populations for – Richmond

Unemployment	10.5%
Median Household Income	38,269
Percentage Change in Median Household Income (1990–2010)	41.9%
Percentage Population Growth/Decline (1990-2010)	1%
Change in Median Age in Years (1990-2010)	4.2
Percent of Households in Poverty	12.7%
Percent of Households Relying on Food Stamps	11.8%

Opportunity for cost savings or cost avoidance: “None Noted”
Opportunity for changes to implementation/compliance schedule: “None Noted”

(5) An assessment of other community investments relating to environmental improvements:

“None Noted”

(6) An assessment of factors set forth in the United States Environmental Protection Agency's guidance, including but not limited to the "Combined Sewer Overflow Guidance for Financial Capability Assessment and Schedule Development" that may ease the cost burdens of implementing wet weather control plans, including but not limited to, small system considerations, the attainability of water quality standards, and the development of wet weather standards:

See Section (2) of this analysis for the residential indicator as outlined in the above-referenced EPA guidance.

Secondary indicators for consideration:

Socioeconomic, Debt and Financial Indicators				
Indicators	Strong (3 points)	Mid-Range (2 points)	Weak (1 point)	Score
Bond rating indicator	Above BBB or Baa	BBB or Baa	Below BBB or Baa	3
Overall net debt as a % of full market property value	Below 2%	2% - 5%	Above 5%	3
Unemployment Rate	>1% below Missouri average	± 1% of Missouri average	>1% above Missouri average	1
Median household income	More than 25% above Missouri MHI	± 25% of Missouri MHI	More than 25% below Missouri average	2
Property tax revenues as a % of full market property value	Below 2%	2% - 4%	Above 4%	2
Property tax collection rate	Above 98%	94% - 98%	Below 94%	3

Average Score for Financial Capability Matrix: 2.33
Residential Indicator (from Criteria #2 above): Medium

Financial Capability Matrix			
Financial Capability Indicators Score from above ↓	Residential Indicator (User rate as a % of MHI)		
	Low (Below 1%)	Mid-Range (Between 1.0% and 2.0%)	High (Above 2.0%)
Weak (below 1.5)	Medium Burden	High Burden	High Burden
Mid-Range (1.5 – 2.5)	Low Burden	Medium Burden	High Burden
Strong (above 2.5)	Low Burden	Low Burden	Medium Burden

Estimated Financial Burden: Medium

(7) An assessment of any other relevant local community economic condition.

Richmond’s population increased 0.99% from 1990-2010. In terms of economic strength, St. Charles County is above average when compared to other counties in the State. The per capita income is 13% below the State’s average.⁵

Conclusion and Finding

This affordability analysis finds that the actions subject to this analysis are affordable. The Department identified the actions for which an affordability analysis is required under Section 644.145 RSMo. The City of Richmond, Missouri applied for a construction permit for Missouri State Operating Permit #MO-0100200. Changes to the permit include:

- a. Increase the design flow to 2.0 MGD.
- b. Establishing effluent limitations for E-coli.
- c. Establishing effluent limitations for Ammonia as N.
- d. Establishing effluent limitations for Oil and Grease.
- e. Changing effluent limitations for BOD and TSS.
- f. Changing effluent limitation range for pH of 6.5-9.0 pH units.
- g. Establishing weekly testing frequency for effluent parameters.
- h. Establishing a Whole Effluent Toxicity Test to be conducted once per year.
- i. Requiring the facility to submit an annual report on measures taken to locate and eliminate sources of infiltration and inflow into the collection system.

The Department considered all seven (7) of the criteria presented in subsection 644.145.3 when evaluating the affordability of the relevant actions. Taking into consideration these criteria, this analysis examined whether the above referenced permit modifications affects the ability of an individual customer or household to pay a utility bill without undue hardship or unreasonable sacrifice in the essential lifestyle or spending patterns of the individual or household. As a result of reviewing the above criteria, the Department hereby finds that the action described above will result in a medium burden with regard to the community’s overall financial capability and a medium financial impact for most individual customers/households.

Reference

¹ City of Richmond, Missouri – <http://cityofrichmondmo.org/finance.html#top>

² Unemployment data from Missouri Department of Economic Development (December 2012) – <http://www.missourieconomy.org/pdfs/urel1202.pdf>

³ Median Household Income data from American Community Survey – Median income in the past 12 months – <http://factfinder2.census.gov/faces/nav/jsf/pages/searchresults.xhtml?refresh=t>

⁴ 2010 Census Population Data - <http://factfinder2.census.gov/faces/nav/jsf/pages/searchresults.xhtml?refresh=t>
2000 Census Population Data - <http://www.census.gov/popest/data/cities/totals/2009/tables/SUB-EST2009-04-29.xls> 1990 Census Population Data - <http://www.census.gov/prod/cen1990/cp1/cp-1-27.pdf>

⁵ Poverty data – American Community Survey - <http://factfinder2.census.gov/faces/nav/jsf/pages/searchresults.xhtml?refresh=t>

⁶ Pre-screening Tool 11 29 2012.xls

⁷ <http://www.missourieconomy.org/indicators/wages/pci10county.stm>

**Missouri Department of Natural Resources
Water Protection Program
Water Pollution Control Branch
NPDES Permits and Engineering Section**

Water Quality and Antidegradation Review

*For the Protection of Water Quality
and Determination of Effluent Limits for Discharge to the
Unnamed Tributary to Willow Creek*



November 2012

Richmond South Wastewater Treatment Facility
South Wellington
Richmond, MO 64085

Table of Contents

1. Facility Information	3
2. Water Quality Information	3
2.1 WATER QUALITY HISTORY:	3
3. Outfall Characteristics	3
4. Receiving Waterbody Information	3
5. General Comments	4
6. Antidegradation Review Information	4
6.1 TIER DETERMINATION	4
Table 1. Pollutants of Concern and Tier Determination	4
6.2 EXISTING WATER QUALITY	4
6.3 ASSIMILATIVE CAPACITY CALCULATIONS	4
6.4 ALTERNATIVE ANALYSIS	5
TABLE 2. TECHNOLOGY-BASED EFFLUENT LIMITS AND ECONOMIC EFFICIENCY ANALYSIS	5
6.5 DEMONSTRATION OF NECESSITY AND SOCIAL AND ECONOMIC IMPORTANCE	5
6.6 PRELIMINARY DETERMINATION	5
7. General Assumptions of the Water Quality and Antidegradation Review	5
8. Mixing Considerations	6
9. Permit Limits and Information	6
9.1 OUTFALL #001– Main Facility Outfall	6
10. Receiving Water Monitoring Requirements	6
11. Derivation and Discussion of Limits	6
11.1 OUTFALL #001 – Main Facility Outfall – Limit Derivation	7
Appendix A: Map of Discharge Location	9
Appendix B: Antidegradation Review Summary Attachments	10
Appendix C: Dissolved Oxygen Model	Error! Bookmark not defined.

1. FACILITY INFORMATION

FACILITY NAME: Richmond South Wastewater Treatment Plant NPDES #: MO-0100200

FACILITY TYPE/DESCRIPTION: Proposed facility expansion from 475,000 gallons per day to 2.0 million gallons per day. The preferred alternative of the submitted alternatives analysis (AA) was construction of an Sequencing Batch Reactor with ultraviolet disinfection. This project would eliminate the Richmond North WWTP (MO-0021822) with a lift station to the south plant. The facility will discharge into the Unnamed Tributary to Willow Creek. First classified stream is Willow Creek (Location – See Appendix A).

EDU: Central Plains/Blackwater/Lamine ECOREGION: Plains
LEGAL DESCRIPTION: NE¼, SE¼, Sec. 6, T51N, R27W COUNTY: Ray
UTM COORDINATES: X: 416526 Y: 4345601 12-DIGIT HUC: 10300101-0801

2. WATER QUALITY INFORMATION

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(2)] and federal antidegradation policy at Title 40 Code of Federal Regulation (CFR) Section 131.12 (a), the Missouri Department of Natural Resources (MDNR) developed a statewide antidegradation policy and corresponding procedures to implement the policy. A proposed discharge to a water body will be required to undergo a level of Antidegradation Review which documents that the use of a water body's available assimilative capacity is justified. Effective August 30, 2008, a facility is required to use *Missouri's Antidegradation Rule and Implementation Procedure (AIP)* for new and expanded wastewater discharges.

2.1 WATER QUALITY HISTORY:

The existing facility has occasional DMR exceedances: BOD – 1/08, 4/08, and 3/11, and TSS – 1/07, 2/07, 3/07, and 1/08.

3. OUTFALL CHARACTERISTICS

OUTFALL	DESIGN FLOW (CFS)	TREATMENT TYPE	RECEIVING WATERBODY	DISTANCE TO CLASSIFIED SEGMENT
001	3.1	Secondary	tributary to Willow Creek	1.3

4. RECEIVING WATERBODY INFORMATION

WATERBODY	CLASS	WBID	1Q10 (CFS)	7Q10 (CFS)	30Q10 (CFS)	*DESIGNATED USES
tributary to Willow Creek	U	–	–	–	–	General Criteria
Willow Creek	C	0381	0.0	0.0	0.1	LWW, AQL, WBC(B)

*Cool Water Fishery (CLF), Cold Water Fishery (CDF), Irrigation (IRR), Industrial (IND), Boating & Canoeing (BTG), Drinking Water Supply (DWS), Whole Body Contact Recreation (WBC), Protection of Warm water Aquatic Life and Human Health (AQL), Livestock & Wildlife Watering (LWW)

RECEIVING WATER BODY SEGMENT #1: tributary to Willow Creek
Upper end segment* UTM coordinates: X: 416526, Y: 4345601 (Outfall)
Lower end segment* UTM coordinates: X: 416171, Y: 4343925 (Confluence with Willow Creek)

RECEIVING WATER BODY SEGMENT #2: Willow Creek
Upper end segment* UTM coordinates: X: 416171, Y: 4343925 (Confluence with tributary)
Lower end segment* UTM coordinates: X: 422966, Y: 4338595 (Confluence with Missouri River)

*Segment is the portion of the stream where discharge occurs. Segment is used to track changes in assimilative capacity and is bound at a minimum by existing sources and confluences with other significant water bodies.

5. General Comments

Olsson Associates prepared, on behalf of City of Richmond, the *Revised North/South WWTP Antidegradation Report for the City of Richmond* (Report) revised October 17, 2012. The Geohydrological Evaluation states this is a gaining stream setting. A Tier Analysis was submitted by the applicant. A dissolved oxygen modeling analysis was submitted showing that the dissolved oxygen recovers to above 5.0 before the classified stream (Appendix C). This discharge is proposed to serve the City of Richmond with a population of 6,746 along with flows from the City of Henrietta with a population of 553; and assumed to result in significant degradation for all pollutants of concern (POCs) in the unnamed tributary to Willow Creek and Willow Creek.

The effluent limits in this review were developed to be protective of beneficial uses and to retain the remaining assimilative capacity. MDNR has determined that the submitted report is sufficient and meets the requirement of the AIP. Information found in the submitted report and in the summary forms provided by the applicant in Appendix B was used to develop this review document. A Missouri Department of Conservation Natural Heritage Review – Level 1 response was obtained by the applicant.

6. ANTIDEGRADATION REVIEW INFORMATION

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(2)] and federal antidegradation policy at Title 40 Code of Federal Regulation (CFR) Section 131.12 (a), the department was to develop a statewide antidegradation policy and corresponding procedures to implement the policy. A proposed discharge to a water body will be required to undergo a level of Antidegradation Review which documents that the use of a water body's available assimilative capacity is justified. Effective August 30, 2008, a facility is required to use *Missouri's Antidegradation Rule and Implementation Procedure (AIP)*. This procedure is applicable to new and expanded wastewater facilities. The following is a review of the *Revised North/South WWTP Antidegradation Report for the City of Richmond*.

6.1 TIER DETERMINATION

Below is a list of pollutants of concern reasonably expected to be in the discharge (see Appendix B: Tier Determination and Effluent Limit Summary). Pollutants of concern are defined as those pollutants "proposed for discharge that affect beneficial use(s) in waters of the state. POCs include pollutants that create conditions unfavorable to beneficial uses in the water body receiving the discharge or proposed to receive the discharge." (AIP, Page 7).

Table 1 Pollutants of Concern and Tier Determination

POLLUTANTS OF CONCERN	TIER	DEGRADATION	COMMENT
Biochemical Oxygen Demand	2	Significant	*
Total Suspended Solids***	2	Significant	*
pH	2	Significant	**
Ammonia as Nitrogen	2	Significant	
Bacteria (E. Coli)	2	Significant	
Oil And Grease	2	Significant	
Dissolved Oxygen	2	Significant	

* No in-stream standards for these parameters, therefore tier determination was not possible.

** Standards for these parameters are ranges and therefore tier determination was not possible.

*** Narrative criteria.

The following Antidegradation Review Summary attachments in Appendix B were used by the applicant:

Tier Determination and Effluent Summary

For pollutants of concern, the attachments are:

Attachment A, Tier 2 with significant degradation.

Attachment B, Tier 2 with minimal degradation.

Attachment D, Tier 1 Review. Additionally, a Tier 2 review must be conducted for each pollutant of concern on the appropriate water body segment.

6.2 EXISTING WATER QUALITY

No existing water quality data was submitted.

6.3 ASSIMILATIVE CAPACITY CALCULATIONS

This antidegradation review assumed significant degradation for all Pollutants of Concern, so there is no need to calculate the assimilative capacity for this review.

6.4 ALTERNATIVE ANALYSIS

This antidegradation review assumed significant degradation for all Pollutants of Concern, so there is a demonstration of necessity (i.e., alternatives analysis) and a determination of social and economic importance included in the report. Non-degrading alternatives such as land application, subsurface irrigation, or seasonal discharge were considered not practicable due to the large design flow. The report also stated regionalization was not practicable as Richmond is the largest community in the area. If regionalization would happen, Richmond would likely be the provider as it is the largest community and already treats flow from the City of Henrietta. The report also showed the economic efficiency of replacing the North Plant with a lift station and having only one treatment plant. The report included an analysis of four alternatives ranging from less degrading to the degrading alternative (base case alternative). The alternative of upgrading and expanding both existing treatment plants was determined to be not practicable due to the high cost. The less degrading alternatives of an Sequencing Batch Reactor (Base Cost Alternative), Sequencing Batch Reactor with Filtration, Membrane Bioreactor, and Sequencing Batch Reactor with two outfalls (Partial pumping back to existing North location) were considered practicable with the economic efficiency analysis shown in Table 2. All meet Water Quality Standards. The preferred alternative is construction of Sequencing Batch Reactor as it was the base case and preferred alternative as it was the only option that was considered economically efficient. Although the proposed ammonia values in the report included time of travel, those values are replaced with water quality based effluent limits at the end of pipe for the Sequencing Batch Reactor per discussion with the engineer.

TABLE 2. TECHNOLOGY-BASED EFFLUENT LIMITS AND ECONOMIC EFFICIENCY ANALYSIS

DISCHARGING ALTERNATIVES	BOD ₅ (MG/L)	TSS (MG/L)	E. COLI (#/100 ML)	DO (MG/L)	NH ₄ (MG/L)	PRESENT WORTH COST*	% BASE COST
Sequencing Batch Reactor	20	20	206	5	1.4/2.9	\$21,650,800	100% (BASE)
Sequencing Batch Reactor-Filtration	7	7	206	5	1.0/2.5	\$26,379,020	122%
Membrane Bioreactor	3	1	206	5	0.4/0.6	\$34,269,100	158%
Sequencing Batch Reactor-2 Outfalls	18	18	206	5	1.4/2.9	\$27,288,650	126%

* Present Worth Cost: 20 year design life and 5% interest

6.5 DEMONSTRATION OF NECESSITY AND SOCIAL AND ECONOMIC IMPORTANCE

This antidegradation review assumed significant degradation for all Pollutants of Concern, so there is a demonstration of necessity (i.e., alternatives analysis) and a determination of social and economic importance that was included in the report. This facility will provide the wastewater service to accommodate long-term growth within the community. The expanded wastewater treatment plant will eliminate the outfall at the north treatment plant by regionalizing the two existing treatment plants into one. This project will provide capacity for commercial growth along new Highway 10/13 and accommodate growth within the City of Henrietta. This anticipated growth will provide tax revenue within the area. This project also includes upgrade to provide disinfection, which the existing plants do not currently provide.

6.6 PRELIMINARY DETERMINATION

The proposed facility is assumed to result in significant degradation for all POCs in the noted waterbody segments. Olsson Associates assumed significant degradation for the segments mentioned above and provided an alternatives analysis which showed that an Sequencing Batch Reactor would be the most economically efficient and practicable option for treatment. The Social and Economic Importance of the proposed facility will provide much needed capacity for long-term growth for the community and surrounding area. The effluent limits in this review were developed to be protective of beneficial uses and to retain the remaining assimilative capacity. MDNR has determined that the submitted report is sufficient and meets the requirement of the AIP. No further analysis is needed for this discharge.

7. GENERAL ASSUMPTIONS OF THE WATER QUALITY AND ANTIDEGRADATION REVIEW

1. A Water Quality and Antidegradation Review (WQAR) assumes that [10 CSR 20-6.010(3) Continuing Authorities and 10 CSR 20-6.010(4) (D), consideration for no discharge] has been or will be addressed in a Missouri State Operating Permit or Construction Permit Application.
2. A WQAR does not indicate approval or disapproval of alternative analysis as per [10 CSR 20-7.015(4) Losing Streams], and/or any section of the effluent regulations.
3. Changes to Federal and State Regulations made after the drafting of this WQAR may alter Water Quality Based Effluent Limits (WQBEL).
4. Effluent limitations derived from Federal or Missouri State Regulations (FSR) may be WQBEL or Effluent Limit Guidelines (ELG).
5. WQBEL supersede ELG only when they are more stringent. Mass limits derived from technology based limits are still appropriate.
6. A WQAR does not allow discharges to waters of the state, and shall not be construed as a National Pollution Discharge Elimination System or Missouri State Operating Permit to discharge or a permit to construct, modify, or upgrade.

- 7. Limitations and other requirements in a WQAR may change as Water Quality Standards, Methodology, and Implementation procedures change.
- 8. Nothing in this WQAR removes any obligations to comply with county or other local ordinances or restrictions.

8. MIXING CONSIDERATIONS

Mixing Zone (MZ). Not allowed, 7Q10 less than 0.1 cfs [10 CSR 20-7.031(4)(A)4.B.(I)(a)].
Zone of Initial Dilution (ZID). Not allowed [10 CSR 20-7.031(4)(A)5.B.(IV)(b)].

9. PERMIT LIMITS AND INFORMATION

TMDL WATERSHED: N (Y OR N) W.L.A. STUDY CONDUCTED: N (Y OR N) DISINFECTION REQUIRED: Y (Y OR N) USE ATTAINABILITY ANALYSIS: N (Y OR N)

9.1 OUTFALL #001– Main Facility Outfall

WET TEST (Y OR N): N FREQUENCY: N/A A.E.C. 100% METHOD: N/A

PARAMETER	UNITS	DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	WQBEL (NOTE 1)	MONITORING FREQUENCY
FLOW	MGD	*		*	FSR	Once/Day
BIOCHEMICAL OXYGEN DEMAND (BOD ₅)	MG/L		30	20	PAL	Once/Week
TOTAL SUSPENDED SOLIDS	MG/L		30	20	PAL	Once/Week
pH	SU	6.5 – 9.0		6.5 – 9.0	FSR	Once/Week
<i>ESCHERICHIA COLI (E. COLI)</i>	**		1030	206***	FSR	Once/Week
AMMONIA AS N (APRIL 1- SEPT 30)	MG/L	3.7		1.4	PAL/ WQBEL	Once/Week
AMMONIA AS N (OCT 1 – MARCH 30)	MG/L	7.5		2.9	PAL/ WQBEL	Once/Week
OIL AND GREASE	MG/L	15		10	FSR	Once/Week

Note 1– Water Quality-based Effluent Limitation --WQBEL; or Minimally Degrading Effluent Limit--MDEL; or Technology-based Effluent Limit--TBEL; or No Degradation Limit--NDL; or PAL—Preferred Alternative Effluent Limit; or FSR --Federal/State Regulation; or N/A--Not Applicable. Also, please see the **General Assumptions of the WQAR #4 & #5.**

- * – Monitoring Requirement Only
- ** – colonies/100 mL
- *** – The Monthly Average for E. coli shall be reported as a Geometric Mean.

10. RECEIVING WATER MONITORING REQUIREMENTS

No receiving water monitoring requirements recommended at this time.

11. DERIVATION AND DISCUSSION OF LIMITS

Wasteload allocations were calculated using water quality criteria or water quality model results and the dilution equation below:

$$C = \frac{(Cs \times Qs) + (Ce \times Qe)}{(Qe + Qs)} \quad \text{(EPA/505/2-90-001, Section 4.5.5)}$$

- Where
- C = downstream concentration
 - Cs = upstream concentration
 - Qs = upstream flow
 - Ce = effluent concentration
 - Qe = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA’s “Technical Support Document For Water Quality-based Toxics Control” (EPA/505/2-90-001).

11.1 OUTFALL #001 – Main Facility Outfall – Limit Derivation

- **Flow.** In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the department, which may require the submittal of an operating permit modification.
- **Biochemical Oxygen Demand (BOD₅).** Preferred alternative effluent limits: 20 mg/L monthly average. Proposed limit of 20 mg/l was provided by applicant in the Antidegradation Report. To derive the Monthly Daily Maximum (MDL), the average monthly limit was multiplied by 1.5, thus the MDL = 30 mg/l. Influent monitoring may be required for this facility in its Missouri State Operating Permit.
- **Total Suspended Solids (TSS).** Preferred alternative effluent limits: 20 mg/L monthly average. Proposed limit of 20 mg/l was provided by applicant in the Antidegradation Report. To derive the Monthly Daily Maximum (MDL), the average monthly limit was multiplied by 1.5, thus the MDL = 30 mg/l. Influent monitoring may be required for this facility in its Missouri State Operating Permit.
- **pH.** pH shall be maintained in the range from 6.5 – 9.0 standard units [10 CSR 20-7.015(8)(A)2].
- **Escherichia coli (E. coli).** Discharge shall not contain more than a monthly geometric mean of 206 and weekly average of 1030 colonies/100 mL during the recreational season (April 1 – October 31), to protect Whole Body Contact Recreation (B) designated use of the receiving stream, as per 10 CSR 20-7.031(4)(C) and Table A. Daily Maximum or Weekly Average effluent variability will be evaluated in development of a future effluent limit. An effluent limit for both monthly average and weekly average is required by 40 CFR 122.45(d). Also, please see **GENERAL ASSUMPTIONS OF THE WQRS #7.**
- **Total Ammonia Nitrogen.** Early Life Stages Present Total Ammonia Nitrogen criteria apply [10 CSR 20-7.031(4)(B)7.C. & Table B3]. Background total ammonia nitrogen = 0.01 mg/L

Season	Temp (°C)	pH (SU)	Total Ammonia Nitrogen CCC (mg N/L)	Total Ammonia Nitrogen CMC (mg N/L)
Summer	26	7.8	1.5	12.1
Winter	6	7.8	3.1	12.1

Summer: April 1 – September 30, Winter: October 1 – March 31.

Summer

$$C_c = (((Q_e + Q_s) * C) - (Q_s * C_s)) / Q_e$$

Chronic WLA: $C_c = 1.5 \text{ mg/L}$
 Acute WLA: $C_c = 12.1 \text{ mg/L}$

$LTA_c = 1.5 \text{ mg/L} (0.780) = \mathbf{1.2 \text{ mg/L}}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L} (0.321) = 3.88 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

MDL = $1.2 \text{ mg/L} (3.11) = 3.7 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
 AML = $1.2 \text{ mg/L} (1.19) = 1.4 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

Winter

Chronic WLA: $C_c = 3.1 \text{ mg/L}$
 Acute WLA: $C_c = 12.1 \text{ mg/L}$

$LTA_c = 3.1 \text{ mg/L} (0.780) = \mathbf{2.4 \text{ mg/L}}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L} (0.321) = 3.9 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

MDL = $2.4 \text{ mg/L} (3.11) = 7.5 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
 AML = $2.4 \text{ mg/L} (1.19) = 2.9 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

The proposed effluent limits provided in the Antidegradation Report were the same as the calculated water quality based effluent limits.


Season	Maximum Daily Limit (mg/l)	Average Monthly Limit (mg/l)
Summer	3.7	1.4
Winter	7.5	2.9

- **Oil & Grease.** Conventional pollutant [10 CSR 20-7.031, Table A], effluent limitation for protection of aquatic life; 10 mg/L monthly average, 15 mg/L maximum daily limit.

Reviewer: Keith Forck
Date: November 1, 2012
Unit Chief: John Rustige

Monitoring and effluent limits contained within this document have been developed in accordance with EPA guidelines using the best available data and are believed to be consistent with Missouri's Water Quality Standards and Effluent Regulations. If additional water quality data or anecdotal information are available that may affect the recommended monitoring and effluent limits, please forward these data and information to the author.


Richmond South



APPENDIX II: ANTIDegradation REVIEW SUMMARY ATTACHMENTS

The attachments that follow contain summary information provided by the applicant

- 1) Tier Determination and Effluent Limit Summary Sheet
Attachment A: Summary of the alternatives analysis.



MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM
ANTIDegradation REVIEW SUMMARY
TIER DETERMINATION AND EFFLUENT LIMIT SUMMARY

OCT 22 2012

WATER PROTECTION PROGRAM

1. FACILITY			
NAME RICHMOND SOUTH WASTEWATER TREATMENT PLANT		TELEPHONE NUMBER WITH AREA CODE (816) 776-5304	
ADDRESS (PHYSICAL) SOUTH WELLINGTON		CITY RICHMOND	STATE MO
			ZIP CODE 64085
2. RECEIVING WATER BODY SEGMENT #1			
NAME UNNAMED TRIBUTARY TO WILLOW CREEK			
2.1 UPPER END OF SEGMENT (Location of discharge) UTM _____ OR Lat +3915206, Long -093581029			
2.2 LOWER END OF SEGMENT UTM _____ OR Lat +3914401, Long -093581955			
Per the Missouri Antidegradation Rule and Implementation Procedure, or AIP, the definition of a segment, "a segment is a section of water that is bound, at a minimum, by significant existing sources and confluences with other significant water bodies."			
3. WATER BODY SEGMENT #2 (IF APPLICABLE)			
NAME WILLOW CREEK			
3.1 UPPER END OF SEGMENT UTM _____ OR Lat +3914401, Long -093581955			
3.2 LOWER END OF SEGMENT UTM _____ OR Lat +3914276, Long -093581938			
4. WATER BODY SEGMENT #3 (IF APPLICABLE)			
NAME			
4.1 UPPER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
4.2 LOWER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
5. PROJECT INFORMATION			
Is the receiving water body an Outstanding National Resource Water, an Outstanding State Resource Water, or drainage thereto? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
In Tables D and E of 10 CSR 20-7.031, Outstanding National Resource Waters and Outstanding State Resource Water are listed. Per the Antidegradation Implementation Procedure Section 1.B.3., "any degradation of water quality is prohibited in these waters unless the discharge only results in temporary degradation." Therefore, if degradation is significant or minimal, the Antidegradation Review will be denied.			
Will the proposed discharge of all pollutants of concern, or POCs, result in no net increase in the ambient water quality concentration of the receiving water after mixing? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
If yes, submit a summary table showing the levels of each pollutant of concern before and after the proposed discharge in the receiving water and then complete Attachment B for the first downstream classified water body segment.			
Will the discharge result in temporary degradation? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
If yes, complete Attachment C.			
Has the project been determined as non-degrading? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
If yes, complete No Degradation Evaluation – Conclusion of Antidegradation Review form. Submit with the appropriate Construction Permit Application as no antidegradation review is required.			
If yes to one of the above questions, skip to Section 8 - Wet Weather.			

6. EXISTING WATER QUALITY DATA OR MODEL SUMMARY

Obtaining Existing Water Quality is possible by three methods according to the Antidegradation Implementation Procedure Section II.A.1.: (1) using previously collected data with an appropriate Quality Assurance Project Plan, or QAPP (2) collecting water quality data by approved the Missouri Department of Natural Resources methodology or (3) using an appropriate water quality model. QAPPs must be submitted to the department for approval well in advance (six months) of the proposed activity. Provide all the appropriate corresponding data and reports which were approved by the department Water Quality Monitoring and Assessment Section.

Date existing water quality data was provided by the Water Quality Monitoring and Assessment Section:

Approval date of the QAPP by the Water Quality Monitoring and Assessment Section:

Approval date of the project sampling plan by the Water Quality Monitoring and Assessment Section:

Approval date of the data collected for all appropriate pollutants of concern by the Water Quality Monitoring and Assessment Section:

Comments/Discussion:

7. POLLUTANTS OF CONCERN AND TIER DETERMINATION(S)

Pollutants of Concern to be considered include those pollutants reasonably expected to be present in the discharge per the Antidegradation Implementation Procedure Section II.S. The tier protection levels are specified and defined in rule at 10 CSR 20-7.031 (2).

**Water Body Segment One
Pollutants of Concern and Tier Determination(s)**

Tier 1	Tier 2 with Minimal Degradation	Tier 2 with Significant Degradation
		BOD5
		TSS
		NH3-N
		OIL & GREASE
		E. COLI

Note: Add an asterisk to items that you only assume are Tier 2 with significant degradation.

**Water Body Segment Two
Pollutants of Concern and Tier Determination(s)**

Tier 1	Tier 2 with Minimal Degradation	Tier 2 with Significant Degradation
		BOD5
		TSS
		NH3-N
		OIL & GREASE
		E. COLI

- For pollutants of concern that are Tier 2 with significant degradation, complete Attachment A.
- For pollutants of concern that are Tier 2 with minimal degradation, complete Attachment B.
- For pollutants of concern that are Tier 1, complete Attachment D. Additionally, a Tier 2 review must be conducted for each pollutant of concern on the appropriate water body segment.

8. WET WEATHER ANTICIPATIONS

If an applicant anticipates excessive inflow or infiltration and pursues approval from the department to bypass secondary treatment, a feasibility analysis is required. The feasibility analysis must comply with the criteria of all applicable state and federal regulations including 40 CFR 122.41(m)(4). Attach the feasibility analysis to this report.

What is the Wet Weather Flow Peaking Factor in relation to design flow? 2.26

Wet Weather Design Summary:

THIS FACILITY WILL NOT BYPASS SECONDARY TREATMENT FOLLOWING THE PLANT IMPROVEMENTS. AN EQUALIZATION BASIN WILL BE ADDED UPSTREAM OF THE PLANT AND ALL FLOW WILL BE TREATED.

9. SUMMARY OF THE PROPOSED ANTIDegradation REVIEW EFFLUENT LIMITS

What are the proposed pollutants of concern and their respective effluent limits that the selected treatment option will comply with:

Pollutant of Concern	Units	Wasteload Allocation	Average Monthly Limit	Daily Maximum Limit
BOD5	MG/L		20	
TSS	MG/L		20	
Dissolved Oxygen	MG/L			
Ammonia	MG/L		1.85 / 2.65	
Bacteria (E. Coli)	/100ML		206	

These proposed limits must not violate water quality standards, be protective of beneficial uses and achieve the highest statutory and regulatory requirements.

Attach the Antidegradation Review report and all supporting documentation.

CONSULTANT: I have prepared or reviewed this form and all attached reports and documentation. The conclusion proposed is consistent with the Antidegradation Implementation Procedure and current state and federal regulation.

SIGNATURE <i>Michael Milius</i>		DATE 10/17/12	
NAME AND OFFICIAL TITLES MICHAEL MILIUS, PE			
COMPANY NAME OLSSON ASSOCIATES			
ADDRESS 1251 NW BRIARCLIFF PKWY	CITY	STATE	ZIP CODE KANSAS CITY, MO 64116
TELEPHONE NUMBER WITH AREA CODE 816 361 1177	E-MAIL ADDRESS MMILUS@OACONSULTING.COM		

OWNER: I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE <i>Ronald G. Brohammer</i>		DATE 10/19/12	
NAME AND OFFICIAL TITLES RONALD G. BROHAMMER, CITY ADMINISTRATOR			
ADDRESS 205 Summit Street	CITY Richmond	STATE MO	ZIP CODE 64085
TELEPHONE NUMBER WITH AREA CODE 816.776.5304	E-MAIL ADDRESS rbrohammer@cityofrichmondmo.org		

CONTINUING AUTHORITY: Continuing Authority is the permanent organization that will be responsible for the operation, maintenance and modernization of the facility. The regulatory requirement regarding continuing authority is found in 10 CSR 20-6.010(3) available at www.sos.mo.gov/adrules/csr/current/10csr/10c20-6a.pdf.

I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE <i>Ronald G. Brohammer</i>		DATE 10/19/12	
NAME AND OFFICIAL TITLES Ronald G. Brohammer, City Administrator			
ADDRESS 205 Summit Street	CITY Richmond	STATE MO	ZIP CODE 64085
TELEPHONE NUMBER WITH AREA CODE 816-770-5304	E-MAIL ADDRESS rbrohammer@cityofrichmondmo.org		



MISSOURI DEPARTMENT OF NATURAL RESOURCES
 WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH
ANTIDegradation REVIEW SUMMARY
ATTACHMENT A: TIER 2 – SIGNIFICANT DEGRADATION

OCT 22 2012

WATER PROTECTION PROGRAM

1. FACILITY

NAME RICHMOND SOUTH WASTEWATER TREATMENT PLANT		TELEPHONE NUMBER WITH AREA CODE (816) 776-5304	
ADDRESS (PHYSICAL) SOUTH WELLINGTON	CITY RICHMOND	STATE MO	ZIP CODE 64085

2. RECEIVING WATER BODY SEGMENT #1

NAME TRIBUTARY TO WILLOW CREEK

3. WATER BODY SEGMENT #2 (IF APPLICABLE)

NAME WILLOW CREEK

4. IDENTIFYING ALTERNATIVES

Supply a summary of the alternatives considered and the level of treatment attainable with regards to the alternative. "For Discharges likely to cause significant degradation, an analysis of non-degrading and less-degrading alternatives must be provided," as stated in the Antidegradation Implementation Procedure Section II.B.1. Per 10 CSR 20-6.010(4)(D)1., the feasibility of a no-discharge system must be considered. Attach all supportive documentation in the Antidegradation Review report.

Non-degrading alternatives: Land application not suitable for flows analyzed; other non-degrading alt. is Membrane, shown below.

Alternatives ranging from less-degrading to degrading including Preferred Alternative (All must meet water quality standards):

Alternatives	Level of Treatment Attainable for each Pollutant of Concern				
	BOD (mg/L)	TSS (mg/L)	Ammonia as N (mg/L)	Bacteria (E. Coli) (#/100mL)	<i>oil & Grease</i> mg/L
Alt. 1 - SBR	20	20	1.85/2.65	n/a	10
Alt. 2 - SBR w/Filter	7	7	1.85/2.65	n/a	2
Alt. 3 - Membrane Bioreactor	3	1	0.4/0.6	n/a	2
Alt. 4 - SBR w/Two Outfalls	18	18	1.85/2.65	206 @ north	10

Identifying Alternatives Summary: _____

5. DETERMINATION OF THE REASONABLE ALTERNATIVE

Per the Antidegradation Implementation Procedure Section II.B.2, "a reasonable alternative is one that is practicable, economically efficient and affordable." Provide basis and supporting documentation in the Antidegradation Review report.

Practicability Summary:

"The practicability of an alternative is considered by evaluating the effectiveness, reliability, and potential environmental impacts," according to the Antidegradation Implementation Procedure Section II.B.2.a. Examples of factors to consider, including secondary environmental impacts, are given in the Antidegradation Implementation Procedure Section II.B.2.a.

Per the attached report, non-degrading options were not deemed practical. Alt. 1, 2, and 4 were the most practical. Refer to report.

Economic Efficiency Summary:

Alternatives that are deemed practicable must undergo a direct cost comparison in order to determine economic efficiency. Means to determine economic efficiency are provided in the Antidegradation Implementation Procedure Section II.B.2.b.

An economic efficiency analysis was performed on all practical alternatives, with all alts being >120% more costly than base alt.

Affordability Summary:

Alternatives identified as most practicable and economically efficient are considered affordable if the applicant does not supply an affordability analysis. An affordability analysis per the Antidegradation Implementation Procedure Section II.B.2.c, "may be used to determine if the alternative is too expensive to reasonably implement."

Alt. 1, SBR, was the only alternate determined to be practical and economically efficient. This alt. is also deemed affordable.

Preferred Chosen Alternative:

Based on the analyses presented in the Anti-Deg report, Alt. 1-SBR is the preferred alternative. Refer to report.

Reasons for Rejecting the other Evaluated Alternatives:

Non-discharging alts. not suitable for design flow studied, Alt. 3 was not practical, Alts. 2, 3, & 4 were not economically efficient.

Comments/Discussion:

Consideration should be given to the fact that the preferred alternative, while not non-degrading, does consolidate two existing WWTP discharges into one and eliminates a discharge that would require disinfection. The preferred alternative utilizes an existing WWTP site and general outfall location, thus no new discharge point locations are being created.

6. SOCIAL AND ECONOMIC IMPORTANCE OF THE PREFERRED ALTERNATIVE

If the preferred alternative will result in significant degradation, then it must be demonstrated that it will allow important economic and social development in accordance to the Antidegradation Implementation Procedure Section II.E. Social and Economic Importance is defined as the social and economic benefits to the community that will occur from any activity involving a new or expanding discharge.

Identify the affected community:

The affected community is defined in 10 CSR 20-7.031(2)(B) as the community "in the geographical area in which the waters are located.: Per the Antidegradation Implementation Procedure Section II.E.1, "the affected community should include those living near the site of the proposed project as well as those in the community that are expected to directly or indirectly benefit from the project."

The affected communities are the City of Richmond and the City of Henrietta. The improvements will occur at an existing WWTP site.

Identify relevant factors that characterize the social and economic conditions of the affected community:

Examples of social and economic factors are provided in the Antidegradation Implementation Procedure Section II.E.1., but specific community examples are encouraged.

Both affected communities will benefit socially and economically by consolidating the existing two plants and providing treatment capacity to accommodate the next twenty years of growth. As the greater metro area surrounding Kansas City continues to grow and more businesses and residents are established along the edges of the metro area, Richmond and Henrietta must position themselves to accommodate the growth. It is estimated that 70% of Richmond's future growth will fall within the South WWTP service area.

Describe the important social and economic development associated with the project:

Determining benefits for the community and the environment should be site specific and in accordance with the Antidegradation Implementation Procedure Section II.E.1.

The benefits to the affected area include accommodating imminent future growth and removing one existing WWTP discharge.

PROPOSED PROJECT SUMMARY:

Replace North WWTP with new pump stn. and force main to pump to South WWTP. Upgrade South WWTP to 2.0 MGD SBR.

Attach the Antidegradation Review report and all supporting documentation. This is a technical document, which must be signed, sealed and dated by a registered professional engineer of Missouri.

CONSULTANT: I have prepared or reviewed this form and all attached reports and documentation. The conclusion proposed in consistent with the Antidegradation Implementation Procedure and current state and federal regulations.

SIGNATURE 	DATE 10/17/12
--	------------------

PRINT NAME Michael Milius, PE	LICENSE # : PE-2011033243
----------------------------------	------------------------------

TELEPHONE NUMBER WITH AREA CODE (816) 361-1177	E-MAIL ADDRESS: mmilius@OACConsulting.com
---	--


OWNER: I have read and reviewed the prepared documents and agree with this submittal.


SIGNATURE 	DATE 10/19/12
--	------------------

CONTINUING AUTHORITY: I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE 	DATE 10/19/12
--	------------------

DO Profile, Unnamed Tributary to Willow Creek near South Richmond WWTP
Effluent BOD = 20 mg/L







STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

These Standard Conditions incorporate permit conditions as required by 40 CFR 122.41 or other applicable state statutes or regulations. These minimum conditions apply unless superseded by requirements specified in the permit.

Part I – General Conditions

Section A – Sampling, Monitoring, and Recording

1. **Sampling Requirements.**
 - a. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity.
 - b. All samples shall be taken at the outfall(s) or Missouri Department of Natural Resources (Department) approved sampling location(s), and unless specified, before the effluent joins or is diluted by any other body of water or substance.
2. **Monitoring Requirements.**
 - a. Records of monitoring information shall include:
 - i. The date, exact place, and time of sampling or measurements;
 - ii. The individual(s) who performed the sampling or measurements;
 - iii. The date(s) analyses were performed;
 - iv. The individual(s) who performed the analyses;
 - v. The analytical techniques or methods used; and
 - vi. The results of such analyses.
 - b. If the permittee monitors any pollutant more frequently than required by the permit at the location specified in the permit using test procedures approved under 40 CFR Part 136, or another method required for an industry-specific waste stream under 40 CFR subchapters N or O, the results of such monitoring shall be included in the calculation and reported to the Department with the discharge monitoring report data (DMR) submitted to the Department pursuant to Section B, paragraph 7.
3. **Sample and Monitoring Calculations.** Calculations for all sample and monitoring results which require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in the permit.
4. **Test Procedures.** The analytical and sampling methods used shall conform to the reference methods listed in 10 CSR 20-7.015 unless alternates are approved by the Department. The facility shall use sufficiently sensitive analytical methods for detecting, identifying, and measuring the concentrations of pollutants. The facility shall ensure that the selected methods are able to quantify the presence of pollutants in a given discharge at concentrations that are low enough to determine compliance with Water Quality Standards in 10 CSR 20-7.031 or effluent limitations unless provisions in the permit allow for other alternatives. A method is “sufficiently sensitive” when; 1) the method minimum level is at or below the level of the applicable water quality criterion for the pollutant or, 2) the method minimum level is above the applicable water quality criterion, but the amount of pollutant in a facility’s discharge is high enough that the method detects and quantifies the level of pollutant in the discharge, or 3) the method has the lowest minimum level of the analytical methods approved under 10 CSR 20-7.015. These methods are also required for parameters that are listed as monitoring only, as the data collected may be used to determine if limitations need to be established. A permittee is responsible for working with their contractors to ensure that the analysis performed is sufficiently sensitive.
5. **Record Retention.** Except for records of monitoring information required by the permit related to the permittee’s sewage sludge use and disposal activities, which shall be retained for a period of at least five (5) years (or longer as required by 40 CFR part 503), the permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the application for the permit, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Department at any time.

6. **Illegal Activities.**
 - a. The Federal Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the permit shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than two (2) years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than \$20,000 per day of violation, or by imprisonment of not more than four (4) years, or both.
 - b. The Missouri Clean Water Law provides that any person or who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than six (6) months, or by both. Second and successive convictions for violation under this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.

Section B – Reporting Requirements

1. **Planned Changes.**
 - a. The permittee shall give notice to the Department as soon as possible of any planned physical alterations or additions to the permitted facility when:
 - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b); or
 - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements under 40 CFR 122.42(a)(1);
 - iii. The alteration or addition results in a significant change in the permittee’s sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan;
 - iv. Any facility expansions, production increases, or process modifications which will result in a new or substantially different discharge or sludge characteristics must be reported to the Department 60 days before the facility or process modification begins. Notification may be accomplished by application for a new permit. If the discharge does not violate effluent limitations specified in the permit, the facility is to submit a notice to the Department of the changed discharge at least 30 days before such changes. The Department may require a construction permit and/or permit modification as a result of the proposed changes at the facility.
2. **Twenty-Four Hour Reporting.**
 - a. The permittee shall report any noncompliance which may endanger health or the environment. Relevant information shall be provided orally or via the current electronic method approved by the Department, within 24 hours from the time the permittee becomes aware of the circumstances, and shall be reported to the appropriate Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. A written submission shall also be provided within five (5) business days of the time the permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

- b. The following shall be included as information which must be reported within 24 hours under this paragraph.
 - i. Any unanticipated bypass which exceeds any effluent limitation in the permit.
 - ii. Any upset which exceeds any effluent limitation in the permit.
 - iii. Violation of a maximum daily discharge limitation for any of the pollutants listed by the Department in the permit required to be reported within 24 hours.
 - c. The Department may waive the written report on a case-by-case basis for reports under paragraph 2. b. of this section if the oral report has been received within 24 hours.
3. **Sanitary Sewer Overflow Reporting.** The following requirements solely reflect reporting obligations, and reporting does not necessarily reflect noncompliance, which may depend on the circumstances of the incident reported.
- a. **Twenty-Four Hour (24-Hour) Reporting.** The permittee or owner shall report any incident in which wastewater escapes the collection system such that it reaches waters of the state or it may pose an imminent or substantial endangerment to the health or welfare of persons. Relevant information shall be provided orally or via the current electronic method approved by the Department within 24 hours from the time the permittee becomes aware of the incident. A written submission shall also be provided within five (5) business days of the time the permittee or owner becomes aware of the incident. The Department may waive the written report on a case-by-case basis if the oral report has been received within 24 hours. The five (5) day reports may be provided via the current electronic method approved by the Department.
 - b. **Incidents Reported via Discharge Monitoring Reports (DMRs).** The permittee or owner shall report any event in which wastewater escapes the collection system, which does not enter waters of the state and is not expected to pose an imminent or substantial endangerment to the health or welfare of persons, which occur typically during wet weather events. Relevant information shall be provided with the permittee's or owner's DMRs.
4. **Anticipated Noncompliance.** The permittee shall give advance notice to the Department of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements. The notice shall be submitted to the Department 60 days prior to such changes or activity.
5. **Compliance Schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date. The report shall provide an explanation for the instance of noncompliance and a proposed schedule or anticipated date, for achieving compliance with the compliance schedule requirement.
6. **Other Noncompliance.** The permittee shall report all instances of noncompliance not reported under paragraphs 2, 3, 4, and 7 of this section, at the time monitoring reports are submitted. The reports shall contain the information listed in paragraph 2. a. of this section.
7. **Other Information.** Where the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Department, it shall promptly submit such facts or information.
8. **Discharge Monitoring Reports.**
- a. Monitoring results shall be reported at the intervals specified in the permit.
 - b. Monitoring results must be reported to the Department via the current method approved by the Department, unless the permittee has been granted a waiver from using the method. If the permittee has been granted a waiver, the permittee must use forms provided by the Department.
 - c. Monitoring results shall be reported to the Department no later than the 28th day of the month following the end of the reporting period.

Section C – Bypass/Upset Requirements

1. **Definitions.**
 - a. *Bypass*: the intentional diversion of waste streams from any portion of a treatment facility.
 - b. *Severe Property Damage*: substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
 - c. *Upset*: an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
2. **Bypass Requirements.**
 - a. Bypass not exceeding limitations. The permittee may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of paragraphs 2. b. and 2. c. of this section.
 - b. Notice.
 - i. Anticipated bypass. If the permittee knows in advance of the need for a bypass, it shall submit prior notice, if possible at least 10 days before the date of the bypass.
 - ii. Unanticipated bypass. The permittee shall submit notice of an unanticipated bypass as required in Section B – Reporting Requirements, paragraph 5 (24-hour notice).
 - c. Prohibition of bypass.
 - i. Bypass is prohibited, and the Department may take enforcement action against a permittee for bypass, unless:
 1. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
 2. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and
 3. The permittee submitted notices as required under paragraph 2. b. of this section.
 - ii. The Department may approve an anticipated bypass, after considering its adverse effects, if the Department determines that it will meet the three (3) conditions listed above in paragraph 2. c. i. of this section.
3. **Upset Requirements.**
 - a. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of paragraph 3. b. of this section are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.
 - b. Conditions necessary for a demonstration of upset. A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
 - i. An upset occurred and that the permittee can identify the cause(s) of the upset;
 - ii. The permitted facility was at the time being properly operated; and
 - iii. The permittee submitted notice of the upset as required in Section B – Reporting Requirements, paragraph 2. b. ii. (24-hour notice).
 - iv. The permittee complied with any remedial measures required under Section D – Administrative Requirements, paragraph 4.
 - c. Burden of proof. In any enforcement proceeding, the permittee seeking to establish the occurrence of an upset has the burden of proof.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

Section D – Administrative Requirements

1. **Duty to Comply.** The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Missouri Clean Water Law and Federal Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.
 - a. The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
 - b. The Federal Clean Water Act provides that any person who violates section 301, 302, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any such sections in a permit issued under section 402, or any requirement imposed in a pretreatment program approved under sections 402(a)(3) or 402(b)(8) of the Act, is subject to a civil penalty not to exceed \$25,000 per day for each violation. The Federal Clean Water Act provides that any person who negligently violates sections 301, 302, 306, 307, 308, 318, or 405 of the Act, or any condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, or any requirement imposed in a pretreatment program approved under section 402(a)(3) or 402(b)(8) of the Act, is subject to criminal penalties of \$2,500 to \$25,000 per day of violation, or imprisonment of not more than one (1) year, or both. In the case of a second or subsequent conviction for a negligent violation, a person shall be subject to criminal penalties of not more than \$50,000 per day of violation, or by imprisonment of not more than two (2) years, or both. Any person who knowingly violates such sections, or such conditions or limitations is subject to criminal penalties of \$5,000 to \$50,000 per day of violation, or imprisonment for not more than three (3) years, or both. In the case of a second or subsequent conviction for a knowing violation, a person shall be subject to criminal penalties of not more than \$100,000 per day of violation, or imprisonment of not more than six (6) years, or both. Any person who knowingly violates section 301, 302, 303, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, and who knows at that time that he thereby places another person in imminent danger of death or serious bodily injury, shall, upon conviction, be subject to a fine of not more than \$250,000 or imprisonment of not more than 15 years, or both. In the case of a second or subsequent conviction for a knowing endangerment violation, a person shall be subject to a fine of not more than \$500,000 or by imprisonment of not more than 30 years, or both. An organization, as defined in section 309(c)(3)(B)(iii) of the CWA, shall, upon conviction of violating the imminent danger provision, be subject to a fine of not more than \$1,000,000 and can be fined up to \$2,000,000 for second or subsequent convictions.
 - c. Any person may be assessed an administrative penalty by the EPA Director for violating section 301, 302, 306, 307, 308, 318 or 405 of this Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of this Act. Administrative penalties for Class I violations are not to exceed \$10,000 per violation, with the maximum amount of any Class I penalty assessed not to exceed \$25,000. Penalties for Class II violations are not to exceed \$10,000 per day for each day during which the violation continues, with the maximum amount of any Class II penalty not to exceed \$125,000.
 - d. It is unlawful for any person to cause or permit any discharge of water contaminants from any water contaminant or point source located in Missouri in violation of sections 644.006 to 644.141 of the Missouri Clean Water Law, or any standard, rule or regulation promulgated by the commission. In the event the commission or the director determines that any provision of sections 644.006 to 644.141 of the Missouri Clean Water Law or standard, rules, limitations or regulations promulgated pursuant thereto, or permits issued by, or any final abatement order, other order, or determination made by the commission or the director, or any filing requirement pursuant to sections 644.006 to 644.141 of the Missouri Clean Water Law or any other provision which this state is required to enforce pursuant to any federal water pollution control act, is being, was, or is in imminent danger of being violated, the commission or director may cause to have instituted a civil action in any court of competent jurisdiction for the injunctive relief to prevent any such violation or further violation or for the assessment of a penalty not to exceed \$10,000 per day for each day, or part thereof, the violation occurred and continues to occur, or both, as the court deems proper. Any person who willfully or negligently commits any violation in this paragraph shall, upon conviction, be punished by a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than one year, or both. Second and successive convictions for violation of the same provision of this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.
2. **Duty to Reapply.**
 - a. If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and obtain a new permit.
 - b. A permittee with a currently effective site-specific permit shall submit an application for renewal at least 180 days before the expiration date of the existing permit, unless permission for a later date has been granted by the Department. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
 - c. A permittees with currently effective general permit shall submit an application for renewal at least 30 days before the existing permit expires, unless the permittee has been notified by the Department that an earlier application must be made. The Department may grant permission for a later submission date. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
3. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.
4. **Duty to Mitigate.** The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.
5. **Proper Operation and Maintenance.** The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems which are installed by a permittee only when the operation is necessary to achieve compliance with the conditions of the permit.
6. **Permit Actions.**
 - a. Subject to compliance with statutory requirements of the Law and Regulations and applicable Court Order, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:
 - i. Violations of any terms or conditions of this permit or the law;
 - ii. Having obtained this permit by misrepresentation or failure to disclose fully any relevant facts;
 - iii. A change in any circumstances or conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge; or
 - iv. Any reason set forth in the Law or Regulations.
 - b. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

7. **Permit Transfer.**
 - a. Subject to 10 CSR 20-6.010, an operating permit may be transferred upon submission to the Department of an application to transfer signed by the existing owner and the new owner, unless prohibited by the terms of the permit. Until such time the permit is officially transferred, the original permittee remains responsible for complying with the terms and conditions of the existing permit.
 - b. The Department may require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the Missouri Clean Water Law or the Federal Clean Water Act.
 - c. The Department, within 30 days of receipt of the application, shall notify the new permittee of its intent to revoke or reissue or transfer the permit.
8. **Toxic Pollutants.** The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the Federal Clean Water Act within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
9. **Property Rights.** This permit does not convey any property rights of any sort, or any exclusive privilege.
10. **Duty to Provide Information.** The permittee shall furnish to the Department, within a reasonable time, any information which the Department may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The permittee shall also furnish to the Department upon request, copies of records required to be kept by this permit.
11. **Inspection and Entry.** The permittee shall allow the Department, or an authorized representative (including an authorized contractor acting as a representative of the Department), upon presentation of credentials and other documents as may be required by law, to:
 - a. Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of the permit;
 - b. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
 - c. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
 - d. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Federal Clean Water Act or Missouri Clean Water Law, any substances or parameters at any location.
12. **Closure of Treatment Facilities.**
 - a. Persons who cease operation or plan to cease operation of waste, wastewater, and sludge handling and treatment facilities shall close the facilities in accordance with a closure plan approved by the Department.
 - b. Operating Permits under 10 CSR 20-6.010 or under 10 CSR 20-6.015 are required until all waste, wastewater, and sludges have been disposed of in accordance with the closure plan approved by the Department and any disturbed areas have been properly stabilized. Disturbed areas will be considered stabilized when perennial vegetation, pavement, or structures using permanent materials cover all areas that have been disturbed. Vegetative cover, if used, shall be at least 70% plant density over 100% of the disturbed area.
13. **Signatory Requirement.**
 - a. All permit applications, reports required by the permit, or information requested by the Department shall be signed and certified. (See 40 CFR 122.22 and 10 CSR 20-6.010)
 - b. The Federal Clean Water Act provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or non-compliance shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than six (6) months per violation, or by both.
14. **Severability.** The provisions of the permit are severable, and if any provision of the permit, or the application of any provision of the permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of the permit, shall not be affected thereby.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
MAY 1, 2013

PART II - SPECIAL CONDITIONS – PUBLICLY OWNED
TREATMENT WORKS
SECTION A – INDUSTRIAL USERS

1. Definitions

Definitions as set forth in the Missouri Clean Water Laws and approved by the Missouri Clean Water Commission shall apply to terms used herein.

Significant Industrial User (SIU). Except as provided in the *General Pretreatment Regulation* 10 CSR 20-6.100, the term Significant Industrial User means:

1. All Industrial Users subject to Categorical Pretreatment Standards; and
2. Any other Industrial User that: discharges an average of 25,000 gallons per day or more of process wastewater to the Publicly-Owned Treatment Works (POTW) (excluding sanitary, noncontact cooling and boiler blowdown wastewater); contributes a process wastestream which makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the POTW treatment plant; or is designated as such by the Control Authority on the basis that the Industrial User has a reasonable potential for adversely affecting the POTW's or for violating any Pretreatment Standard or requirement.

Clean Water Act (CWA) is the the federal Clean Water Act of 1972, 33 U.S.C. § 1251 et seq. (2002).

2. Identification of Industrial Discharges

Pursuant to 40 CFR 122.44(j)(1), all POTWs shall identify, in terms of character and volume of pollutants, any Significant Industrial Users discharging to the POTW subject to Pretreatment Standards under section 307(b) of the CWA and 40 CFR 403.

3. Application Information

Applications for renewal or modification of this permit must contain the information about industrial discharges to the POTW pursuant to 40 CFR 122.21(j)(6)

4. Notice to the Department

Pursuant to 40 CFR 122.42(b), all POTWs must provide adequate notice of the following:

1. Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to section 301 or 306 of CWA if it were directly discharging these pollutants; and
2. Any substantial change into the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit.
3. For purposes of this paragraph, adequate notice shall include information on:
 - i. the quality and quantity of effluent introduced into the POTW, and
 - ii. any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

For POTWs without an approved pretreatment program, the notice of industrial discharges which was not included in the permit application shall be made as soon as practicable. For POTWs with an approved pretreatment program, notice is to be included in the annual pretreatment report required in the special conditions of this permit. Notice may be sent to:

Missouri Department of Natural Resources
Water Protection Program
Attn: Pretreatment Coordinator
P.O. Box 176
Jefferson City, MO 65102

**STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
AUGUST 15, 1994**

PART III – SLUDGE & BIOSOLIDS FROM DOMESTIC WASTEWATER TREATMENT FACILITIES

SECTION A – GENERAL REQUIREMENTS

1. This permit pertains to sludge requirements under the Missouri Clean Water Law and regulation and incorporates applicable federal sludge disposal requirements under 40 CFR 503. The Environmental Protection Agency (EPA) has principal authority for permitting and enforcement of the federal sludge regulations under 40 CFS 503 until such time as Missouri is delegated the new EPA sludge program. EPA has reviewed and accepted these standard sludge conditions. EPA may choose to issue a separate sludge addendum to this permit or a separate federal sludge permit at their discretion to further address federal requirements.
2. These PART III Standard Conditions apply only to sludge and biosolids generated at domestic wastewater treatment facilities, including public owned treatment works (POTW) and privately owned facilities.
3. Sludge and Biosolids Use and Disposal Practices.
 - a. Permittee is authorized to operate the sludge and biosolids treatment, storage, use, and disposal facilities listed in the facility description of this permit.
 - b. Permittee shall not exceed the design sludge volume listed in the facility description and shall not use sludge disposal methods that are not listed in the facility description, without prior approval of the permitting authority.
 - c. Permittee is authorized to operate the storage, treatment or generating sites listed in the Facility Description section of this permit.
 - d. A separate operating permit is required for each operating location where sludge or biosolids are generated, stored, treated, or disposed, unless specifically exempted in this permit or in 10 CSR 20, Chapter 6 regulations. For land application, see section H, subsection 3 of these standard conditions.
4. Sludge Received From Other Facilities
 - a. Permittees may accept domestic wastewater sludge from other facilities including septic tank pumpings from residential sources as long as the design sludge volume is not exceeded and the treatment facility performance is not impaired.
 - b. The permittee shall obtain a signed statement from the sludge generator or hauler that certifies the type and source of the sludge.
 - c. Sludge received from out-of-state generators shall receive prior approval of the permitting authority and shall be listed in the facility description or special conditions section of the permit.
5. These permit requirements do not supersede nor remove liability for compliance with county and other local ordinances.
6. These permit requirements do not supersede nor remove liability for compliance with other environmental regulations such as odor emissions under the Missouri Air Pollution Control Law and regulations.
7. This permit may (after du process) be modified, or alternatively revoked and reissued, to comply with any applicable sludge disposal standard or limitation issued or approved under Section 405(d) of the Clean Water Act or under Chapter 644 RsMo.
8. In addition to the STANDARD CONDITIONS, the department may include sludge limitations in the special conditions portion or other sections of this permit.
9. Alternate Limits in Site Specific Permit.

Where deemed appropriate, the department may require an individual site specific permit in order to authorize alternate limitations:

 - a. An individual permit must be obtained for each operating location, including application sites.
 - b. To request a site specific permit, an individual permit application, permit fees, and supporting documents shall be submitted for each operating location. This shall include a detailed sludge/biosolids management plan or engineering report.
10. Exceptions to these Standard Conditions may be authorized on a case-by-case basis by the department, as follows:
 - a. The department will prepare a permit modification and follow permit public notice provisions as applicable under 10 CSR 20-6.020, 40 CFR 124.10, and 40 CFR 501.15(a)(2)(ix)(E). This includes notification of the owners of property located adjacent to each land application site, where appropriate.
 - b. Exceptions cannot be granted where prohibited by the federal sludge regulations under 40 CFR 503.
11. Compliance Period
Compliance shall be achieved as expeditiously as possible but no later than the compliance dates under 40 CFR 503.2.

SECTION B – DEFINITIONS

1. Biosolids means an organic fertilizer or soil amendment produced by the treatment of domestic wastewater sludge. Untreated sludge or sludge that does not conform to the pollutants and pathogen treatment requirements in this permit is not considered biosolids.
2. Biosolids land application facility is a facility where biosolids are spread onto the land at agronomic rates for production of food or fiber. The facility includes any structures necessary to store the biosolids until soil, weather, and crop conditions are favorable for land application.
3. Class A biosolids means a material that has met the Class A pathogen reduction requirements or equivalent treatment by a Process to Further Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
4. Class B biosolids means a material that has met the Class B pathogen reduction requirements or equivalent treatment by a Process to Significantly Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
5. Domestic wastewater means wastewater originating from the sanitary conveniences of residences, commercial buildings, factories and institutions; or co-mingled sanitary and industrial wastewater processed by a public owned treatment works (POTW) or privately owned facility.
6. Mechanical treatment plants are wastewater treatment facilities that use mechanical devices to treat wastewater, including septic tanks, extended aeration, activated sludge, contact stabilization, trickling filters, rotating biological discs, and other similar facilities. It does not include unaerated wastewater treatment lagoons and constructed wetlands for wastewater treatment.
7. Operating location as defined in 10 CSR 20-2.010 is all contiguous lands owned, operated or controlled by one (1) person or by two (2) or more persons jointly or as tenants in common.
8. Plant Available Nitrogen (PAN) is the nitrogen that will be available to plants during the next growing season after biosolids application.
9. Sinkhole is a depression in the land surface into which surface water flows to join an underground drainage system.
10. Site Specific Permit is a permit that has alternate limits developed to address specific site conditions for each land application site or storage site.
11. Sludge is the solid, semisolid, or liquid residue removed during the treatment of wastewater. Sludge includes septage removed from septic tanks.
12. Sludge lagoon is an earthen basin that receives sludge that has been removed from a wastewater treatment facility. It does not include a wastewater treatment lagoon or sludge treatment units that are not a part of a mechanical wastewater treatment facility.
13. Wetlands are those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamp, marshes, bogs, and similar areas. Wetlands do not include constructed wetlands used for wastewater treatment.

SECTION C – MECHANICAL WASTEWATER TREATMENT FACILITIES

1. Sludge shall be routinely removed from the wastewater treatment facilities and handled according to the permit facility description and sludge conditions in this permit.
2. The permittee shall operate the facility so that there is no sludge loss into the discharged effluent in excess of permit limits, no sludge bypassing, and no discharge of sludge to waters of the state.
3. Mechanical treatment plants shall have separate sludge storage compartments in accordance with 10 CSR 20, Chapter 8. Failure to remove sludge from these storage compartments on the required design schedule is a violation of this permit.

SECTION D – SLUDGE DISPOSED AT OTHER TREATMENT FACILITY OR CONTRACT HAULER

1. This section applies to permittees that haul sludge to another treatment facility for disposal or use contract haulers to remove and dispose of sludge.
2. Permittees that use contract haulers are responsible for compliance with all the terms of this permit including final disposal, unless the hauler has a separate permit for sludge or biosolids disposal issued by the department; or the hauler transports the sludge to another permitted treatment facility.
3. The permittee shall require documentation from the contractor of the disposal methods used and permits obtained by the contractor.
4. Testing of sludge, other than total solids content, is not required if sludge is hauled to a municipal wastewater treatment facility or other permitted wastewater treatment facility.

SECTION E – WASTEWATER TREATMENT LAGOONS AND STORMWATER RETENTION BASINS

1. Sludge that is retained within a wastewater treatment lagoon is subject to sludge disposal requirements when the sludge is removed from the lagoon or when the lagoon ceases to receive and treat wastewater.
2. If sludge is removed during the year, an annual sludge report must be submitted.
3. Storm water retention basins or other earthen basins, which have been used as sludge storage for a mechanical treatment system is considered a sludge lagoon and must comply with Section G of this permit.

SECTION F – INCINERATION OF SLUDGE

1. Sludge incineration facilities shall comply with the requirements of 40 CFR 503 Subpart E; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
2. Permittee may be authorized under the facility description of this permit to store incineration ash in lagoons or ash ponds. This permit does not authorize the disposal of incineration ash. Incineration ash shall be disposed in accordance with 10 CSR 80; or if the ash is determined to be hazardous waste, shall be disposed in accordance with 10 CSR 25.
3. In addition to normal sludge monitoring, incineration facilities shall report the following as part of the annual report, quantity of sludge incinerated, quantity of ash generated, quantity of ash stored; and ash use or disposal method, quantity, and location. Permittee shall also provide the name of the disposal facility and the applicable permit number.
4. Additional limitations, monitoring, and reporting requirements may be addressed in the Special Conditions sections of this permit.

SECTION G – SURFACE DISPOSAL SITES AND SLUDGE LAGOONS

1. Surface disposal sites shall comply with the requirements in 40 CFR 503 Subpart C, and solid waste disposal regulations under 10 CSR 80.
2. Additional limitations, monitoring, and reporting requirements may be addressed in the Special Conditions section of this permit.
3. Effective February 19, 1995, a sludge lagoon that has been in use for more than two years without removal of accumulated sludge, or that has not been properly closed shall comply with one of the following options:
 - a. Permittee shall obtain a site specific permit to address surface disposal requirements under 40 CFR 503, ground water quality regulations under 10 CSR 20, Chapter 7 and 8, and solid waste management regulations under 10 CSR 80;
 - b. Permittee shall clean out the sludge lagoon to remove any sludge over two years old and shall continue to remove accumulated sludge at least every two years or an alternate schedule approved under 40 CFR 503.20(b). In order to avoid damage to the lagoon seal during cleaning, the permittee may leave a layer of sludge on the bottom of the lagoon, upon prior approval of the department; or
 - c. Permittee shall close the lagoon in accordance with Section 1.

SECTION H – LAND APPLICATION

1. The permittee shall not land apply sludge or biosolids unless land application is authorized in the Facility Description or special conditions section of the permit.
2. This permit replaces and terminates all previous sludge management plan approvals by the department for land application of sludge or biosolids.
3. Land application sites within a 20 mile radius of the wastewater treatment facility are authorized under this permit when biosolids are applied for beneficial use in accordance with these standard conditions unless a site specific permit is required under Section A, Subsection 9.
4. Biosolids shall not be applied unless authorized in this permit or exempted under 10 CSR 20, Chapter 6.
 - a. This permit does not authorize the land application of sludge except when sludge meets the definition of biosolids.
 - b. This permit authorizes “Class A or B” biosolids derived from domestic wastewater sludges to be land applied onto grass land, crop land, timber land or other similar agricultural or silviculture lands at rates suitable for beneficial use as organic fertilizer and soil conditioner.
5. Public Contact Sites.
Permittees who wish to apply Class A biosolids to public contact sites must obtain approval from the department. Applications for approval shall be in the form of an engineering report and shall address priority pollutants and dioxin concentrations. Authorization for land applications must be provided in the special conditions section of this permit or in a separate site-specific permit.

6. Agricultural and Silvicultural Sites.

In addition to specified conditions herein, this permit is subject to the attached Water Quality Guides numbers WQ 422 through 426 published by the University of Missouri, and hereby incorporated as though fully set forth herein. The guide topics are as follows:

WQ 422	Land Application of Septage
WQ 423	Monitoring Requirements for Biosolids Land Application
WQ 424	Biosolids Standards for Pathogens and Vectors
WQ 425	Biosolids Standards for Metals and Other Trace Substances
WQ 426	Best Management Practices for Biosolids Land Applications

SECTION I – CLOSURE REQUIREMENTS

1. This section applies to all wastewater treatment facilities (mechanical and lagoons) and sludge or biosolids storage and treatment facilities and incineration ash ponds. It does not apply to land application sites.
2. Permittees who plan to cease operation must obtain department approval of a closure plan which addresses proper removal and disposal of all residues, including sludge, biosolids, and ash. Permittee must maintain this permit until the facility is properly closed per 10 CSR 20-6.010 and 10 CSR 20-6.015.
3. Residuals that are left in place during closure of a lagoon or earthen structure shall not exceed the agricultural loading rates as follows:
 - a. Residuals shall meet the monitoring and land application limits for agricultural rates as referenced in Section H of these standard conditions.
 - b. If a wastewater treatment lagoon has been in operation for 15 years or more, the sludge in the lagoon qualifies for Class B with respect to pathogens (see WQ 424, Table 3), and testing for fecal coliform is not required. For other lagoons, testing for fecal coliform is required to show compliance with Class B limitations. See WQ 423 and 424.
 - c. The allowable nitrogen loading that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. See WQ 426 for calculation procedures. For a grass cover crop, the allowable PAN is 300 pounds/acre.
4. When closing a wastewater treatment lagoon with a design treatment capacity equal or less than 150 persons, the residuals are considered “septage” under the similar treatment works” definition. See WQ 422. Under the septage category, residuals may be left in place as follows:
 - a. Testing for metals or fecal coliform is not required.
 - b. If the wastewater treatment lagoon has been in use for less than 15 years, mix lime with the sludge at the rate of 50 pounds of hydrated lime per 1000 gallons (134 cubic feet) of sludge.
 - c. The amount of sludge that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. 100 dry tons/acre of sludge may be left in the basin without testing for nitrogen. If more than 100 dry tons/acre will be left in the lagoon, test for nitrogen and determine the PAN in accordance with WQ 426. Allowable PAN loading is 300 pounds/acre.
5. Residuals left within the lagoon shall be mixed with soil on at least a 1 to 1 ratio, the lagoon berms shall be demolished, and the site shall be graded and vegetated so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
6. Lagoon closure activities shall obtain a storm water permit for land disturbance activities that equal or exceed five acres in accordance with 10 CSR 20-6.200.
7. If sludge exceeds agricultural loading rates under Section H or I, a landfill permit or solid waste disposal permit shall be obtained to authorize on-site sludge disposal under the Missouri Solid Waste Management Law and regulations per 10 CSR 80, and the permittee must comply with the surface disposal requirements under 40 CFR 503, Subpart C.

SECTION J – MONITORING FREQUENCY

1. At a minimum, sludge or biosolids shall be tested for volume and percent total solids on a frequency that will accurately represent sludge quantities produced and disposed.
2. Testing for land application is listed under Section H, Subsection 6 of these standard conditions (see WQ 423). Once per year is the minimum test frequency. Additional testing shall be performed for each 100 dry tons of sludge generated or stored during the year.
3. Additional testing may be required in the special conditions or other sections of the permit. Permittees receiving industrial wastewater may be required to conduct additional testing upon request from the department.
4. Monitoring requirements shall be performed in accordance with, “POTW Sludge Sampling and Analysis Guidance Document”, United States Environmental Protection Agency, August 1989, and subsequent revisions.

SECTION K – RECORD KEEPING AND REPORTING REQUIREMENTS

1. The permittee shall maintain records on file at the facility for at least five years for the items listed in these Standard Conditions and any additional items in the Special Conditions section of this permit. This shall include dates when the sludge facility is checked for proper operation, records of maintenance and repairs and other relevant information.
2. Reporting Period
 - a. By January 28th of each year, an annual report shall be submitted for the previous calendar year period for all mechanical wastewater treatment facilities, sludge lagoons, and sludge or biosolids disposal facilities.
 - b. Permittees with wastewater treatment lagoons shall submit the above annual report only when sludge or biosolids are removed from the lagoon during the report period or when the lagoon is closed.
3. Report Forms. The annual report shall be submitted on report forms provided by the department or equivalent forms approved by the department.
4. Report shall be submitted as follows:
Major facilities (those serving 10,000 persons or 1 million gallons per day) shall report to both the department and EPA. Other facilities need to report only to the department. Reports shall be submitted to the addresses listed as follows:

DNR regional office listed in your permit
(See cover letter of permit)

EPA Region VII
Water Compliance Branch (WACM)
Sludge Coordinator
901 N 5th Street
Kansas City, KS 66101

5. Annual Report Contents. The annual report shall include the following:
 - a. Sludge/biosolids testing performed. Include a copy or summary of all test results, even if not required by this permit.
 - b. Sludge or Biosolids quantity shall be reported as dry tons for quantity generated by the wastewater treatment facility, the quantity stored on site at end of year, and the quantity used or disposed.
 - c. Gallons and % solids data used to calculate the dry ton amounts.
 - d. Description of any unusual operating conditions.
 - e. Final disposal method, dates, and location, and person responsible for hauling and disposal.
 - (1) This must include the name, address and permit number for the hauler and the sludge facility. If hauled to a municipal wastewater treatment facility, sanitary landfill, or other approved treatment facility, give the name and permit number of that facility.
 - (2) Include a description of the type of hauling equipment used and the capacity in tons, gallons, or cubic feet.
 - f. Contract Hauler Activities.
If contract hauler, provide a copy of a signed contract or billing receipts from the contractor. Permittee shall require the contractor to supply information required under this permit for which the contractor is responsible. The permittee shall submit a signed statement from the contractor that he has complied with the standards contained in this permit, unless the contract hauler has a separate sludge disposal or biosolids use permit.
 - g. Land Application Sites.
 - (1) Report the location of each application site, the annual and cumulative dry tons/acre for each site, and the landowners name and address. The location for each spreading site shall be given as legal description for nearest ¼, ¼, Section, Township, Range, and County, or as latitude and longitude.
 - (2) If biosolids application exceeds 2 dry tons/acre/year, report biosolids nitrogen results. Plant Available Nitrogen (PAN) in pounds/acre, crop nitrogen requirement, available nitrogen in the soil prior to biosolids application, and PAN calculations for each site.
 - (3) If the “Low Metals” criteria is exceeded, report the annual and cumulative pollutant loading rates in pounds per acre for each applicable pollutant, and report the percent of cumulative loading which has been reached at each site.
 - (4) Report the method used for compliance with pathogen and vector attraction requirements.
 - (5) Report soil test results for pH, CEC, and phosphorus. If none was tested during the year, report the last date when tested and results.



MISSOURI DEPARTMENT OF NATURAL RESOURCES
 WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH
**FORM B2 – APPLICATION FOR CONSTRUCTION OR OPERATING
 PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC
 WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS
 PER DAY**

AP 9506

FOR AGENCY USE ONLY	
CHECK NUMBER NONE SENT	
DATE RECEIVED 1/23/12	FEE SUBMITTED Ø

①

PART A – BASIC APPLICATION INFORMATION

1. This application is for:

An operating permit and antidegradation review public notice.

A construction permit following an appropriate operating permit and antidegradation review public notice.

A construction permit, a concurrent operating permit and antidegradation review public notice.

A construction permit (submitted before Aug. 30, 2008 or antidegradation review is not required).

An operating permit for a new or unpermitted facility. Construction Permit # _____

An operating permit renewal: Permit #MO-0100200 Expiration Date JULY 19, 2012

An operating permit modification: Permit #MO-_____ Reason: _____

1.1 Is this a Federal/State Funded Project? Yes No Funding Agency/Project #: _____

1.2 Is the appropriate fee included with the application (See instructions for appropriate fee)? Yes No

2. FACILITY

NAME <u>Richmond South WASTEWATER TREATMENT PLANT</u>		TELEPHONE NUMBER WITH AREA CODE <u>816-776-6504</u>	
ADDRESS (PHYSICAL) <u>9069 WELLINGTON STREET</u>	CITY <u>Richmond</u>	STATE <u>MO</u>	ZIP <u>64085</u>

2.1 LEGAL DESCRIPTION (Plant Site): 1/4, NW 1/4, SE 1/4, Sec. 6, T51N, R 27W County RAY

2.2 UTM Coordinates Easting (X): _____ Northing (Y): _____
 For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)

3. OWNER

NAME <u>CITY OF RICHMOND</u>		TELEPHONE NUMBER WITH AREA CODE <u>816-776-5304</u>	
ADDRESS <u>205 Summit STREET</u>	CITY <u>Richmond</u>	STATE <u>MO.</u>	ZIP <u>64085</u>

3.1 Request review of draft permit prior to Public Notice? Yes No

4. CONTINUING AUTHORITY: Permanent organization which will serve as the continuing authority for the operation, maintenance and modernization of the facility.

NAME <u>CITY OF RICHMOND</u>		CITY <u>Richmond</u>	
ADDRESS <u>205 Summit STREET</u>	CERTIFICATE NUMBER (IF APPLICABLE)	STATE <u>MO.</u>	ZIP <u>64085</u>

5. OPERATOR

NAME <u>ELWYN B. GRIFFIN</u>	TITLE <u>WASTEWATER OPERATOR</u>	TELEPHONE NUMBER WITH AREA CODE <u>816-776-6504</u>
---------------------------------	-------------------------------------	--

6. FACILITY CONTACT

NAME <u>ELWYN B. GRIFFIN</u>	TITLE <u>WASTEWATER OPERATOR</u>
---------------------------------	-------------------------------------

JAN 13 2012
 MISSOURI CITY RECORDS



MISSOURI DEPARTMENT OF NATURAL RESOURCES
 WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH
FORM B2 -- APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE AND HAVE A DESIGN FLOW MORE THAN 100,000 GALLONS PER DAY

FACILITY NAME <i>Richmond South Wastewater Treatment Plant</i>	
PERMIT NO. <i>MO-0100200</i>	COUNTY <i>RAY</i>

APPLICATION OVERVIEW

Form B2 has been developed in a modular format and consists of Parts A, B and C and a Supplemental Application Information (Parts D, E, F and G) packet. All applicants must complete Parts A, B and C. Some applicants must also complete parts of the Supplemental Application Information packet. The following items explain which parts of Form B2 you must complete. Submittal of an incomplete application may result in the application being returned.

BASIC APPLICATION INFORMATION

A. Basic Application Information for all Applicants. All applicants must complete Part A.
 B. Additional Application Information for all Applicants. All applicants must complete Part B.
 C. Certification. All applicants must complete Part C.

SUPPLEMENTAL APPLICATION INFORMATION

D. Expanded Effluent Testing Data. A treatment works that discharges effluent to surface water of the United States and meets one or more of the following criteria must complete *Part D - Expanded Effluent Testing Data*:

- Has a design flow rate greater than or equal to 1 million gallons per day.
- Is required to have or currently has a pretreatment program.
- Is otherwise required by the permitting authority to provide the information.

E. Toxicity Testing Data. A treatment works that meets one or more of the following criteria must complete *Part E - Toxicity Testing Data*:


- Has a design flow rate greater than or equal to 1 million gallons per day.
- Is required to have or currently has a pretreatment program.
- Is otherwise required by the permitting authority to provide the information.

F. Industrial User Discharges and Resource Conservation and Recovery Act / Comprehensive Environmental Response, Compensation and Liability Act Wastes. A treatment works that accepts process wastewater from any significant industrial users, also known as SIUs, or receives a Resource Conservation and Recovery Act or CERCLA wastes must complete *Part F - Industrial User Discharges and Resource Conservation and Recovery Act /CERCLA Wastes*.

SIUs are defined as:

- All Categorical Industrial Users, or CIUs, subject to Categorical Pretreatment Standards under 40 Code of Federal Regulations 403.6 and 40 Code of Federal Regulations 403.6 and 40 CFR Chapter 1, Subchapter N.
- Any other industrial user that meets one or more of the following:
 - Discharges an average of 25,000 gallons per day or more of process wastewater to the treatment works (with certain exclusions).
 - Contributes a process waste stream that makes up five percent or more of the average dry weather hydraulic or organic capacity of the treatment plant.
 - Is designated as an SIU by the control authority.

G. Combined Sewer Systems. A treatment works that has a combined sewer system must complete *Part G - Combined Sewer Systems*.



ALL APPLICANTS MUST COMPLETE PARTS A, B and C

FACILITY NAME SOUTH WASTEWATER Richmond PLANT		PERMIT NO. MO- 0100200	OUTFALL NO. #001
PART A - BASIC APPLICATION INFORMATION			
7. ADDITIONAL FACILITY INFORMATION			
7.1 BRIEF DESCRIPTION OF FACILITIES Extended aeration/sludge ISLAND APPLIED OX DITCH			
7.2 TOPOGRAPHIC MAP. ATTACH TO THIS APPLICATION A TOPOGRAPHIC MAP OF THE AREA EXTENDING AT LEAST ONE MILE BEYOND FACILITY PROPERTY BOUNDARIES. THIS MAP MUST SHOW THE OUTLINE OF THE FACILITY AND THE FOLLOWING INFORMATION. (YOU MAY SUBMIT MORE THAN ONE MAP IF ONE MAP DOES NOT SHOW THE ENTIRE AREA.)			
<ul style="list-style-type: none"> a. The area surrounding the treatment plant, including all unit processes. b. The location of the downstream landowner(s). (See Item 10.) c. The major pipes or other structures through which wastewater enters the treatment works and the pipes or other structures through which treated wastewater is discharged from the treatment plant. Include outfalls from bypass piping, if applicable. d. The actual point of discharge. e. Wells, springs, other surface water bodies and drinking water wells that are: 1) within ¼ mile of the property boundaries of the treatment works, and 2) listed in public record or otherwise known to the applicant. f. Any areas where the sewage sludge produced by the treatment works is stored, treated or disposed. g. If the treatment works receives waste that is classified as hazardous under the Resource Conservation and Recovery Act, or RCRA, by truck, rail or special pipe, show on the map where that hazardous waste enters the treatment works and where it is treated, stored or disposed. 			
7.3 PROCESS FLOW DIAGRAM OR SCHEMATIC. PROVIDE A DIAGRAM SHOWING THE PROCESSES OF THE TREATMENT PLANT. ALSO, PROVIDE A WATER BALANCE SHOWING ALL TREATMENT UNITS, INCLUDING DISINFECTION (E.G. CHLORINATION AND DECHLORINATION). THE WATER BALANCE MUST SHOW DAILY AVERAGE FLOW RATES AT INFLUENT AND DISCHARGE POINTS AND APPROXIMATE DAILY FLOW RATES BETWEEN TREATMENT UNITS. INCLUDE A BRIEF NARRATIVE DESCRIPTION OF THE DIAGRAM.			
7.4 FACILITY SIC CODE	DISCHARGE SIC CODE: 4952	FACILITY NAICS CODE:	DISCHARGE NAICS CODE:
7.5 NUMBER OF SEPARATE DISCHARGE POINTS 1			
7.6 NUMBER OF PEOPLE PRESENTLY CONNECTED OR POPULATION EQUIVALENT POPULATION OF 1709 CITY OF RICHMOND + 457 FROM CITY OF HENRIETTA		DESIGN POPULATION EQUIVALENT 4'500	
NUMBER OF UNITS PRESENTLY CONNECTED HOMES 629 APARTMENTS 220 TRAILERS 9 OTHER 34			
TOTAL DESIGN FLOW (ALL OUTFALLS) 475'000		ACTUAL FLOW 459'000	
7.7 DOES ANY BYPASSING OCCUR ANYWHERE IN THE COLLECTION SYSTEM OR AT THE TREATMENT FACILITY? YES THE PLANT HAS A PEAK FLOW CLARIFIER Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> (If Yes, attach an explanation.)			
7.8 LENGTH OF THE SANITARY SEWER COLLECTION SYSTEM IN MILES 21 MILES			
7.9 IS INDUSTRIAL WASTE DISCHARGED TO THE FACILITY IDENTIFIED IN ITEM 2? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			
7.10 WILL THE DISCHARGE BE CONTINUOUS THROUGH THE YEAR? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>			
A. DISCHARGE WILL OCCUR DURING THE FOLLOWING MONTHS		B. HOW MANY DAYS OF THE WEEK WILL THE DISCHARGE OCCUR?	
7.11 IS WASTEWATER LAND APPLIED? (If Yes, Attach Form I) Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		7.12 DOES THIS FACILITY DISCHARGE TO A LOSING STREAM OR SINKHOLE? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
7.13 HAS A WASTE LOAD ALLOCATION STUDY BEEN COMPLETED FOR THIS FACILITY? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>			
7.14 LIST ALL PERMIT VIOLATIONS, INCLUDING EFFLUENT LIMIT EXCEEDANCES IN THE LAST FIVE YEARS. 2 NOV, IN 2011 ATTACH A SEPARATE SHEET IF NECESSARY. IF NONE, WRITE NONE. 2 EXCEEDANCES IN 2008 1 MISSING REPORT IN 2007			
8. LABORATORY CONTROL INFORMATION			
8.1 LABORATORY WORK CONDUCTED BY PLANT PERSONNEL			
Lab work conducted outside of plant.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Push-button or visual methods for simple test such as pH, settleable solids.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Additional procedures such as Dissolved Oxygen, Chemical Oxygen Demand, Biological Oxygen Demand, titrations, solids, volatile content.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph.		Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>

FACILITY NAME <i>Richmond South WASTEWATER PLANT</i>	PERMIT NO. <i>MO- 0100200</i>	OUTFALL NO. <i>#001</i>
---	----------------------------------	----------------------------

PART A - BASIC APPLICATION INFORMATION

9. SLUDGE HANDLING, USE AND DISPOSAL

9.1 IS THE SLUDGE A HAZARDOUS WASTE AS DEFINED BY 10 CSR 25?
 Yes No

9.2 SLUDGE PRODUCTION, INCLUDING SLUDGE RECEIVED FROM OTHERS
 Design Dry Tons/Year *94.5* Actual Dry Tons/Year *69.3*

9.3 CAPACITY OF SLUDGE HOLDING STRUCTURES *270,000 gal.*

9.4 SLUDGE STORAGE PROVIDED
 Cubic Feet *36,000*, Days of Storage *50* Average Percent Solids of Sludge *2 1/2 %* No Sludge Storage is Provided

9.5 TYPE OF STORAGE
 Holding Tank Basin Building Concrete Pad Other (Describe) _____

9.6 SLUDGE TREATMENT
 Anaerobic Digester Storage Tank Lime Stabilization Lagoon
 Aerobic Digester Air or Heat Drying Composting Other (Attach Description)

9.7 SLUDGE USE OR DISPOSAL
 Land Application Contract Hauler Hauled to Another Treatment Facility Solid Waste Landfill
 Surface Disposal (Sludge Disposal Lagoon, Sludge Held For More Than Two Years) Incineration
 Other (Attach Explanation Sheet) _____

9.8 PERSON RESPONSIBLE FOR HAULING SLUDGE TO DISPOSAL FACILITY

NAME
CITY OF RICHMOND

ADDRESS <i>205 SUMMIT STREET</i>	CITY <i>RICHMOND</i>	STATE <i>MO</i>	ZIP <i>64085</i>
-------------------------------------	-------------------------	--------------------	---------------------

CONTACT PERSON <i>DALE SHIPP</i>	TELEPHONE NUMBER WITH AREA CODE <i>816-776-5304</i>	PERMIT NO. <i>MO- 0100200</i>
-------------------------------------	--	----------------------------------

9.9 SLUDGE USE OR DISPOSAL FACILITY
 By Applicant By Others (Complete Below)

NAME
CITY OF RICHMOND

ADDRESS <i>205 SUMMIT STREET</i>	CITY <i>RICHMOND</i>	STATE <i>MO.</i>	ZIP <i>6408</i>
-------------------------------------	-------------------------	---------------------	--------------------

CONTACT PERSON <i>DALE SHIPP</i>	TELEPHONE NUMBER WITH AREA CODE <i>816-776-5304</i>	PERMIT NO. <i>MO- 0100200</i>
-------------------------------------	--	----------------------------------

9.10 DO THE SLUDGE OR BIOSOLIDS DISPOSAL COMPLY WITH FEDERAL SLUDGE REGULATIONS UNDER 40 CFR 503?
 Yes No (Attach Explanation)

10. DOWNSTREAM LANDOWNER(S). (ATTACH ADDITIONAL SHEETS AS NECESSARY.)

NAME
MILTON STIGALL

ADDRESS <i>9067 WELLINGTON</i>	CITY <i>RICHMOND</i>	STATE <i>MO.</i>	ZIP <i>64085</i>
-----------------------------------	-------------------------	---------------------	---------------------

11. DRINKING WATER SUPPLY INFORMATION

11.1 SOURCE OF YOUR DRINKING WATER SUPPLY *CITY OF RICHMOND*

A. PUBLIC SUPPLY (MUNICIPAL OR WATER DISTRICT WATER) (IF PUBLIC, PLEASE GIVE NAME OF PUBLIC SUPPLY)
CITY OF RICHMOND


B. PRIVATE WELL

C. SURFACE WATER (LAKE, POND OR STREAM)


11.2 DOES YOUR DRINKING WATER SOURCE SERVE AT LEAST 25 PEOPLE AT LEAST 60 DAYS PER YEAR (NOT NECESSARILY CONSECUTIVE DAYS)?
 Yes No

11.3 DOES YOUR SPPLY SERVE HOUSING THAT IS OCCUPIED YEAR ROUND BY THE SAME PEOPLE? THIS DOES NOT INCLUDE HOUSING THAT IS OCCUPIED SEASONALLY?
 Yes No

END OF PART A



MAKE ADDITIONAL COPIES OF THIS FORM FOR EACH OUTFALL			
FACILITY NAME <i>RICHMOND SOUTH WASTEWATER PLANT</i>	PERMIT NO. <i>MO-0100200</i>	OUTFALL NO. <i>#001</i>	
PART B - ADDITIONAL APPLICATION INFORMATION			
20. INFLOW AND INFILTRATION			
ESTIMATE THE AVERAGE NUMBER OF GALLONS PER DAY THAT FLOW INTO THE TREATMENT WORKS FROM INFLOW AND INFILTRATION. Gallons Per Day <i>250'000.</i>			
BRIEFLY EXPLAIN ANY STEPS UNDERWAY OR PLANNED TO MINIMIZE INFLOW AND INFILTRATION. <i>LOOKING IN TO DOING MANHOLE REHAB & CURED-IN-PLACE PIPE</i>			
20.1 OPERATION AND MAINTENANCE PERFORMED BY CONTRACTOR(S)			
ARE ANY OPERATIONAL OR MAINTENANCE ASPECTS (RELATED TO WASTEWATER TREATMENT AND EFFLUENT QUALITY) OF THE TREATMENT WORKS THE RESPONSIBILITY OF A CONTRACTOR? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> If Yes, list the name, address, telephone number and status of each contractor and describe the contractor's responsibilities. (Attach additional pages if necessary.)			
NAME			
MAILING ADDRESS			
TELEPHONE NUMBER WITH AREA CODE			
RESPONSIBILITIES OF CONTRACTOR			
20.2 SCHEDULED IMPROVEMENTS AND SCHEDULES OF IMPLEMENTATION. PROVIDE INFORMATION ABOUT ANY UNCOMPLETED IMPLEMENTATION SCHEDULE OR UNCOMPLETED PLANS FOR IMPROVEMENTS THAT WILL AFFECT THE WASTEWATER TREATMENT, EFFLUENT QUALITY OR DESIGN CAPACITY OF THE TREATMENT WORKS. IF THE TREATMENT WORKS HAS SEVERAL DIFFERENT IMPLEMENTATION SCHEDULES OR IS PLANNING SEVERAL IMPROVEMENTS, SUBMIT SEPARATE RESPONSES FOR EACH. (IF NONE, GO TO QUESTION B-20.3.)			
A. List the outfall number that is covered by this implementation schedule Outfall No.		B. Indicate whether the planned improvements or implementation schedule are required by local, state or federal agencies. Yes <input type="checkbox"/> No <input type="checkbox"/>	
20.3 WASTEWATER DISCHARGES: COMPLETE QUESTIONS 20.4 THROUGH 20.7 ONCE FOR EACH OUTFALL (INCLUDING BYPASS POINTS) THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION ON COMBINED SEWER OVERFLOWS IN THIS SECTION.			
20.4 DESCRIPTION OF OUTFALL			
OUTFALL NUMBER <i>#001</i>			
A. LOCATION <i>1/4 1/4 NW 1/4 SE</i> Section <i>6</i> Township <i>S1N</i> Range <i>27W</i> <input type="checkbox"/> E <input type="checkbox"/> W UTM Coordinates Easting (X): _____ Northing (Y): _____ For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)			
B. Distance from Shore (If Applicable) _____ ft.		C. Depth Below Surface (If Applicable) _____ ft.	D. Average Daily Flow Rate <i>4555</i> mgd
E. Does this outfall have either an intermittent or periodic discharge? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, Provide the following information:			
Number of Days Per Year Discharge Occurs:	Average Duration of Each Discharge:	Average Flow Per Discharge: mgd	Months in Which Discharge Occurs:
Is Outfall Equipped with a Diffuser? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
20.5 DESCRIPTION OF RECEIVING WATER			
B. Name of Receiving Water <i>UN NAMED TRIBUTARY OF WILLOW CREEK</i>			
B. Name of Watershed (If Known) <i>WILLOW CREEK</i>		U.S. Soil Conservation Service 14-Digit Watershed Code (If Known) <i>10300101-090002</i>	
B. Name of State Management/River Basin (If Known)		U.S. Geological Survey 8-Digit Hydrologic Cataloging Unit Code (If Known)	
B. Critical Flow of Receiving Stream (If Applicable) Acute _____ cfs Chronic _____ cfs		B. Total Hardness of Receiving Stream at Critical Low Flow (If Applicable) mg/L of CaCO ₃	



FACILITY NAME RICHMOND SOUTH WASTE WATER PLANT	PERMIT NO. MO-0100200	OUTFALL NO. #001
---	---------------------------------	----------------------------

PART B - ADDITIONAL APPLICATION INFORMATION (CONTINUED)

20.6 DESCRIPTION OF TREATMENT

A. WHAT LEVELS OF TREATMENT ARE PROVIDED? Check All That Apply
 Primary Secondary Advanced Other (Describe)

B. INDICATE THE FOLLOWING REMOVAL RATES (AS APPLICABLE)
 Design BOD₅ Removal Or Design CBOD₅ Removal 85 % Design SS Removal 85 %
 Design P Removal % Design N Removal % Other %

C. What type of disinfection is used for the effluent from this outfall? If disinfection varies by season, please describe:
NONE

If disinfection is by chlorination, is dechlorination used for this outfall? Yes No

Does the treatment plant have post aeration? Yes No

20.7 EFFLUENT TESTING DATA. ALL APPLICANTS THAT DISCHARGE TO WATERS OF THE U.S. MUST PROVIDE EFFLUENT TESTING DATA FOR THE FOLLOWING PARAMETERS. PROVIDE THE INDICATED EFFLUENT DATA FOR EACH OUTFALL THROUGH WHICH EFFLUENT IS DISCHARGED. DO NOT INCLUDE INFORMATION OF COMBINED SEWER OVERFLOWS IN THIS SECTION. ALL INFORMATION REPORTED MUST BE BASED ON DATA COLLECTED THROUGH ANALYSIS CONDUCTED USING 40 CFR PART 136 METHODS. IN ADDITION, THIS DATA MUST COMPLY WITH QA/QC REQUIREMENTS OF 40 CFR PART 136 AND OTHER APPROPRIATE QA/QC REQUIREMENTS FOR STANDARD METHODS FOR ANALYTES NOT ADDRESSED BY 40 CFR PART 136.


PARAMETER	MAXIMUM DAILY VALUE		AVERAGE DAILY VALUE		
	VALUE	UNITS	VALUE	UNITS	NO. OF SAMPLES
pH (Minimum)	<u>7.16</u>	S.U.	<u>7.41</u>	S.U.	<u>12</u>
pH (Maximum)	<u>8.02</u>	S.U.	<u>7.83</u>	S.U.	<u>12</u>
FLOW RATE	<u>1.8077 MGD</u>	MGD	<u>.4555</u>	MGD	<u>12</u>
TEMPERATURE (Winter)	<u>15.8°</u>	°C	<u>10.02</u>	°C	<u>60</u> <small>JAN, FEB, DEC 2011</small>
TEMPERATURE (Summer)	<u>26.8°</u>	°C	<u>22.83</u>	°C	<u>65</u> <small>JUNE, JULY, AUG 2011</small>

*For pH report a minimum and a maximum daily value.

POLLUTANT	MAXIMUM DAILY DISCHARGE		AVERAGE DAILY DISCHARGE			ANALYTICAL METHOD	ML/MDL
	CONC.	UNITS	CONC.	UNITS	NO. OF SAMPLES		

Conventional and Nonconventional Compounds							
BIOCHEMICAL OXYGEN DEMAND (Report One)	BOD ₅						
		<u>51.5</u>	mg/L	<u>13.48</u>	mg/L	<u>18</u>	<u>STANDARD METHODS 5210-B</u>
	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
FECAL COLIFORM	<u>N/A</u>	#/100 mL	<u>N/A</u>	#/100 mL			
TOTAL SUSPENDED SOLIDS (TSS)	<u>49.3</u>	mg/L	<u>9.15</u>	mg/L	<u>83</u>	<u>STANDARD METHODS 2540-D</u>	
AMMONIA (AS N)	<u>3.6</u>	mg/L	<u>.65</u>	mg/L	<u>12</u>	<u>STANDARD METHODS 4500-NH3D</u>	
CHLORINE (TOTAL RESIDUAL, TRC)	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
DISSOLVED OXYGEN	<u>15.62</u>	mg/L	<u>8.68</u>	mg/L	<u>251</u>	<u>YSI DO METER MODEL 5B (4500-O-0)</u>	
TOTAL KJELDAHL NITROGEN (TKN)	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
NITRATE PLUS NITRITE NITROGEN	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
OIL AND GREASE	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
PHOSPHORUS (TOTAL)	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
TOTAL DISSOLVE SOLIDS (TDS)	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			
OTHER	<u>N/A</u>	mg/L	<u>N/A</u>	mg/L			

END OF PART B



PART C - CERTIFICATION

30. CERTIFICATION

All applicants must complete the Certification Section. This certification must be signed by an officer of the company or city official. All applicants must complete all applicable sections as explained in the Application Overview. By signing this certification statement, applicants confirm that they have reviewed the entire form and have completed all sections that apply to the facility for which this application is submitted.

ALL APPLICANTS MUST COMPLETE THE FOLLOWING CERTIFICATION.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

PRINTED NAME AND OFFICIAL TITLE (MUST BE AN OFFICER OF THE COMPANY OR CITY OFFICIAL)

Ronald G. Brohammer, City Administrator

SIGNATURE

Ronald G. Brohammer

TELEPHONE NUMBER WITH AREA CODE

816-776-5304

DATE SIGNED

1-11-12

Upon request of the permitting authority, you must submit any other information necessary to assess wastewater treatment practices at the treatment works or identify appropriate permitting requirements.

For Design Flows Less than 1 Million Gallons Per Day, Send Completed Form to:

Appropriate Regional Office

Map of regional offices with addresses and phone numbers is available on the Web at www.dnr.mo.gov/regions/ro-map.pdf.

For Design Flows of 1 Million Gallons Per Day or Greater, Send Completed Form to:

Department of Natural Resources
Water Protection Program
ATTN: NPDES Permits and Engineering Section
P.O. Box 176
Jefferson City, MO 65102


END OF PART C.

REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM B2 YOU MUST COMPLETE.

Do not complete the remainder of this application, unless:

1. Your facility design flow is equal to or greater than 1,000,000 gallons per day.
2. Your facility is a pretreatment treatment works.
3. Your facility is a combined sewer system.

Submittal of an incomplete application may result in the application being returned. Permit fees for returned applications shall be forfeited. Permit fees for applications being processed by the department that are withdrawn by the applicant shall be forfeited.





RECEIVED
JAN 13 2012
 KANSAS CITY REGIONAL OFFICE

HENRIETTA DRAINAGE DISTRICT
 CITY OF RICHMOND

2.004
4.11 AC

2.003
17.8 AC

2.005
71.2 AC

16
27 AC

13
0 AC


14
9 AC

15
9 AC

WELLINGTON STREET


12
73.09 AC

60°



CITY OF RICHMOND MO, SOUTH WWT, PLANT

- INF.
- MIXED LIQUOR
- EFF.
- COMMON & BASIN LINES
- DITCH VALVE
- BASIN VALVE



DECLARED
JAN 13 2012
KANSAS CITY REGIONAL OFFICE