

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES

MISSOURI CLEAN WATER COMMISSION



MISSOURI STATE OPERATING PERMIT

In compliance with the Missouri Clean Water Law, (Chapter 644 R.S. Mo. as amended, hereinafter, the Law), and the Federal Water Pollution Control Act (Public Law 92-500, 92nd Congress) as amended,

Permit No. MO-0137278

Owner: Village of Sunrise Beach
Address: 16537 MO Hwy 5, Sunrise Beach, MO 65079

Continuing Authority: Same as above
Address: Same as above

Facility Name: Sunrise Beach WWTF
Facility Address: Intersection of Hwy 5 and Kula Bay Drive, Sunrise Beach, MO 65079

Legal Description: NW ¼, NE ¼, Sec. 16, T39N, R17W, Camden County
UTM Coordinates: X= 518213, Y= 4220052

Receiving Stream: Unnamed Tributary to Lake of the Ozarks (U)
First Classified Stream and ID: Lake of the Ozarks (L2) (07205) 303(d) list
USGS Basin & Sub-watershed No.: (10290109-0207)

is authorized to discharge from the facility described herein, in accordance with the effluent limitations and monitoring requirements as set forth herein:

FACILITY DESCRIPTION

Outfall #001 – POTW – SIC #4952

The use or operation of this facility shall be by or under the supervision of a Certified “C” Operator.

Flow equalization / Extended aeration / Tertiary filtration / Chemical addition for phosphorus removal / Ultraviolet disinfection /

Sludge disposal by contract hauler

Design population equivalent is 500.

Design flow is 50,000 gallons per day.

Design sludge production is 10.5 dry tons/year.

This permit authorizes only wastewater discharges under the Missouri Clean Water Law and the National Pollutant Discharge Elimination System; it does not apply to other regulated areas. This permit may be appealed in accordance with Section 621.250 RSMo, Section 640.013 RSMo and Section 644.051.6 of the Law.

June 1, 2014

Effective Date


Sara Parker Pauley, Director, Department of Natural Resources

May 31, 2019

Expiration Date


John Madros, Director, Water Protection Program

OUTFALL #001	TABLE A. FINAL EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS	PAGE NUMBER 2 of 6
		PERMIT NUMBER MO-0137278

The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The final effluent limitations shall become effective on **June 1, 2014**, and remain in effect until expiration of the permit. Such discharges shall be controlled, limited and monitored by the permittee as specified below:

EFFLUENT PARAMETER(S)	UNITS	FINAL EFFLUENT LIMITATIONS			MONITORING REQUIREMENTS	
		DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Flow	MGD	*		*	once/weekday***	24 hr. total
Biochemical Oxygen Demand ₅	mg/L		30	20	once/month	composite**
Total Suspended Solids	mg/L		30	20	once/month	composite**
<i>E. coli</i> (Note 1)	#/100 ml		630	126	once/month	grab
pH – Units	SU	****		****	once/month	grab
Ammonia as N (April 1 – Sept 30) (Oct 1 – March 31)	mg/L	3.7 7.5		1.4 2.9	once/month	grab
Oil & Grease	mg/L	15		10	once/month	grab
Total Nitrogen	mg/L	*		*	once/month	grab
Total Phosphorus	mg/L	*		*	once/month	grab
Aluminum, Total Recoverable (Note 2)	mg/L	*		*	once/month	grab
Iron, Total Recoverable (Note 2)	mg/L	*		*	once/month	grab

MONITORING REPORTS SHALL BE SUBMITTED MONTHLY; THE FIRST REPORT IS DUE JULY 28, 2014. THERE SHALL BE NO DISCHARGE OF FLOATING SOLIDS OR VISIBLE FOAM IN OTHER THAN TRACE AMOUNTS.

EFFLUENT PARAMETER(S)	UNITS	DAILY MINIMUM	WEEKLY AVERAGE MINIMUM	MONTHLY AVERAGE MINIMUM	MEASUREMENT FREQUENCY	SAMPLE TYPE
Dissolved Oxygen	mg/L	5.0		5.0	once/month	grab

MONITORING REPORTS SHALL BE SUBMITTED MONTHLY; THE FIRST REPORT IS DUE JULY 28, 2014.

Whole Effluent Toxicity (WET) test	% Survival	See Special Condition #17	once/permit cycle	24-hr composite**
------------------------------------	------------	---------------------------	-------------------	-------------------

WET TEST REPORTS SHALL BE SUBMITTED ONCE PER PERMIT CYCLE; THE FIRST REPORT IS DUE BY NOVEMBER 28, 2018.

- * Monitoring requirement only.
- ** A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampling device.
- *** Once each weekday means: Monday, Tuesday, Wednesday, Thursday, and Friday.
- **** pH is measured in pH units and is not to be averaged. The pH is limited to the range of 6.5-9.0 pH units.

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a geometric mean. The Weekly Average for *E. coli* will be expressed as a geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

Note 2 – If no Aluminum or Iron was used in a given sampling period, an actual analysis is not necessary. Simply report as “0 mg/L”.

TABLE B. INFLUENT MONITORING REQUIREMENTS		PAGE NUMBER 3 of 6	
		PERMIT NUMBER MO-0137278	
The facility is required to meet a removal efficiency of 85% or more as a monthly average. The monitoring requirements shall become effective upon issuance and remain in effect until expiration of the permit. To determine removal efficiencies, the influent wastewater shall be monitored by the permittee as specified below:			
SAMPLING LOCATION AND PARAMETER(S)	UNITS	MONITORING REQUIREMENTS	
		MEASUREMENT FREQUENCY	SAMPLE TYPE
Biochemical Oxygen Demand ₅	mg/L	once/month	composite**
Total Suspended Solids	mg/L	once/month	composite**
MONITORING REPORTS SHALL BE SUBMITTED <u>MONTHLY</u> ; THE FIRST REPORT IS DUE <u>JULY 28, 2014</u> .			

C. STANDARD CONDITIONS

In addition to specified conditions stated herein, this permit is subject to the attached Parts I, II, & III standard conditions dated November 1, 2013, May 1, 2013 & March 1, 2014, and hereby incorporated as though fully set forth herein.

D. SPECIAL CONDITIONS

1. This permit establishes final ammonia limitations based on Missouri's current Water Quality Standard. On August 22, 2013, the U.S. Environmental Protection Agency (EPA) published a notice in the Federal Register announcing of the final national recommended ambient water quality criteria for protection of aquatic life from the effects of ammonia in freshwater. The EPA's guidance, Final Aquatic Life Ambient Water Quality Criteria for Ammonia – Fresh Water 2013, is not a rule, nor automatically part of a state's water quality standards. States must adopt new ammonia criteria consistent with EPA's published ammonia criteria into their water quality standards that protect the designated uses of the water bodies. The Department of Natural Resources has initiated stakeholder discussions on how to best incorporate these new criteria into the State's rules. A date for when this rule change will occur has not been determined. Also, refer to Section VI of this permit's factsheet for further information including estimated future effluent limits for this facility. It is recommended the permittee view the Department's 2013 EPA criteria Factsheet located at <http://dnr.mo.gov/pubs/pub2481.htm>.
2. This permit may be reopened and modified, or alternatively revoked and reissued, to:
 - (a) Comply with any applicable effluent standard or limitation issued or approved under Sections 301(b)(2)(C) and (D), 304(b)(2), and 307(a) (2) of the Clean Water Act, if the effluent standard or limitation so issued or approved:
 - (1) contains different conditions or is otherwise more stringent than any effluent limitation in the permit; or
 - (2) controls any pollutant not limited in the permit.
 - (b) Incorporate new or modified effluent limitations or other conditions, if the result of a waste load allocation study, toxicity test or other information indicates changes are necessary to assure compliance with Missouri's Water Quality Standards.
 - (c) Incorporate new or modified effluent limitations or other conditions if, as the result of a watershed analysis, a Total Maximum Daily Load (TMDL) limitation is developed for the receiving waters which are currently included in Missouri's list of waters of the state not fully achieving the state's water quality standards, also called the 303(d) list.
 - (d) Incorporate the requirement to develop a pretreatment program pursuant to 40 CFR 403.8(a) when the Director of the Water Protection Program determines that a pretreatment program is necessary due to any new introduction of pollutants into the Publically Owned Treatment Works or any substantial change in the volume or character of pollutants being introduced. The permit as modified or reissued under this paragraph shall also contain any other requirements of the Clean Water Act then applicable.
3. All outfalls must be clearly marked in the field.
4. Permittee will cease discharge by connection to a facility with an area-wide management plan per 10 CSR 20-6.010(3)(B) within 90 days of notice of its availability.
5. Water Quality Standards
 - (a) To the extent required by law, discharges to waters of the state shall not cause a violation of water quality standards rule under 10 CSR 20-7.031, including both specific and general criteria.
 - (b) General Criteria. The following general water quality criteria shall be applicable to all waters of the state at all times including mixing zones. No water contaminant, by itself or in combination with other substances, shall prevent the waters of the state from meeting the following conditions:
 - (1) Waters shall be free from substances in sufficient amounts to cause the formation of putrescent, unsightly or harmful bottom deposits or prevent full maintenance of beneficial uses;

D. SPECIAL CONDITIONS (continued)

- (2) Waters shall be free from oil, scum and floating debris in sufficient amounts to be unsightly or prevent full maintenance of beneficial uses;
- (3) Waters shall be free from substances in sufficient amounts to cause unsightly color or turbidity, offensive odor or prevent full maintenance of beneficial uses;
- (4) Waters shall be free from substances or conditions in sufficient amounts to result in toxicity to human, animal or aquatic life;
- (5) There shall be no significant human health hazard from incidental contact with the water;
- (6) There shall be no acute toxicity to livestock or wildlife watering;
- (7) Waters shall be free from physical, chemical or hydrologic changes that would impair the natural biological community;
- (8) Waters shall be free from used tires, car bodies, appliances, demolition debris, used vehicles or equipment and solid waste as defined in Missouri's Solid Waste Law, section 260.200, RSMo, except as the use of such materials is specifically permitted pursuant to section 260.200-260.247.

6. Changes in Discharges of Toxic Substances

The permittee shall notify the Director as soon as it knows or has reason to believe:

- (a) That any activity has occurred or will occur which would result in the discharge of any toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels:"
 - (1) One hundred micrograms per liter (100 µg/L);
 - (2) Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,5 dinitrophenol and for 2-methyl-4, 6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
 - (3) Five (5) times the maximum concentration value reported for the pollutant in the permit application;
 - (4) The level established by the Director in accordance with 40 CFR 122.44(f).
- (b) That they have begun or expect to begin to use or manufacture as an intermediate or final product or byproduct any toxic pollutant, which was not reported in the permit application.

7. Report as no-discharge when a discharge does not occur during the report period.

8. It is a violation of the Missouri Clean Water Law to fail to pay fees associated with this permit (644.055 RSMo).

9. The permittee shall comply with any applicable requirements listed in 10 CSR 20-9, unless the facility has received written notification that the Department has approved a modification to the requirements. The monitoring frequencies contained in this permit shall not be construed by the permittee as a modification of the monitoring frequencies listed in 10 CSR 20-9. If a modification of the monitoring frequencies listed in 10 CSR 20-9 is needed, the permittee shall submit a written request to the Department for review and, if deemed necessary, approval.

10. Bypasses, as defined in 10 CSR 20-7.015(9)(G), are not authorized at this facility and are subject to 40 CFR 122.41(m). If a bypass occurs, the permittee shall report in accordance to 40 CFR 122.41(m)(3)(i), and with Standard Condition Part I, Section B, subsection 2.b. Relevant information shall be provided orally within 24 hours from the time the permittee becomes aware of a bypass, and shall be reported to the Southwest Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours.

11. The facility must be sufficiently secured to restrict entry by children, livestock and unauthorized persons as well as to protect the facility from vandalism.

12. At least one gate must be provided to access the wastewater treatment facility and provide for maintenance and mowing. The gate shall remain closed except when temporarily opened by; the permittee to access the facility, perform operational monitoring, sampling, maintenance, mowing, or for inspections by the Department. The gate shall be closed and locked when the facility is not staffed.

13. At least one (1) warning sign shall be placed on each side of the facility enclosure in such positions as to be clearly visible from all directions of approach. There shall also be one (1) sign placed for every five hundred feet (500') (150 m) of the perimeter fence. A sign shall also be placed on each gate. Minimum wording shall be SEWAGE TREATMENT FACILITY—KEEP OUT. Signs shall be made of durable materials with characters at least two inches (2") high and shall be securely fastened to the fence, equipment or other suitable locations.

14. An Operation and Maintenance (O & M) manual shall be maintained by the permittee and made available to the operator. The O & M manual shall include key operating procedures and a brief summary of the operation of the facility.

D. SPECIAL CONDITIONS (continued)

15. An all-weather access road shall be provided to the treatment facility.
16. The discharge from the wastewater treatment facility shall be conveyed to the receiving stream via a closed pipe or a paved or rip-rapped open channel. Sheet or meandering drainage is not acceptable. The outfall sewer shall be protected against the effects of floodwater, ice or other hazards as to reasonably insure its structural stability and freedom from stoppage. The outfall shall be maintained so that a sample of the effluent can be obtained at a point after the final treatment process and before the discharge mixes with the receiving waters.
17. Whole Effluent Toxicity (WET) Test shall be conducted as follows: (Note to permit writers: please use the appropriate and latest version of WET testing contained in the departments T drive).

SUMMARY OF ACUTE WET TESTING FOR THIS PERMIT				
OUTFALL	AEC	FREQUENCY	SAMPLE TYPE	MONTH
001	100%	Once/permit cycle	24 hr. composite*	Any in the fourth year

* A 24-hour composite sample is composed of 48 aliquots (subsamples) collected at 30 minute intervals by an automatic sampler.

Dilution Series						
100% effluent	50% effluent	25% effluent	12.5% effluent	6.25% effluent	(Control) 100% upstream, if available	(Control) 100% Lab Water, also called synthetic water

(a) Test Schedule and Follow-Up Requirements

- (1) Perform a MULTIPLE-dilution acute WET test in the months and at the frequency specified above. For tests which are successfully passed, submit test results using the Department's WET test report form #MO-780-1899 along with complete copies of the test reports as received from the laboratory, including copies of chain-of-custody forms within 30 calendar days of availability to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102. If the effluent passes the test, do not repeat the test until the next test period.
 - (i) Chemical and physical analysis of the upstream control and effluent sample shall occur immediately upon being received by the laboratory, prior to any manipulation of the effluent sample beyond preservation methods consistent with federal guidelines for WET testing that are required to stabilize the sample during shipping.
 - (ii) Any and all chemical or physical analysis of the effluent sample performed in conjunction with the WET test shall be performed at the 100% Effluent concentration in addition to analysis performed upon any other effluent concentration.
 - (iii) All chemical analyses included in the Missouri Department of Natural Resources WET test report form #MO-780-1899 shall be performed and results shall be recorded in the appropriate field of the report form.
- (2) The WET test will be considered a failure if mortality observed in effluent concentrations for either specie, equal to or less than the AEC, is significantly different (at the 95% confidence level; $p = 0.05$) than that observed in the upstream receiving-water control sample. Where upstream receiving water is not available, synthetic laboratory control water may be used.
- (3) All failing test results along with complete copies of the test reports as received from the laboratory, INCLUDING THOSE TESTS CONDUCTED UNDER CONDITION (3) BELOW, shall be reported to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102 within 14 calendar days of the availability of the results.
- (4) If the effluent fails the test for BOTH test species, a multiple dilution test shall be performed for BOTH test species within 30 calendar days and biweekly thereafter (for storm water, tests shall be performed on the next and subsequent storm water discharges as they occur, but not less than 7 days apart) until one of the following conditions are met: Note: Written request regarding single species multiple dilution accelerated testing will be address by THE WATER PROTECTION PROGRAM on a case by case basis.
 - (i) THREE CONSECUTIVE MULTIPLE-DILUTION TESTS PASS. No further tests need to be performed until next regularly scheduled test period.
 - (ii) A TOTAL OF THREE MULTIPLE-DILUTION TESTS FAIL.
- (5) Follow-up tests do not negate an initial failed test.
- (6) The permittee shall submit a summary of all test results for the test series along with complete copies of the test reports as received from the laboratory to the WATER PROTECTION PROGRAM, P.O. Box 176, Jefferson City, MO 65102 within 14 calendar days of the third failed test.

D. SPECIAL CONDITIONS (continued)

- (7) Additionally, the following shall apply upon failure of the third follow up MULTIPLE DILUTION test. The permittee should contact THE WATER PROTECTION PROGRAM within 14 calendar days from availability of the test results to ascertain as to whether a TIE or TRE is appropriate. If the permittee does not contact THE WATER PROTECTION PROGRAM upon the third follow up test failure, a toxicity identification evaluation (TIE) or toxicity reduction evaluation (TRE) is automatically triggered. The permittee shall submit a plan for conducting a TIE or TRE to the WATER PROTECTION PROGRAM within 60 calendar days of the date of the automatic trigger or DNR's direction to perform either a TIE or TRE. This plan must be approved by DNR before the TIE or TRE is begun. A schedule for completing the TIE or TRE shall be established in the plan approval.
 - (8) Upon DNR's approval, the TIE/TRE schedule may be modified if toxicity is intermittent during the TIE/TRE investigations. A revised WET test schedule may be established by DNR for this period.
 - (9) If a previously completed TIE has clearly identified the cause of toxicity, additional TIEs will not be required as long as effluent characteristics remain essentially unchanged and the permittee is proceeding according to a DNR approved schedule to complete a TRE and reduce toxicity. Regularly scheduled WET testing as required in the permit, without the follow-up requirements, will be required during this period.
 - (10) When WET test sampling is required to run over one DMR period, each DMR report shall contain a copy of the Department's WET test report form that was generated during the reporting period.
 - (11) Submit a concise summary in tabular format of all WET test results with the annual report.
- (b) Test Conditions
- (1) Test Type: Acute Static non-renewal
 - (2) All tests, including repeat tests for previous failures, shall include both test species listed below unless approved by the department on a case by case basis.
 - (3) Test species: Ceriodaphnia dubia and Pimephales promelas (fathead minnow). Organisms used in WET testing shall come from cultures reared for the purpose of conducting toxicity tests and cultured in a manner consistent with the most current USEPA guidelines. All test animals shall be cultured as described in the most current edition of Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms.
 - (4) Test period: 48 hours at the "Allowable Effluent Concentration" (AEC) specified above.
 - (5) Upstream receiving stream water shall be used as dilution water. If upstream water is unavailable or if mortality in the upstream water exceeds 10%, "reconstituted" water will be used as dilution water. Procedures for generating reconstituted water will be supplied by the MDNR upon request.
 - (6) Tests will be run with 100% receiving-stream water (if available), collected upstream of the outfall at a point beyond any influence of the effluent, and reconstituted water.
 - (7) If reconstituted-water control mortality for a test species exceeds 10%, the entire test will be rerun.
 - (8) If upstream control mortality exceeds 10%, the entire test will be rerun using reconstituted water as the dilutant.
 - (9) Whole-effluent-toxicity test shall be consistent with the most current edition of Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms.

**MISSOURI DEPARTMENT OF NATURAL RESOURCES
FACT SHEET
FOR THE PURPOSE OF NEW CONSTRUCTION
OF
MO-0137278
SUNRISE BEACH WWTF**

The Federal Water Pollution Control Act ("Clean Water Act" Section 402 Public Law 92-500 as amended) established the National Pollution Discharge Elimination System (NPDES) permit program. This program regulates the discharge of pollutants from point sources into the waters of the United States, and the release of storm water from certain point sources. All such discharges are unlawful without a permit (Section 301 of the "Clean Water Act"). After a permit is obtained, a discharge not in compliance with all permit terms and conditions is unlawful. Missouri State Operating Permits (MSOPs) are issued by the Director of the Missouri Department of Natural Resources (Department) under an approved program, operating in accordance with federal and state laws (Federal "Clean Water Act" and "Missouri Clean Water Law" Section 644 as amended). MSOPs are issued for a period of five (5) years unless otherwise specified.

As per [40 CFR Part 124.8(a)] and [10 CSR 20-6.020(1)2.] a Factsheet shall be prepared to give pertinent information regarding the applicable regulations, rationale for the development of effluent limitations and conditions, and the public participation process for the Missouri State Operating Permit (operating permit) listed below.

A Factsheet is not an enforceable part of an operating permit.

This Factsheet is for a Minor

Part I – Facility Information

Facility Type: POTW - SIC #4952

Facility Description:

This is a proposed new treatment facility.

Flow equalization / Extended aeration / Tertiary filtration / Chemical addition for phosphorus removal / Ultraviolet disinfection / Sludge disposal by contract hauler

Have any changes occurred at this facility or in the receiving water body that effects effluent limit derivation?

- No.

Application Date: December 6, 2012

OUTFALL(S) TABLE:

OUTFALL	DESIGN FLOW (CFS)	TREATMENT LEVEL	EFFLUENT TYPE	DISTANCE TO CLASSIFIED SEGMENT (MI)
#001	0.078	Secondary	Municipal	0.1

Receiving Water Body's Water Quality & Facility Performance History:

None, since this is a new wastewater treatment facility.

Comments:

None.

Part II – Operator Certification Requirements

Applicable ; This facility is required to have a certified operator.

As per [10 CSR 20-6.010(8) Terms and Conditions of a Permit], permittees shall operate and maintain facilities to comply with the Missouri Clean Water Law and applicable permit conditions and regulations. Operators or supervisors of operations at regulated wastewater treatment facilities shall be certified in accordance with [10 CSR 20-9.020(2)] and any other applicable state law or regulation. As per [10 CSR 20-9.020(2)(A)], requirements for operation by certified personnel shall apply to all wastewater treatment systems, if applicable, as listed below:

Check boxes below that are applicable to the facility;

- Owned or operated by or for:
 - Municipalities

Each of the above entities are only applicable if they have a Population Equivalent greater than two hundred (200) and/or fifty (50) or more service connections.

This facility currently requires an operator with a “C” Certification Level. Please see **Appendix 1 - Classification Worksheet**. Modifications made to the wastewater treatment facility may cause the classification to be modified.

Operator’s Name: Steve Hollaway
Certification Number: 10635
Certification Level: C

The listing of the operator above only signifies that staff drafting this operating permit have reviewed appropriate Department records and determined that the name listed on the operating permit application has the correct and applicable Certification Level.

Part III– Operational Monitoring

As per [10 CSR 20-9.010(4)], the facility is not required to conduct operational monitoring.

Part IV – Receiving Stream Information

10 CSR 20-7.031 Missouri Water Quality Standards, the Department defines the Clean Water Commission water quality objectives in terms of "water uses to be maintained and the criteria to protect those uses." The receiving stream and/or 1st classified receiving stream's beneficial water uses to be maintained are located in the Receiving Stream Table located below in accordance with [10 CSR 20-7.031(3)].

RECEIVING STREAM(S) TABLE:

WATER-BODY NAME	CLASS	WBID	DESIGNATED USES*	12-DIGIT HUC	EDU**
Unnamed Tributary to Lake of the Ozarks	U	N/A	General Criteria	10290109-0207	Ozark / Highlands
Lake of the Ozarks	L2	07205	AQL, LWW, SCR, WBC(A)		

* - Irrigation (IRR), Livestock & Wildlife Watering (LWW), Protection of Warm Water Aquatic Life and Human Health-Fish Consumption (AQL), Cool Water Fishery(CLF), Cold Water Fishery (CDF), Whole Body Contact Recreation (WBC), Secondary Contact Recreation (SCR), Drinking Water Supply (DWS), Industrial (IND), Groundwater (GRW).

** - Ecological Drainage Unit

RECEIVING STREAM(S) LOW-FLOW VALUES:

RECEIVING STREAM (U, C, P)	LOW-FLOW VALUES (CFS)		
	1Q10	7Q10	30Q10
Unnamed Tributary to Lake of the Ozarks (U)	0	0	0

MIXING CONSIDERATIONS

Mixing Zone: Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(a)].

Zone of Initial Dilution: Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(b)].

RECEIVING STREAM MONITORING REQUIREMENTS:

No receiving water monitoring requirements recommended at this time.

Part V – Rationale and Derivation of Effluent Limitations & Permit Conditions

ALTERNATIVE EVALUATIONS FOR NEW FACILITIES:

As per [10 CSR 20-7.015(4)(A)], discharges to losing streams shall be permitted only after other alternatives including land application, discharges to a gaining stream and connection to a regional wastewater treatment facility have been evaluated and determined to be unacceptable for environmental and/or economic reasons.

Not Applicable ; The facility does not discharge to a Losing Stream as defined by [10 CSR 20-2.010(36)] & [10 CSR 20-7.031(1)(N)], or is an existing facility.

ANTI-BACKSLIDING:

A provision in the Federal Regulations [CWA §303(d)(4); CWA §402(c); 40 CFR Part 122.44(I)] that requires a reissued permit to be as stringent as the previous permit with some exceptions.

- New facility, backsliding does not apply.

ANTIDEGRADATION:

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(2)], the Department is to document by means of Antidegradation Review that the use of a water body's available assimilative capacity is justified. Degradation is justified by documenting the socio-economic importance of a discharging activity after determining the necessity of the discharge.

- New and/or expanded discharge, please see **APPENDIX 3 FOR ANTIDEGRADATION ANALYSIS.**

AREA-WIDE WASTE TREATMENT MANAGEMENT & CONTINUING AUTHORITY:

As per [10 CSR 20-6.010(3)(B)], ...An applicant may utilize a lower preference continuing authority by submitting, as part of the application, a statement waiving preferential status from each existing higher preference authority, providing the waiver does not conflict with any area-wide management plan approved under section 208 of the Federal Clean Water Act or any other regional sewage service and treatment plan approved for higher preference authority by the Department.

BIOSOLIDS & SEWAGE SLUDGE:

Biosolids are solid materials resulting from domestic wastewater treatment that meet federal and state criteria for beneficial uses (i.e. fertilizer). Sewage sludge is solids, semi-solids, or liquid residue generated during the treatment of domestic sewage in a treatment works; including but not limited to, domestic septage; scum or solids removed in primary, secondary, or advanced wastewater treatment process; and a material derived from sewage sludge. Sewage sludge does not include ash generated during the firing of sewage sludge in a sewage sludge incinerator or grit and screening generated during preliminary treatment of domestic sewage in a treatment works. Additional information regarding biosolids and sludge is located at the following web address:

<http://dnr.mo.gov/env/wpp/pub/index.html>, items WQ422 through WQ449.

- Permittee is not authorized to land apply biosolids. Sludge/biosolids are removed by contract hauler, incinerated, stored in the lagoon, etc.

COMPLIANCE AND ENFORCEMENT:

Enforcement is the action taken by the Water Protection Program (WPP) to bring an entity into compliance with the Missouri Clean Water Law, its implementing regulations, and/or any terms and conditions of an operating permit. The primary purpose of the enforcement activity in the WPP is to resolve violations and return the entity to compliance.

Not Applicable ; The permittee/facility is not currently under Water Protection Program enforcement action.

PRETREATMENT PROGRAM:

The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to or in lieu of discharging or otherwise introducing such pollutants into a Publicly Owned Treatment Works [40 CFR Part 403.3(q)].

Pretreatment programs are required at any POTW (or combination of POTW operated by the same authority) and/or municipality with a total design flow greater than 5.0 MGD and receiving industrial wastes that interfere with or pass through the treatment works or are otherwise subject to the pretreatment standards. Pretreatment programs can also be required at POTWs/municipals with a design flow less than 5.0 MGD if needed to prevent interference with operations or pass through.

Several special conditions pertaining to the permittee's pretreatment program may be included in the permit, and are as follows:

- Implementation and enforcement of the program,
- Annual pretreatment report submittal,
- Submittal of list of industrial users,
- Technical evaluation of need to establish local limitations, and
- Submittal of the results of the evaluation

Not Applicable ; The permittee, at this time, is not required to have a Pretreatment Program or does not have an approved pretreatment program.

REASONABLE POTENTIAL ANALYSIS (RPA):

Federal regulation [40 CFR Part 122.44(d)(1)(i)] requires effluent limitations for all pollutants that are or may be discharged at a level that will cause or have the reasonable potential to cause or contribute to an in-stream excursion above narrative or numeric water quality standard.

In accordance with [40 CFR Part 122.44(d)(iii)] if the permit writer determines that any given pollutant has the reasonable potential to cause, or contribute to an in-stream excursion above the WQS, the permit must contain effluent limits for that pollutant.

Not Applicable ; A RPA was not conducted for this facility.

REMOVAL EFFICIENCY:

Removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD₅) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals.

Applicable ; Secondary Treatment is 85% removal [40 CFR Part 133.102(a)(3) & (b)(3)].

SANITARY SEWER OVERFLOWS (SSO) AND INFLOW AND INFILTRATION (I&I):

Sanitary Sewer Overflows (SSOs) are defined as an untreated or partially treated sewage release are considered bypassing under state regulation [10 CSR 20-2.010(11)] and should not be confused with the federal definition of bypass. SSO's have a variety of causes including blockages, line breaks, and sewer defects that allow excess storm water and ground water to (1) enter and overload the collection system, and (2) overload the treatment facility. Additionally, SSO's can be also be caused by lapses in sewer system operation and maintenance, inadequate sewer design and construction, power failures, and vandalism. SSOs also include overflows out of manholes and onto city streets, sidewalks, and other terrestrial locations.

Additionally, Missouri RSMo §644.026.1 mandates that the Department require proper maintenance and operation of treatment facilities and sewer systems and proper disposal of residual waste from all such facilities.

- Not applicable. This facility is not required to develop or implement a program for maintenance and repair of the collection system; however, it is a violation of Missouri State Environmental Laws and Regulations to allow untreated wastewater to discharge to waters of the state.

SCHEDULE OF COMPLIANCE (SOC):

A schedule of remedial measures included in a permit, including an enforceable sequence of interim requirements (actions, operations, or milestone events) leading to compliance with the Missouri Clean Water Law, its implementing regulations, and/or the terms and conditions of an operating permit.

Not Applicable ; This permit does not contain a SOC.

STORM WATER POLLUTION PREVENTION PLAN (SWPPP):

In accordance with 40 CFR 122.44(k) *Best Management Practices (BMPs)* to control or abate the discharge of pollutants when: (1) Authorized under section 304(e) of the Clean Water Act (CWA) for the control of toxic pollutants and hazardous substances from ancillary industrial activities; (2) Authorized under section 402(p) of the CWA for the control of storm water discharges; (3) Numeric effluent limitations are infeasible; or (4) the practices are reasonably necessary to achieve effluent limitations and standards or to carry out the purposes and intent of the CWA.

In accordance with the EPA's *Developing Your Stormwater Pollution Prevention Plan, A Guide for Industrial Operators*, (Document number EPA 833-B-09-002) [published by the United States Environmental Protection Agency (USEPA) in February 2009], BMPs are measures or practices used to reduce the amount of pollution entering (regarding this operating permit) waters of the state. BMPs may take the form of a process, activity, or physical structure.

Additionally in accordance with the Storm Water Management, a SWPPP is a series of steps and activities to (1) identify sources of pollution or contamination, and (2) select and carry out actions which prevent or control the pollution of storm water discharges.

Not Applicable ; At this time, the permittee is not required to develop and implement a SWPPP.

VARIANCE:

As per the Missouri Clean Water Law § 644.061.4, variances shall be granted for such period of time and under such terms and conditions as shall be specified by the commission in its order. The variance may be extended by affirmative action of the commission. In no event shall the variance be granted for a period of time greater than is reasonably necessary for complying with the Missouri Clean Water Law §§644.006 to 644.141 or any standard, rule or regulation promulgated pursuant to Missouri Clean Water Law §§644.006 to 644.141.

Not Applicable ; This operating permit is not drafted under premises of a petition for variance.

WASTELOAD ALLOCATIONS (WLA) FOR LIMITS:

As per [10 CSR 20-2.010(78)], the amount of pollutant each discharger is allowed by the Department to release into a given stream after the Department has determined total amount of pollutant that may be discharged into that stream without endangering its water quality.

Applicable ; Wasteload allocations were calculated where applicable using water quality criteria or water quality model results and the dilution equation below:

$$C_e = \frac{(Q_e + Q_s)C - (C_s \times Q_s)}{(Q_e)} \quad (\text{EPA/505/2-90-001, Section 4.5.5})$$

Where C = downstream concentration
Cs = upstream concentration
Qs = upstream flow
Ce = effluent concentration
Qe = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

Number of Samples "n":

Additionally, in accordance with the TSD for water quality-based permitting, effluent quality is determined by the underlying distribution of daily values, which is determined by the Long Term Average (LTA) associated with a particular Wasteload Allocation (WLA) and by the Coefficient of Variation (CV) of the effluent concentrations. Increasing or decreasing the monitoring frequency does not affect this underlying distribution or treatment performance, which should be, at a minimum, be targeted to comply with the values dictated by the WLA. Therefore, it is recommended that the actual planned frequency of monitoring normally be used to determine the value of "n" for calculating the AML. However, in situations where monitoring frequency is once per month or less, a higher value for "n" must be assumed for AML derivation purposes. Thus, the statistical procedure being employed using an assumed number of samples is "n = 4" at a minimum. For Total Ammonia as Nitrogen, "n = 30" is used.

WLA MODELING:

There are two general types of effluent limitations, technology-based effluent limits (TBELs) and water quality based effluent limits (WQBELs). If TBELs do not provide adequate protection for the receiving waters, then WQBEL must be used.

Not Applicable ; A WLA study was either not submitted or determined not applicable by Department staff.

WATER QUALITY STANDARDS:

Per [10 CSR 20-7.031(3)], General Criteria shall be applicable to all waters of the state at all times including mixing zones. Additionally, [40 CFR 122.44(d)(1)] directs the Department to establish in each NPDES permit to include conditions to achieve water quality established under Section 303 of the Clean Water Act, including State narrative criteria for water quality.

WHOLE EFFLUENT TOXICITY (WET) TEST:

A WET test is a quantifiable method of determining if a discharge from a facility may be causing toxicity to aquatic life by itself, in combination with or through synergistic responses when mixed with receiving stream water.

Applicable ; Under the federal Clean Water Act (CWA) §101(a)(3), requiring WET testing is reasonably appropriate for site-specific Missouri State Operating Permits for discharges to waters of the state issued under the National Pollutant Discharge Elimination System (NPDES). WET testing is also required by 40 CFR 122.44(d)(1). WET testing ensures that the provisions in the 10 CSR 20-6.010(8)(A)7. and the Water Quality Standards 10 CSR 20-7.031(3)(D),(F),(G),(I)2.A & B are being met. Under [10 CSR 20-6.010(8)(A)4], the Department may require other terms and conditions that it deems necessary to assure compliance with the Clean Water Act and related regulations of the Missouri Clean Water Commission. In addition the following MCWL apply: §§644.051.3 requires the Department to set permit conditions that comply with the MCWL and CWA; 644.051.4 specifically references toxicity as an item we must consider in writing permits (along with water quality-based effluent limits, pretreatment, etc...); and 644.051.5 is the basic authority to require testing conditions. WET test will be required by facilities meeting the following criteria:

Facility is a municipality or domestic discharger with a Design Flow ≥ 22,500 gpd.

40 CFR 122.41(M) - BYPASSES:

The federal Clean Water Act (CWA), Section 402 prohibits wastewater dischargers from “bypassing” untreated or partially treated sewage (wastewater) beyond the headworks. A bypass is defined as an intentional diversion of waste streams from any portion of a treatment facility, [40 CFR 122.41(m)(1)(i)]. Additionally, Missouri regulation 10 CSR 20-2.010(11) defines a bypass as the diversion of wastewater from any portion of wastewater treatment facility or sewer system to waters of the state. Only under exceptional and specified limitations do the federal regulations allow for a facility to bypass some or all of the flow from its treatment process. Bypasses are prohibited by the CWA unless a permittee can meet all of the criteria listed in 40 CFR 122.41(m)(4)(i)(A), (B), & (C). Any bypasses from this facility are subject to the reporting required in 40 CFR 122.41(l)(6) and per Missouri’s Standard Conditions I, Section B, part 2.b. Additionally, Anticipated Bypasses include bypasses from peak flow basins or similar devices designed for peak wet weather flows.

Not Applicable ; This facility does not anticipate bypassing.

303(d) LIST & TOTAL MAXIMUM DAILY LOAD (TMDL):

Section 303(d) of the federal Clean Water Act requires that each state identify waters that are not meeting water quality standards and for which adequate water pollution controls have not been required. Water quality standards protect such beneficial uses of water as whole body contact (such as swimming), maintaining fish and other aquatic life, and providing drinking water for people, livestock and wildlife. The 303(d) list helps state and federal agencies keep track of waters that are impaired but not addressed by normal water pollution control programs.

A TMDL is a calculation of the maximum amount of a given pollutant that a body of water can absorb before its water quality is affected. If a water body is determined to be impaired as listed on the 303(d) list, then a watershed management plan will be developed that shall include the TMDL calculation

Not Applicable ; This facility does not discharge to a 303(d) listed stream.

Part VI – 2013 Water Quality Criteria for Ammonia

Upcoming changes to the Water Quality Standard for ammonia may require significant upgrades to wastewater treatment facilities.

On August 22, 2013, the U.S. Environmental Protection Agency (EPA) finalized new water quality criteria for ammonia, based on toxicity studies of mussels and gill breathing snails. Missouri's current ammonia criteria are based on toxicity testing of several species, but did not include data from mussels or gill breathing snails. Missouri is home to 69 of North America's mussel species, which are spread across the state. According to the Missouri Department of Conservation nearly two-thirds of the mussel species in Missouri are considered to be "of conservation concern". Nine species are listed as federally endangered, with an additional species currently proposed as endangered and another species proposed as threatened.

The adult forms of mussels that are seen in rivers, lakes, and streams are sensitive to pollutants because they are sedentary filter feeders. They vacuum up many pollutants with the food they bring in and cannot escape to new habitats, so they can accumulate toxins in their bodies and die. But very young mussels, called glochidia, are exceptionally sensitive to ammonia in water. As a result of a citizen suit, the EPA was compelled to conduct toxicity testing and develop ammonia water quality criteria that would be protective if young mussels may be present in a waterbody. These new criteria will apply to any discharge with ammonia levels that may pose a reasonable potential to violate the standards. Nearly all discharging domestic wastewater treatment facilities (cities, subdivisions, mobile home parks, etc.), as well as certain industrial and stormwater dischargers with ammonia in their effluent, will be affected by this change in the regulations.

When new water quality criteria are established by the EPA, states must adopt them into their regulations in order to keep their authorization to issue permits under the National Pollutant Discharge Elimination System (NPDES). States are required to review their water quality standards every three years, and if new criteria have been developed they must be adopted. States may be more protective than the Federal requirements, but not less protective. Missouri does not have the resources to conduct the studies necessary for developing new water quality standards, and therefore our standards mirror those developed by the EPA; however, we will utilize any available flexibility based on actual species of mussels that are native to Missouri and their sensitivity to ammonia.

Many treatment facilities in Missouri are currently scheduled to be upgraded to comply with the current water quality standards. But these new ammonia standards may require a different treatment technology than the one being considered by the permittee. It is important that permittees discuss any new and upcoming requirements with their consulting engineers to ensure that their treatment systems are capable of complying with the new requirements. The Department encourages permittees to construct treatment technologies that can attain effluent quality that supports the EPA ammonia criteria.

Ammonia toxicity varies by temperature and by pH of the water. Assuming a stable pH value, but taking into account winter and summer temperatures, Missouri includes two seasons of ammonia effluent limitations. Current effluent limitations in this permit are:

Summer – 3.7 mg/L daily maximum, 1.4 mg/L monthly average.

Winter – 7.5 mg/L daily maximum, 2.9 mg/L monthly average.

Under the new EPA criteria, where mussels of the family Unionidae are present or expected to be present, the estimated effluent limitations for a facility in a location such as this that discharges to a receiving stream with no mixing will be:

Summer – 1.7 mg/L daily maximum, 0.6 mg/L monthly average.

Winter – 5.6 mg/L daily maximum, 2.1 mg/L monthly average.

Actual effluent limits will depend in part on the actual performance of the facility.

Operating permits for facilities in Missouri must be written based on current statutes and regulations. Therefore permits will be written with the existing effluent limitations until the new standards are adopted. To aid permittees in decision making, an advisory will be added to permit Fact Sheets notifying permittees of the expected effluent limitations for ammonia. When setting schedules of compliance for ammonia effluent limitations, consideration will be given to facilities that have recently constructed upgraded facilities to meet the current ammonia limitations.

For more information on this topic feel free to contact the Missouri Department of Natural Resources, Water Protection Program, Water Pollution Control Branch, Operating Permits Section at (573) 751-1300.

Part VII – Effluent Limits Determination

APPLICABLE DESIGNATIONS OF WATERS OF THE STATE:

As per Missouri’s Effluent Regulations [10 CSR 20-7.015], the waters of the state are divided into the below listed seven (7) categories. Each category lists effluent limitations for specific parameters, which are presented in each outfall’s Effluent Limitation Table and further discussed in the Derivation & Discussion of Limits section.

Lake or Reservoir [10 CSR 20-7.015(3)]:
All Other Waters [10 CSR 20-7.015(8)]:

OUTFALL #001 – MAIN FACILITY OUTFALL

EFFLUENT LIMITATIONS TABLE:

PARAMETER	Unit	Basis for Limits	Daily Maximum	Weekly Average	Monthly Average	Modified	Previous Permit Limitations
Flow	MGD	1	*		*		
BOD ₅	mg/L	1		30	20		
TSS	mg/L	1		30	20		
pH	SU	1	6.5 – 9.0		6.5 – 9.0		
Ammonia as N (April 1 – Sept 30)	mg/L	2, 3, 5	3.7		1.4		
Ammonia as N (Oct 1 – March 31)	mg/L	2, 3, 5	7.5		2.9		
Dissolved Oxygen (DO)**	mg/L	3, 9	5.0 minimum		5.0 minimum		
Escherichia coli	***	1, 3		630	126		
Total Nitrogen	mg/L	1	*		*		
Total Phosphorus	mg/L	1	*		*		
Aluminum, Total Recoverable	mg/L	1	*		*		
Iron, Total Recoverable	mg/L	1	*		*		
Oil & Grease (mg/L)	mg/L	1, 3	15		10		
Whole Effluent Toxicity (WET) Test	% Survival	11	Please see WET Test in the Derivation and Discussion Section below.				

* - Monitoring requirement only.

** - For DO the Daily Maximum is a Daily Minimum and the Monthly Average is a Monthly Average Minimum.

*** - # of colonies/100mL; the Monthly Average for *E. coli* is a geometric mean.

Basis for Limitations Codes:

- | | |
|--|------------------------------------|
| 1. State or Federal Regulation/Law | 7. Antidegradation Policy |
| 2. Water Quality Standard (includes RPA) | 8. Water Quality Model |
| 3. Water Quality Based Effluent Limits | 9. Best Professional Judgment |
| 4. Lagoon Policy | 10. TMDL or Permit in lieu of TMDL |
| 5. Ammonia Policy | 11. WET Test Policy |
| 6. Antidegradation Review | |

OUTFALL #001 – DERIVATION AND DISCUSSION OF LIMITS:

- **Flow.** In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the Department, which may require the submittal of an operating permit modification.

- **Biochemical Oxygen Demand (BOD₅).**

–30 mg/L as a Weekly Average and 20 mg/L as a Monthly Average. Please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information**.

- **Total Suspended Solids (TSS).**

-30 mg/L as a Weekly Average and 20 mg/L as a Monthly Average. Please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the **Receiving Stream Information.**

- **pH.** Effluent limitation range is 6.5 – 9.0 Standard pH Units (SU), as per the applicable section of 10 CSR 20-7.015. pH is not to be averaged.

- **Total Ammonia Nitrogen.** Early Life Stages Present Total Ammonia Nitrogen criteria apply [10 CSR 20-7.031(4)(B)7.C. & Table B3] default pH 7.8 SU. Background total ammonia nitrogen = 0.01 mg/L. No mixing considerations allowed; therefore, WLA = appropriate criterion.

Season	Temp (°C)	pH (SU)	Total Ammonia Nitrogen CCC (mg/L)	Total Ammonia Nitrogen CMC (mg/L)
Summer	26	7.8	1.5	12.1
Winter	6	7.8	3.1	12.1

Summer: April 1 – September 30

Chronic WLA: $C_e = ((0.078 + 0.0)1.5 - (0.0 * 0.01))/0.078$
 $C_e = 1.5 \text{ mg/L}$

Acute WLA: $C_e = ((0.078 + 0.0)12.1 - (0.0 * 0.01))/0.078$
 $C_e = 12.1 \text{ mg/L}$

$LTA_c = 1.5 \text{ mg/L} (0.780) = 1.2 \text{ mg/L}$

[CV = 0.6, 99th Percentile, 30 day avg.]

$LTA_a = 12.1 \text{ mg/L} (0.321) = 3.88 \text{ mg/L}$

[CV = 0.6, 99th Percentile]

Use most protective number of LTA_c or LTA_a .

MDL = 1.2 mg/L (3.11) = 3.7 mg/L

[CV = 0.6, 99th Percentile]

AML = 1.2 mg/L (1.19) = 1.4 mg/L

[CV = 0.6, 95th Percentile, n=30]

Winter: October 1 – March 31

Chronic WLA: $C_e = ((0.078 + 0.0)3.1 - (0.0 * 0.01))/0.078$
 $C_e = 3.1 \text{ mg/L}$

Acute WLA: $C_e = ((0.078 + 0.0)12.1 - (0.0025 * 0.01))/0.078$
 $C_e = 12.1 \text{ mg/L}$

$LTA_c = 3.1 \text{ mg/L} (0.780) = 2.4 \text{ mg/L}$

[CV = 0.6, 99th Percentile, 30 day avg.]

$LTA_a = 12.1 \text{ mg/L} (0.321) = 3.9 \text{ mg/L}$

[CV = 0.6, 99th Percentile]

Use most protective number of LTA_c or LTA_a .

MDL = 2.4 mg/L (3.11) = 7.5 mg/L

[CV = 0.6, 99th Percentile]

AML = 2.4 mg/L (1.19) = 2.9 mg/L

[CV = 0.6, 95th Percentile, n=30]

- **Dissolved Oxygen.** Effluent dissolved oxygen of 5.0 mg/L minimum was proposed in the Antidegradation Report submitted by LO Environmental, LLC. 5.0 mg/L was determine to protect aquatic life.
- **Escherichia coli (E. coli).** Monthly average of 126 per 100 ml as a geometric mean and Weekly Average of 630 during the recreational season (April 1 – October 31), to protect Whole Body Contact Recreation (A) designated use of the receiving stream, as per 10 CSR 20-7.031(4)(C). An effluent limit for both monthly average and weekly average is required by 40 CFR 122.45(d).
- **Oil & Grease.** Conventional pollutant, effluent limitation for protection of aquatic life; 10 mg/L monthly average, 15 mg/L daily maximum.
- **Total Phosphorus.** Lake of the Ozarks is 303(d) listed for total phosphorus. Monitoring only will be required to gather information about the facility and to determine the impacts if any to the lake for this parameter. The department does not have an approved implementation plan for nutrients.

- **Total Nitrogen** Lake of the Ozarks is 303(d) listed for total nitrogen. No water quality standards are available for total nitrogen. Monitoring only will be required to gather information about the facility and to determine the impacts if any to the lake for this parameter. The department does not have an approved implementation plan for nutrients.
- **Aluminum, Total Recoverable** Monitoring requirement only. This facility uses chemicals for phosphorous removal that may contain aluminum. Monitoring is required to determine if reasonable potential exists for this facility's discharge to exceed water quality standards for Aluminum (Total Recoverable).
- **Iron, Total Recoverable.** Monitoring requirement only. This facility uses chemicals for phosphorous removal that may contain iron. Monitoring is required to determine if reasonable potential exists for this facility's discharge to exceed water quality standards for Iron (Total Recoverable).
- **WET Test.** WET Testing schedules and intervals are established in accordance with the Department's Permit Manual; Section 5.2 *Effluent Limits / WET Testing for Compliance Bio-monitoring*. It is recommended that WET testing be conducted during the period of lowest stream flow.
 - Acute
 - No less than ONCE/PERMIT CYCLE:**
 - Municipality or domestic facility with a design flow \geq 22,500 gpd, but less than 1.0 MGD.

Acute and/or Chronic Allowable Effluent Concentrations (AECs) for facilities that discharge to unclassified, Class C, Class P (with default Mixing Considerations), or Lakes [10 CSR 20-7.031(4)(A)4.B.(IV)(b)] are 100%, 50%, 25%, 12.5%, & 6.25%.

Minimum Sampling and Reporting Frequency Requirements.

PARAMETER	SAMPLING FREQUENCY	REPORTING FREQUENCY
Flow	once/weekday	once/month
BOD ₅	once/month	once/month
TSS	once/month	once/month
pH	once/month	once/month
Ammonia as N	once/month	once/month
<i>E. coli</i>	once/month	once/month
Total Phosphorus	once/month	once/month
Total Nitrogen	once/month	once/month
Oil & Grease	once/month	once/month
Dissolved Oxygen	once/month	once/month

Sampling Frequency Justification:

This facility is a new facility monthly sampling is required to determine if the facility will be in compliance with the operating permit in accordance with Appendix U of Missouri's Water Pollution Control Permit Manual. The Clean Water Commission has directed the Department to proceed with amending 10 CSR 20-7.015 to reduce the sampling frequency required for *E. coli* to a lesser frequency, still protective of water quality standards, for smaller facilities, including those with discharges of 100,000 gallons per day or less.

Sampling Type Justification

As per 10 CSR 20-7.015, BOD₅, TSS, and WET test samples collected for mechanical plants shall be a 24 hour composite sample. Grab samples, however, must be collected for pH, Ammonia as N, *E. coli*, TRC, Oil & Grease, Total Phosphorus, Total Nitrogen, and Dissolved Oxygen. This is due to the holding time restriction for *E. coli*, the volatility of Ammonia and TRC, and the fact that pH and DO cannot be preserved and must be sampled in the field. As Ammonia, Oil & Grease, and Total Phosphorus samples must be immediately preserved with acid, therefore these samples are to be collected as a grab.

Part VIII – Finding of Affordability

Pursuant to Section 644.145, RSMo., the Department is required to determine whether a permit or decision is affordable and makes a finding of affordability for certain permitting and enforcement decisions. This requirement applies to discharges from combined or separate sanitary sewer systems or publically-owned treatment works.

Applicable; The Department is required to determine findings of affordability because the permit applies to a **combined or separate sanitary sewer system for a publically-owned treatment works**.

Finding of affordability - The department has made a reasonable search for empirical data indicating the permit is affordable. The search consisted of a review of department records that might contain economic data on the community, a review of information provided by the applicant as part of the application, and public comments received in response to public notices of this draft permit. If the empirical cost data was used by the permit writer, this data may consist of median household income, any other ongoing projects that the Department has knowledge, and other demographic financial information that the community provided as contemplated by Section 644.145.3. See **Appendix 4 – Affordability Analysis**

Part IX – Administrative Requirements

On the basis of preliminary staff review and the application of applicable standards and regulations, the Department, as administrative agent for the Missouri Clean Water Commission, proposes to issue a permit(s) subject to certain effluent limitations, schedules, and special conditions contained herein and within the operating permit. The proposed determinations are tentative pending public comment.

PERMIT SYNCHRONIZATION:

The Department of Natural Resources is currently undergoing a synchronization process for operating permits. Permits are normally issued on a five-year term, but to achieve synchronization many permits will need to be issued for less than the full five years allowed by regulation. The intent is that all permits within a watershed will move through the Watershed Based Management (WBM) cycle together will all expire in the same fiscal year. This will allow further streamlining by placing multiple permits within a smaller geographic area on public notice simultaneously, thereby reducing repeated administrative efforts. This will also allow the Department to explore a watershed based permitting effort at some point in the future. Renewal applications must continue to be submitted within 180 days of expiration, however, in instances where effluent data from the previous renewal is less than 4 years old, that data may be re-submitted to meet the requirements of the renewal application. If the permit provides a schedule of compliance for meeting new water quality based effluent limits beyond the expiration date of the permit, the time remaining in the schedule of compliance will be allotted in the renewed permit.

PUBLIC NOTICE:

The Department shall give public notice that a draft permit has been prepared and its issuance is pending. Additionally, public notice will be issued if a public hearing is to be held because of a significant degree of interest in and water quality concerns related to a draft permit. No public notice is required when a request for a permit modification or termination is denied; however, the requester and permittee must be notified of the denial in writing.

The Department must issue public notice of a pending operating permit or of a new or reissued statewide general permit. The public comment period is the length of time not less than 30 days following the date of the public notice which interested persons may submit written comments about the proposed permit.

For persons wanting to submit comments regarding this proposed operating permit, then please refer to the Public Notice page located at the front of this draft operating permit. The Public Notice page gives direction on how and where to submit appropriate comments.

- The Public Notice period for this operating permit was from March 1, 2013 to April 1, 2013. No responses received.

DATE OF FACT SHEET: MAY 12, 2014

COMPLETED BY:

EMILY CARPENTER, PLAN REVIEWER
MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM
FINANCIAL ASSISTANCE CENTER
573-751-6569
emily.carpenter@dnr.mo.gov

Appendices

APPENDIX 1 - CLASSIFICATION WORKSHEET:

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
Maximum Population Equivalent (P.E.) served (Max 10 pts.)	1 pt./10,000 PE or major fraction thereof.	
Maximum: 10 pt Design Flow (avg. day) or peak month; use greater (Max 10 pts.)	1 pt. / MGD or major fraction thereof.	
EFFLUENT DISCHARGE RECEIVING WATER SENSITIVITY:		
Missouri or Mississippi River	0	
All other stream discharges except to losing streams and stream reaches supporting whole body contact	1	
Discharge to lake or reservoir outside of designated whole body contact recreational area	2	
Discharge to losing stream, or stream, lake or reservoir area supporting whole body contact recreation	3	3
PRELIMINARY TREATMENT - Headworks		
Screening and/or comminution	3	3
Grit removal	3	
Plant pumping of main flow (lift station at the headworks)	3	
PRIMARY TREATMENT		
Primary clarifiers	5	
Combined sedimentation/digestion	5	
Chemical addition (except chlorine, enzymes)	4	
REQUIRED LABORATORY CONTROL – performed by plant personnel (highest level only)		
Push – button or visual methods for simple test such as pH, Settleable solids	3	
Additional procedures such as DO, COD, BOD, titrations, solids, volatile content	5	5
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.	7	
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph	10	
ALTERNATIVE FATE OF EFFLUENT		
Direct reuse or recycle of effluent	6	
Land Disposal – low rate	3	
High rate	5	
Overland flow	4	
Total from page ONE (1)	----	11

APPENDIX 1 - CLASSIFICATION WORKSHEET (CONTINUED):

ITEM	POINTS POSSIBLE	POINTS ASSIGNED
VARIATION IN RAW WASTE (highest level only) (DMR exceedances and Design Flow exceedances)		
Variation do not exceed those normally or typically expected	0	
Recurring deviations or excessive variations of 100 to 200 % in strength and/or flow	2	
Recurring deviations or excessive variations of more than 200 % in strength and/or flow	4	
Raw wastes subject to toxic waste discharge	6	
SECONDARY TREATMENT		
Trickling filter and other fixed film media with secondary clarifiers	10	
Activated sludge with secondary clarifiers (including extended aeration and oxidation ditches)	15	15
Stabilization ponds without aeration	5	
Aerated lagoon	8	
Advanced Waste Treatment Polishing Pond	2	
Chemical/physical – without secondary	15	
Chemical/physical – following secondary	10	10
Biological or chemical/biological	12	
Carbon regeneration	4	
DISINFECTION		
Chlorination or comparable	5	
Dechlorination	2	
On-site generation of disinfectant (except UV light)	5	
UV light	4	4
SOLIDS HANDLING - SLUDGE		
Solids Handling Thickening	5	5
Anaerobic digestion	10	
Aerobic digestion	6	
Evaporative sludge drying	2	
Mechanical dewatering	8	
Solids reduction (incineration, wet oxidation)	12	
Land application	6	
Total from page TWO (2)	----	34
Total from page ONE (1)	---	11
Grand Total	---	45

- A: 71 points and greater
- B: 51 points – 70 points
- C: 26 points – 50 points
- D: 0 points – 25 points

APPENDIX 2 – SUNRISE BEACH LOCATION MAP:



1" = 2000'
 USGS MAP

11/29/2012
 Designed by: AutoCAD Civil 3D
 Checked by: JL Serviced by: JL
 Project #: 100007 Drawn by: JL
 Sheet Size: 8.5x11
 Date: 11/29/2012

PHASE 1 SANITARY SEWER IMPROVEMENTS
 SUNRISE BEACH, MISSOURI



SS&E
 Engineering

Schwartz & Summers
 Engineering

Southwest Missouri Office - (573) 686-0606
 Lake of the Ozarks Office - (573) 365-2000
 Branson Office - (417) 337-8820
 New Orleans, LA Office - (504) 467-6009
www.schultzandsummers.com

Civil Engineering - Land Surveying - Materials Testing

APPENDIX 3 – WATER QUALITY AND ANTIDegradation REVIEW:

Water Quality and Antidegradation Review

*For the Protection of Water Quality
and Determination of Effluent Limits for Discharge to
Unnamed Tributary to Lake of the Ozarks*

by

***Village of Sunrise Beach
Wastewater Treatment Facility***



July 2012

Table of Contents

1. Facility Information	18
2. Water Quality Information.....	18
2.1. Water Quality History:.....	18
3. Receiving Waterbody Information	18
4. General Comments.....	19
5. Antidegradation Review Information	19
5.1. Tier Determination.....	19
5.2. Existing Water Quality	20
5.3. Demonstration of Necessity and Social and Economic Importance	20
5.3.1. Regionalization Alternative.....	21
5.3.2. Social and Economic Importance Evaluation	21
6. General Assumptions of the Water Quality and Antidegradation Review	22
7. Mixing Considerations.....	22
8. Permit Limits and Monitoring Information	23
9. Receiving Water Monitoring Requirements	23
10. Derivation and Discussion of Limits	23
10.1. Outfall #001 – Main Facility Outfall	24
10.2. Limit Derivation.....	24
11. Antidegradation Review Preliminary Determination	27
Table 1. Pollutants of Concern and Tier Determination	20
Table 2: Comparison Degrading Alternatives for Discharge	21
Table 3: Effluent Limits.....	23
Appendix A: Map of Discharge Location.....	28
Appendix B: Natural Heritage Review	29
Appendix C: Antidegradation Review Summary Attachments	30

1. Facility Information

FACILITY NAME: Village of Sunrise Beach WWTF NPDES #: Mo-0134996

FACILITY TYPE/DESCRIPTION: As a result of the submitted alternative analysis, the applicant's preferred alternative is the Delta Environmental ECOPOD with ultraviolet disinfection. The design flow will be 0.05 MGD. The Water Protection Program staff recommends the extended aeration treatment alternative with ultraviolet disinfection.

COUNTY: Camden UTM COORDINATES: X=518220 / Y= 4220044
 12- DIGIT HUC: 102901090207 LEGAL DESCRIPTION: NW ¼, NE ¼, Section 16, T 39N, R17W
 EDU*: Ozark/Osage COREGION: Ozark/Highlands

* - Ecological Drainage Unit

2. Water Quality Information

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(2)] and federal antidegradation policy at Title 40 Code of Federal Regulation (CFR) Section 131.12 (a), the Missouri Department of Natural Resources (MDNR) developed a statewide antidegradation policy and corresponding procedures to implement the policy. A proposed discharge to a water body will be required to undergo a level of Antidegradation Review which documents that the use of a water body's available assimilative capacity is justified. Effective August 30, 2008, a facility is required to use *Missouri's Antidegradation Rule and Implementation Procedure (AIP)* for new and expanded wastewater discharges.

2.1. Water Quality History:

The operating permit was issued in 2008. Since then, the facility has had multiple exceedances of effluent limits. The Southwest Regional Office sent a letter of warning in June 2009, and in the October 2009, it was issued a Notice of Violation. Currently, this permit is an enforcement case that has been referred to the AGOs office. Since May 2010 inspection, the facility has been cited for violations of effluent limitations and construction without a permit. The facility was inspected in August 2010 and August 2011 with no change in effluent quality. The Lake of the Ozark, Osage Arm is listed on the 303(d) listing of impaired water for total nitrogen (TN).

Outfall	Design Flow (cfs)	Treatment Level	Receiving Waterbody	Distance to Classified Segment (mi)
001	0.078	Secondary	Unnamed Tributary to Lake of the Ozarks	0.1

3. Receiving Waterbody Information

Waterbody Name	Class	WBID	Low-Flow Values (cfs)			Designated Uses**
			1Q10	7Q10	30Q10	
Unnamed Tributary to Lake of the Ozarks	U	NA	NA	NA	NA	General Criteria
Lake of the Ozarks	L2	07205	--	--	--	AQL, LWW, SCR, WBC(A)

** Irrigation (IRR), Livestock & Wildlife Watering (LWW), Protection of Warm Water Aquatic Life and Human Health-Fish Consumption (AQL), Cool Water Fishery(CLF), Cold Water Fishery (CDF), Whole Body Contact Recreation (WBC), Secondary Contact Recreation (SCR), Drinking Water Supply (DWS), Industrial (IND)

RECEIVING WATER BODY SEGMENT #1: Unnamed Trib to Lake Ozarks to Cove of Lake of the Ozarks

Upper end segment* UTM coordinates: X=518220 / Y=4220044 (Outfall)

Lower end segment* UTM coordinates: X=518114 / Y=4219414 (Cove confluence w/ Lake of the Ozarks)

*Segment is the portion of the stream where discharge occurs. Segment is used to track changes in assimilative capacity and is bound at a minimum by existing sources and confluences with other waters.

4. General Comments

Lake Ozark Environmental, LLC prepared, on behalf of Village of Sunrise Beach and Shultz and Summers Engineering, Inc., the *Antidegradation Review Report for Proposed Waste Water Treatment Facility Expansion, Average Daily Design Flow 50,000 gallons per day, Camden County, Missouri* dated June 4, 2012. The Village of Sunrise Beach currently does not have a municipal sewage treatment plant. Several small NPDES permitted facilities serve part of the area, along with several Camden County regulated facilities, subsurface septic systems. Homes and businesses within the incorporated limits of Sunrise Beach rely these small permitted treatment facilities and upon failing onsite sewage disposal that are discharging to the Lake of the Ozark watershed on a regular basis. This review is part of a Phase 1 Sewer Improvement Project. With the writing of this review, the owner of the existing facility, Buccaneer Bay WWTF, expressed a willingness to donate the relatively new 9,000 gpd waste water treatment facility. The Village of Sunrise Beach does not own the facility. The expanded flow of the existing Buccaneer Bay WWTF will serve 39 homes and 37 commercial businesses for a total of 76 connections. For a population equivalent of 144 persons, the total design flow with the addition of a new commercial center will be approximately 40,000 gpd with the projected design flow of 50,000 gpd.

The village has bonds voted and is seeking additional funding through the Water Protection Program's Financial Assistance Center (FAC) for the acquisition and expansion of the facility as Phase 1. According to the *Addendum 2 to Preliminary Engineering Report for Village of Sunrise Beach Camden County, Missouri*, other phases are proposed that will increase the capacity of the treatment facility. This review treats only Phase 1 of the project.

A Geohydrological Evaluation was submitted with the request and the receiving stream is gaining for discharge purposes (Appendix A: Map). In addition, based on the geologic and hydrologic characteristics of the site, the Division of Geology and Land Survey gave the site a severe overall geologic limitations rating and moderate lagoon collapse potential due to the permeability of the bedrock.

Applicant elected to assume that all pollutants of concern (POC) are significantly degrading the receiving stream in the absence of existing water quality. An alternative analysis was conducted to fulfill the requirements of the AIP. Dissolved oxygen modeling analysis was not submitted for review. Information that was provided by the applicant in the submitted report and summary forms in Appendix C was used to develop this review document. A Missouri Department of Conservation Natural Heritage Review was obtained by the applicant (see Appendix B); and no records of endangered species were found that may be impacted by the facility and its discharge.

5. Antidegradation Review Information

The following is a review of the *Antidegradation Review Report for Proposed Waste Water Treatment Facility Expansion, Average Daily Design Flow 50,000 gallons per day, Camden County, Missouri* dated June 4, 2012.

5.1. TIER DETERMINATION

Below is a list of pollutants of concern reasonably expected to be in the discharge (see Appendix C: Tier Determination and Effluent Limit Summary). Pollutants of concern are defined as those pollutants "proposed for discharge that affects beneficial use(s) in waters of the state. POCs include pollutants that create conditions unfavorable to beneficial uses in the water body receiving the discharge or proposed to receive the discharge." (AIP, Page 7). Tier 2 was assumed for all POCs (see Appendix C).

Table 1. Pollutants of Concern and Tier Determination

POLLUTANTS OF CONCERN	TIER*	DEGRADATION	COMMENT
BOD ₅ /DO	2	Significant	
Total Suspended Solids (TSS)	**	Significant	Permit limits applied
Ammonia	2	Significant	
pH	***	Significant	Permit limits applied
Escherichia coli (E. coli)	2	Significant	Permit limits applied
Total Residual Chlorine (TRC)	2	Significant	Method detection limit
Total Phosphorus	1	No Degradation	Nutrient Criteria for lakes
Total Nitrogen	1	No degradation	Nutrient Criteria for lakes

* Tier assumed. Tier determination not possible: ** No in-stream standards for these parameters. *** Standards for these parameters are ranges

The following Antidegradation Review Summary attachments in Appendix C were used by the applicant:

- Tier Determination and Effluent Summary
- For pollutants of concern, the attachments are:
- Attachment A, Tier 2 with significant degradation.

5.2. EXISTING WATER QUALITY

No existing water quality data was submitted. All POCs were considered to be Tier 2 and significantly degraded in the absence of existing water quality.

5.3. DEMONSTRATION OF NECESSITY AND SOCIAL AND ECONOMIC IMPORTANCE

Missouri’s antidegradation implementation procedures specify that if the proposed activity results in significant degradation then a demonstration of necessity (i.e., alternatives analysis) and a determination of social and economic importance are required. Six alternatives from non-degrading to less degrading to degrading alternatives were evaluated. Among the non-degrading alternatives were land application, subsurface irrigation, and connection to a regional sewer. Non-degrading land application would require a total land area of 37.5 acres. That acreage includes 2.6 acres of lagoon and the remainder land application area. According to the antidegradation report, the availability of land and land cost makes this alternative impracticable. Non-degrading subsurface “drip” irrigation was eliminated as impracticable due to availability and cost of 13 acres of land that is necessary for subsurface irrigation. Finally, connection to the City of Laurie facility was considered. The facility has sufficient capacity to take the additional flow from the Village of Sunrise Beach. The cost of the collection system is about the same as a cost of a new treatment facility. Easement acquisition and connection costs would make this alternative not practicable.

Only those alternatives that were considered practicable were included in the economically efficiency analysis. Three alternatives were evaluated in the economic efficiency analysis, the BIOPOD (Delta Environment ECOPOD), which is the base case and also the current facility on the site, a mechanical package plant as extended air without filtration, and a recirculating sand filter. In a September 2009 submittal, Midwest Engineering Company proposed, on behalf of Buccaneer Bay (current owner of MO-0134996), expanding the BIOPOD system from 9,000 gpd to 45,000 gpd. The BIOPOD was designated a non-standard technology when the permit was issued in 2008. The Southwest Regional Office (SWRO) in December 2009 determined that the BIOPOD was not achieving treatment and was not meeting water quality standards. Considering that that for a number of years the facility was not able to meet the limitations, SWRO engineers determined the BIOPOD could not be used in the proposed expansion. SWRO asked Buccaneer Bay to evaluate other technologies to replace the BIOPOD for the proposed expansion.

This analysis was unable to definitively show that the base case treatment alternative provided the best return on environmental benefits at a lower cost of treatment (see Appendix C, Attachment A). The ECOPOD (previously the BIOPOD) facility cannot consistently meet water quality standards for ammonia, and the treatment capacity values in Table 2 are above water quality standards.

The department has permitted 24 BIOPOD facilities statewide, 22 in the Southwest Region and two in the Kansas City Region. Many of these facilities are new and do not have adequate data (data collected at 75% of the design flow) to evaluate their performance. One facility, Barnett Manor WWTF, has three years of “adequate data” and is not consistently meeting the water quality standards for ammonia. The department has worked with the current owner to correct issues with the Buccaneer Bay WWTF; however, the facility has yet to achieve performance that reliably meets water quality standards.

The Antidegradation submittal provided by the Village of Sunrise Beach presented the BIOPOD as the preferred alternative. No affordability analysis was provided which would exclude the extended aeration mechanical plant or the sand filter. The department prefers the extended aeration mechanical plant as it provides marginally better treatment at a moderate increase in present worth costs. The extended aeration mechanical plant is 110% of the base case treatment which is within the 120% rule of thumb. We believe that the BIOPOD as an unproven technology, as defined in the in the *MDNR New Technology Definitions and Requirements* factsheet <http://dnr.mo.gov/pubs/pub2453.pdf>, needs additional maintenance in order to effectively run the facility; therefore the BIOPOD maintenance costs may be underestimated. Finally, it would be prudent for the applicant to consider potential future obligations for nutrient removal at this facility. Removal of nitrites and nitrates will require a separate treatment with anoxic conditions and nitrate recycle.

Table 2: Comparison Degrading Alternatives for Discharge

PARAMETER	BIOPOD	EXTENDED AERATION WITHOUT FILTER	SAND FILTER
BOD ₅ (MG/L)	≤15**	≤10	≤15
TSS (MG/L)	≤15**	≤15	≤10
DO (MG/L)	≥7.7**	≥6	≥6
AMMONIA (MG/L) SUMMER	≤2.5***	≤5****	≤5****
AMMONIA (MG/L) WINTER	***	NA	NA
E. COLI (COLONIES/100 ML)	≤126	≤126	≤126
OIL & GREASE (MG/L)	≤10	≤10	≤10
PRACTICABLE	YES	YES	YES
ECONOMICALLY EFFICIENT	YES	YES	YES
PRESENT WORTH COST	\$942,050	\$1,039,000	\$1,108,550
COST PER GALLON	\$18.84	\$20.78	\$22.17
RATIO	1.00	1.10	1.18

* Life cycle cost at 20 year design life and 5% interest

** Delta Environmental, Pontair Water, *Performance Evaluation* document. Provided by LO Environmental, LLC.

*** Delta Environmental, Pontair Water, *Performance Evaluation* document. Unofficial Lab Reports of Buccaneer Bay provided by LO Environmental, LLC. Summer – highest value sampled. Winter – highest value sampled was 0.8 mg/L (questionable results for winter and modified by the WPP staff reviewer).

**** The provided ammonia capacity is assumed by the reviewer to be summer values.

5.3.1. REGIONALIZATION ALTERNATIVE

Within Section II B 1. of the AIP, discussion of the potential for discharge to a regional waste water collection system is mentioned. The applicant provided discussion of this alternative. The alternative analysis mentions City of Laurie as the regional authority. This authority is not operative at this time so a waiver required under 10 CSR 20-6.010(3) (B) 1 Continuing Authorities can not be obtained.

NEEDS A WAIVER TO PREVENT CONFLICT WITH AREA WIDE MANAGEMENT PLAN APPROVED UNDER SECTION 208 OF THE CLEAN WATER ACT AND/OR UNDER 10 CSR 20-6.010(3) (B) 1 OR 2 CONTINUING AUTHORITIES? (Y OR N) N

5.3.2. SOCIAL AND ECONOMIC IMPORTANCE EVALUATION

The applicant first identified the community that will be affected by the proposed degradation of water quality. The affected community is likely quite a large group of people that use the lake each summer on the weekend. Communities around the lake swell from a few hundred to several thousand each weekend. Several cities such as Gravois Mills, Laurie, Lake Ozark, Osage Beach and Camdenton have sewer and water utilities; however, the remainder of the small towns and rural residents around lake are served by small discharging facilities or septic systems. In a meeting with the Lake of the Ozark Watershed Alliance and the consulting engineers, the economic importance of this discharge was emphasized. Growth of the Village of Sunrise Beach depends on the construction of a centralized waste water treatment facility. The antidegradation review report identified a number of relevant factors related to the development of a centralized waste water treatment facility, including commercial development, needed employment growth, increased land value and tax base, and environmental factors associated with failing septic systems and present level of E. coli in the lake. Within a Social and Economic Importance of the Proposed Project section of the submitted antidegradation review report, these factors were discussed. Appendix

C, Attachment A: Tier 2 with Significant Degradation form contains a summary of this information.

6. General Assumptions of the Water Quality and Antidegradation Review

1. A Water Quality and Antidegradation Review (WQAR) assumes that [10 CSR 20-6.010(3) Continuing Authorities and 10 CSR 20-6.010(4) (D), consideration for no discharge] has been or will be addressed in a Missouri State Operating Permit or Construction Permit Application.
2. A WQAR does not indicate approval or disapproval of alternative analysis as per [10 CSR 20-7.015(4) Losing Streams], and/or any section of the effluent regulations.
3. Changes to Federal and State Regulations made after the drafting of this WQAR may alter Water Quality Based Effluent Limits (WQBEL).
4. Effluent limitations derived from Federal or Missouri State Regulations (FSR) may be WQBEL or Effluent Limit Guidelines (ELG).
5. WQBEL supersede ELG only when they are more stringent. Mass limits derived from technology based limits are still appropriate.
6. A WQAR does not allow discharges to waters of the state, and shall not be construed as a National Pollution Discharge Elimination System or Missouri State Operating Permit to discharge or a permit to construct, modify, or upgrade.
7. Limitations and other requirements in a WQAR may change as Water Quality Standards, Methodology, and Implementation procedures change.
8. Nothing in this WQAR removes any obligations to comply with county or other local ordinances or restrictions.
9. If the proposed treatment technology is not covered in 10 CSR 20-8 Design Guides, the treatment process may be considered an unproven technology. As an unproven technology, the permittee will need to work with the review engineer to ensure equipment is sized properly. The operating permit may contain additional requirements to evaluate the effectiveness of the technology once the facility is in operation. This Antidegradation Review is based on the information provided by the facility and is not a comprehensive review of the proposed treatment technology. If the review engineer determines the proposed technology will not consistently meet proposed effluent limits, the permittee will be required to revise their Antidegradation Report.

7. Mixing Considerations

Mixing Zone (MZ): Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(a)].

Zone of Initial Dilution (ZID): Not Allowed [10 CSR 20-7.031(4)(A)4.B.(I)(b)]

8. Permit Limits and Monitoring Information

WASTELOAD ALLOCATION
STUDY CONDUCTED (Y OR N): N

USE ATTAINABILITY
ANALYSIS CONDUCTED (Y OR N): N

WHOLE BODY CONTACT
USE RETAINED (Y OR N): Y

OUTFALL #001

WET TEST (Y OR N): Y FREQUENCY: ONCE/PERMIT CYCLE AEC: 100% METHOD: MULTIPLE

TABLE 3: EFFLUENT LIMITS

PARAMETER	UNITS	DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	BASIS FOR LIMIT (NOTE 2)	MONITORING FREQUENCY
FLOW	GPD	*		*	FSR	ONCE/MONTH
BOD ₅ ***	MG/L		30	20	FSR	ONCE/MONTH
TSS***	MG/L		30	20	FSR	ONCE/MONTH
PH	SU	6.5 – 9.0		6.5 – 9.0	FSR	ONCE/MONTH
OIL AND GREASE	MG/L	15		10	FSR	ONCE/MONTH
AMMONIA AS N (APR 1 – SEPT 30)	MG/L	3.7		1.4	WQBEL	ONCE/MONTH
AMMONIA AS N (OCT 1 – MAR 31)	MG/L	7.5		2.9	WQBEL	ONCE/MONTH
TOTAL NITROGEN	mg/L	*		*	N/A	ONCE/MONTH
TOTAL PHOSPHORUS	MG/L	*		*	N/A	ONCE/MONTH
DISSOLVED OXYGEN	MG/L	5.0 MINIMUM		5.0 MINIMUM	FSR	ONCE/MONTH
ESCHERICHIA COLIFORM (E. COLI)	NOTE 1		630**	126**	FSR	ONCE/MONTH

* - Monitoring requirements only.

** - The Monthly Average for indicator bacteria shall be reported as a Geometric Mean.

*** This facility is required to meet a removal efficiency of 85% or more for BOD₅ and TSS. Influent BOD₅ and TSS data should be reported to ensure removal efficiency requirements are met.

NOTE 1– COLONIES/100 ML Please see the E. coli discussion in the Derivation & Discussion of Limits section of this WQRS below.

NOTE 2– WATER QUALITY-BASED EFFLUENT LIMITATION --WQBEL; OR MINIMALLY DEGRADING EFFLUENT LIMIT--MDEL; OR TECHNOLOGY-BASED EFFLUENT LIMIT--TBEL; OR NO DEGRADATION LIMIT--NDL; OR FSR --FEDERAL/STATE REGULATION; OR PAL—PREFERRED ALTERNATIVE LIMIT; OR N/A--NOT APPLICABLE. ALSO, PLEASE SEE THE **GENERAL ASSUMPTIONS OF THE WQAR #4 & #5.**

9. Receiving Water Monitoring Requirements

No receiving water monitoring requirements recommended at this time.

10. Derivation and Discussion of Limits

Wasteload allocations and limits were calculated using two methods:

1) Water quality-based – Using water quality criteria or water quality model results and the dilution equation below:

$$C = \frac{(C_s \times Q_s) + (C_e \times Q_e)}{(Q_e + Q_s)} \quad (\text{EPA/505/2-90-001, Section 4.5.5})$$

Where C = downstream concentration

C_s = upstream concentration

Q_s = upstream flow

C_e = effluent concentration

Q_e = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality-based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

2) Alternative Analysis-based – Using the preferred alternative's treatment capacity for conventional pollutants such as BOD₅ and TSS that are provided by the consultant as the WLA, the significantly-degrading effluent average monthly and average weekly limits are determined by applying the WLA as the average monthly (AML) and multiplying the AML by 1.5 to derive the average weekly limit (AWL). For toxic and nonconventional pollutant such as ammonia, the treatment capacity is applied as the significantly-degrading effluent monthly average (AML). A maximum daily can be derived by dividing the AML by 1.19 to determine the long-term average (LTA). The LTA is then multiplied by 3.11 to obtain the maximum daily limitation. This is an accepted procedure that is defined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

Note: Significantly-degrading effluent limits have been based on the authority included in Section III. Permit Consideration of the AIP. Also under 40 CFR 133.105, permitting authorities shall require more stringent limitations than equivalent to secondary treatment limitations for 1) existing facilities if the permitting authority determines that the 30-day average and 7-day average BOD₅ and SS effluent values that could be achievable through proper operation and maintenance of the treatment works, and 2) new facilities if the permitting authority determines that the 30-day average and 7-day average BOD₅ and SS effluent values that could be achievable through proper operation and maintenance of the treatment works, considering the design capability of the treatment process.

10.1. OUTFALL #001 – MAIN FACILITY OUTFALL

10.2. LIMIT DERIVATION

- **Flow.** In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the department, which may require the submittal of an operating permit modification.
- **Biochemical Oxygen Demand (BOD₅).** While the preferred alternative has a treatment capacity as specified in Delta Environmental product description and in Table 2, we recommend BOD₅ limits of 20 mg/L as monthly average and 30 mg/L as average weekly limits [10 CSR 20-7.015(3)(A)1A.]. This is due to the past performance of the current facility and the recommendation of Staff to construct the extended aeration facility without filtration. For discharges to streams ½ mile or less from a lake, numeric effluent limits for BOD₅ and TSS will be applied as specified in 10 CSR 20-7.015(3). Influent monitoring may be required for this facility in its Missouri State Operating Permit.
- **Total Suspended Solids (TSS).** While the preferred alternative has a treatment capacity as specified in Delta Environmental product description and in Table 2, we recommend TSS limits of 20 mg/L as monthly average and 30 mg/L as average weekly limits [10 CSR 20-7.015(3)(A)1A.]. This is due to the past performance of the current facility and the recommendation of Staff to construct the extended aeration facility without filtration. For discharges to streams ½ mile or less from a lake, numeric effluent limits for BOD₅ and TSS will be applied as specified in 10 CSR 20-7.015(3). Influent monitoring may be required for this facility in its Missouri State Operating Permit.
- **pH.** pH shall be maintained in the range from 6.5 to nine (6.5– 9.0) standard units [10 CSR 20-7.015 (3)(A)1.B.].
- **Dissolved Oxygen.** Effluent dissolved oxygen of 5.0 mg/L minimum was proposed in the Antidegradation Report. Staff assigned 5.0 mg/L for the protection of aquatic life.

Summer

$$C_e = ((Q_e + Q_s) * C) - (Q_s * C_s) / Q_e$$

Chronic WLA: $C_e = ((0.078 + 0.0)1.5 - (0.0 * 0.01)) / 0.078$
 $C_e = 1.5 \text{ mg/L}$

Acute WLA: $C_e = ((0.078 + 0.0)12.1 - (0.0 * 0.01)) / 0.078$
 $C_e = 12.1 \text{ mg/L}$

$LTA_c = 1.5 \text{ mg/L (0.780)} = \mathbf{1.2 \text{ mg/L}}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L (0.321)} = 3.88 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

$MDL = 1.2 \text{ mg/L (3.11)} = 3.7 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
 $AML = 1.2 \text{ mg/L (1.19)} = 1.4 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

Winter

Chronic WLA: $C_e = ((0.078 + 0.0)3.1 - (0.0 * 0.01)) / 0.078$
 $C_e = 3.1 \text{ mg/L}$

Acute WLA: $C_e = ((0.078 + 0.0)12.1 - (0.0025 * 0.01)) / 0.078$
 $C_e = 12.1 \text{ mg/L}$

$LTA_c = 3.1 \text{ mg/L (0.780)} = \mathbf{2.4 \text{ mg/L}}$ [CV = 0.6, 99th Percentile, 30 day avg.]
 $LTA_a = 12.1 \text{ mg/L (0.321)} = 3.9 \text{ mg/L}$ [CV = 0.6, 99th Percentile]

$MDL = 2.4 \text{ mg/L (3.11)} = 7.5 \text{ mg/L}$ [CV = 0.6, 99th Percentile]
 $AML = 2.4 \text{ mg/L (1.19)} = 2.9 \text{ mg/L}$ [CV = 0.6, 95th Percentile, n = 30]

Season	Maximum Daily Limit (mg/l)	Average Monthly Limit (mg/l)
Summer	3.7	1.4
Winter	7.5	2.9

- **E. coli.** Effluent limitations for WBC(A) are 126 colonies per 100 ml monthly average and 630 colonies per 100 ml weekly average [10 CSR 20-7.015 (8)(A)4.] and [10 CSR 20-7.031(4)(C), Table A]. Per the Clean Water Commission Directive in January 2011, the *E. Coli* sampling/monitoring frequency shall be set to match the monitoring frequency of other parameters in the permit during the recreational season (April 1 – October 31), with compliance to be determined by calculating the geometric mean of all samples collected during the reporting period (samples collected during the calendar week for the weekly average, and samples collected during the calendar month for the monthly average). The weekly average requirement is consistent with EPA federal regulation 40 CFR 122.45(d). Further, the limit may change depending on the outcome of future state effluent regulation revision. Please see **GENERAL ASSUMPTIONS OF THE WQAR #7**.
- **Oil & Grease.** Conventional pollutant, [10 CSR 20-7.031, Table A]. Effluent limitation for protection of aquatic life; 10 mg/L monthly average, 15 mg/L daily maximum.
- **Total Nitrogen.** Lake of the Ozark is 303 (d) listed for total nitrogen. Total Nitrogen is a Tier 1 pollutant of concern. No water quality standards are available for total nitrogen. Monitoring only will be required to gather information about facilities and to determine the impacts if any to the lake for this parameter. The department does not have an approved implementation plan for nutrients.

- **Total Phosphorus.** Lake of the Ozark is 303 (d) listed for total phosphorus. Total phosphorus is a Tier 1 pollutant of concern. 10 CSR 20-7.031, Table N contains water quality standards for total phosphorus. Monitoring only will be required to gather information about facilities and to determine the impacts if any to the lake for this parameter. The department does not have an approved implementation plan for nutrients.

11. ANTIDegradation REVIEW PRELIMINARY DETERMINATION

The proposed expanded facility discharge, Village of Sunrise Beach WWTF, to 0.05 MGD will result in significant degradation of the segment identified in Lake of the Ozarks. The Delta Environmental ECOPOD was determined to be the base case technology (lowest cost alternative that meets technology limitations; however, this system may not meet ammonia water quality standards). The cost effectiveness of the other technologies was evaluated, and Delta Environmental ECOPOD was found to be cost effective; therefore, it was determined to be the applicant's preferred alternative.


However, since the ECOPOD is an unproven technology, the Department cannot approve the use of the ECOPOD unless adequate data can be provided illustrating it can meet the effluent limits established in the Water Quality and Antidegradation Review. The data will need to be provided as described in the Fact Sheet "New Technology Definitions and Requirements" on the Department's website at <http://dnr.mo.gov/pubs/pub2453.pdf>. The data will need to be from facilities that are located in a climate similar to that of Sunrise Beach.

Therefore, for the reasons described in Section 5.3 above, the department prefers the extended aeration mechanical plant as it provides marginally better treatment at a moderate increase in present worth costs and is a proven technology.

Per the requirements of the AIP, the effluent limits in this review were developed to be protective of beneficial uses and to attain the highest statutory and regulatory requirements. MDNR has determined that the submitted review is sufficient and meets the requirements of the AIP.

Reviewer: Todd Blanc
Date: July 25, 2012
Unit Chief: John Rustige, P.E.

Appendix A: Map of Discharge Location



Appendix B: Natural Heritage Review

	Missouri Department of Conservation <h1 style="margin: 0;">Heritage Review Report</h1> <p style="margin: 0;">May 15, 2012 -- Page 1 of 2</p>		Resource Science Division P. O. Box 180 Jefferson City, MO 65102 Prepared by: Emily Clancy Emily.Clancy@mdc.mo.gov (573) 522-4115 ext. 3182
	LO Environmental Attn: Shelly Hall, PE PO Box 2325 Lake Ozark, MO 65049	Project type: Wastewater Location/Scope: Section 9 of T39N R17W County: Camden Query reference: WWTF- #MO-0134996 Query received: May 14, 2012	
<p><i>This NATURAL HERITAGE REVIEW is not a site clearance letter. Rather, it identifies public lands and sensitive resources known to have been located close to and/or potentially affected by the proposed project. On-site verification is the responsibility of the project. Heritage records were identified at some date and location. This report considers records near but not necessarily at the project site. Animals move and, over time, so do plant communities. To say "there is a record" does not mean the species/habitat is still there. To say that "there is no record" does not mean a protected species will not be encountered. These records only provide one reference and other information (e.g. wetland or soils maps, on-site inspections or surveys) should be considered. Look for additional information about the biological and habitat needs of records listed in order to avoid or minimize impacts. More information may be found at http://mdc.mo.gov/discover-nature/places-qa/natural-areas and mdc4.mdc.mo.gov/applications/mofwis/mofwis_search1.aspx. Contact information for the department's Natural History Biologist is online at http://mdc.mo.gov/contact-us.</i></p>			
<p>Level 3 (federal-listed) and Level 2 (state listed) issues: Records of listed species or critical habitats:</p> <p>Heritage records identify <u>no</u> wildlife preserves, <u>no</u> designated wilderness areas or critical habitats, <u>no</u> federal or state endangered-list species records within one mile of the site, or in the public land survey section listed above or sections adjacent.</p> <p>The project should be managed to minimize erosion and sedimentation/runoff to nearby streams and lakes, including adherence to any "Clean Water Permit" conditions. Pollutants, including sediment, can have significant impacts far downstream. Use silt fences and/or vegetative filter strips to buffer streams and drainages, and monitor those after rain events and until a well-rooted ground cover is reestablished. Revegetate areas in which the natural cover is disturbed to minimize erosion using native plant species compatible with the local landscape and wildlife needs.</p> <p><small>FEDERAL LIST species/habitats are protected under the Federal Endangered Species Act. Consult with U.S. Fish and Wildlife Service, 101 Park Deville Drive Suite A, Columbia, Missouri 65203-0007; 573-234-2132</small></p>			
<p>General recommendations related to this project or site, or based on information about the historic range of species (unrelated to any specific heritage records):</p> <ul style="list-style-type: none"> ➤ Indiana bats (<i>Myotis sodalis</i>, federally and state listed "endangered") may occur in this area. These mammals hibernate during winter months in caves, in Missouri primarily in the southern half of the state. They are found in summer months, primarily north of the Missouri River, roosting and raising young under the bark of trees in riparian forests and upland forests near perennial streams. During project activities, avoid degrading stream quality and where possible leave snags standing and preserve mature forest canopy. If large trees with nesting cavities or loose bark need to be removed by your project, that should be done between November and March. Additional information to incorporate in planning documents is available at http://mdc.mo.gov/110. ➤ Gray bats (<i>Myotis grisescens</i>, federally and state listed "endangered") are likely to occur in the project area, as they forage over 			

Appendix C: Antidegradation Review Summary Attachments

The attachments that follow contain summary information provided by the applicant. MDNR staff determined that changes must be made to the information contained within these attachments. The following were modified and can be found within the MDNR WQAR:

1) Tier Determination and Effluent Limit Summary Sheet:

Page 1 - The segment end was not provided. Staff have include a segment end in the WQAR.

Page 2 – Total nitrogen is a tier 1 pollutant. Both total phosphorus and total nitrogen are POCs.

Page 3 – Limitations for ammonia and maximum daily for TSS and BOD have been revised.

2) Attachment A: The BOD and TSS values that were provided in this form and within the full report were incorrectly cited according to Delta Environmental Performance Evaluation document.



MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM
ANTIDEGRADATION REVIEW SUMMARY
TIER DETERMINATION AND EFFLUENT LIMIT SUMMARY

1. FACILITY			
NAME Buccaneer Bay WWTF		TELEPHONE NUMBER WITH AREA CODE 573-964-6956	
ADDRESS (PHYSICAL) 82 Aloha Lane	CITY Sunrise Beach	STATE MO	ZIP CODE 65079
2. RECEIVING WATER BODY SEGMENT #1			
NAME Lake of the Ozarks			
2.1 UPPER END OF SEGMENT (Location of discharge) UTM _____ OR Lat <u>38.1</u> , Long <u>-92.7</u>			
2.2 LOWER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
<small>Per the Missouri Antidegradation Rule and Implementation Procedure, or AIP, the definition of a segment, "a segment is a section of water that is bound, at a minimum, by significant existing sources and confluences with other significant water bodies."</small>			
3. WATER BODY SEGMENT #2 (IF APPLICABLE)			
NAME			
3.1 UPPER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
3.2 LOWER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
4. WATER BODY SEGMENT #3 (IF APPLICABLE)			
NAME			
4.1 UPPER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
4.2 LOWER END OF SEGMENT UTM _____ OR Lat _____, Long _____			
5. PROJECT INFORMATION			
Is the receiving water body an Outstanding National Resource Water, an Outstanding State Resource Water, or drainage thereto? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<small>In Tables D and E of 10 CSR 20-7.031, Outstanding National Resource Waters and Outstanding State Resource Water are listed. Per the Antidegradation Implementation Procedure Section 1.B.3., "any degradation of water quality is prohibited in these waters unless the discharge only results in temporary degradation." Therefore, if degradation is significant or minimal, the Antidegradation Review will be denied.</small>			
Will the proposed discharge of all pollutants of concern, or POCs, result in no net increase in the ambient water quality concentration of the receiving water after mixing? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<small>If yes, submit a summary table showing the levels of each pollutant of concern before and after the proposed discharge in the receiving water and then complete Attachment B for the first downstream classified water body segment.</small>			
Will the discharge result in temporary degradation? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<small>If yes, complete Attachment C.</small>			
Has the project been determined as non-degrading? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<small>If yes, complete No Degradation Evaluation – Conclusion of Antidegradation Review form. Submit with the appropriate Construction Permit Application as no antidegradation review is required.</small>			
If yes to one of the above questions, skip to Section 8 - Wet Weather.			

MO 780-2025 (05-09)

6. EXISTING WATER QUALITY DATA OR MODEL SUMMARY

Obtaining Existing Water Quality is possible by three methods according to the Antidegradation Implementation Procedure Section II.A.1.: (1) using previously collected data with an appropriate Quality Assurance Project Plan, or QAPP (2) collecting water quality data by approved the Missouri Department of Natural Resources methodology or (3) using an appropriate water quality model. QAPPs must be submitted to the department for approval well in advance (six months) of the proposed activity. Provide all the appropriate corresponding data and reports which were approved by the department Water Quality Monitoring and Assessment Section.

Date existing water quality data was provided by the Water Quality Monitoring and Assessment Section:

Approval date of the QAPP by the Water Quality Monitoring and Assessment Section:

Approval date of the project sampling plan by the Water Quality Monitoring and Assessment Section:

Approval date of the data collected for all appropriate pollutants of concern by the Water Quality Monitoring and Assessment Section:

Comments/Discussion:

7. POLLUTANTS OF CONCERN AND TIER DETERMINATION(S)

Pollutants of Concern to be considered include those pollutants reasonably expected to be present in the discharge per the Antidegradation Implementation Procedure Section II.S. The tier protection levels are specified and defined in rule at 10 CSR 20-7.031 (2).

Water Body Segment One		
Pollutants of Concern and Tier Determination(s)		
Tier 1	Tier 2 with Minimal Degradation	Tier 2 with Significant Degradation
		BOD* & TSS*
		DO*
		Ammonia as N*
		Fecal C* & E. Coli*
		Oil & Grease*

Note: Add an asterisk to items that you only assume are Tier 2 with significant degradation.

Water Body Segment Two		
Pollutants of Concern and Tier Determination(s)		
Tier 1	Tier 2 with Minimal Degradation	Tier 2 with Significant Degradation

- For pollutants of concern that are Tier 2 with significant degradation, complete Attachment A.
- For pollutants of concern that are Tier 2 with minimal degradation, complete Attachment B.
- For pollutants of concern that are Tier 1, complete Attachment D. Additionally, a Tier 2 review must be conducted for each pollutant of concern on the appropriate water body segment.

8. WET WEATHER ANTICIPATIONS

If an applicant anticipates excessive inflow or infiltration and pursues approval from the department to bypass secondary treatment, a feasibility analysis is required. The feasibility analysis must comply with the criteria of all applicable state and federal regulations including 40 CFR 122.41(m)(4). Attach the feasibility analysis to this report.

What is the Wet Weather Flow Peaking Factor in relation to design flow?

Wet Weather Design Summary:

No wet weather bypass is being requested at this time

9. SUMMARY OF THE PROPOSED ANTIDegradation REVIEW EFFLUENT LIMITS

What are the proposed pollutants of concern and their respective effluent limits that the selected treatment option will comply with:

Pollutant of Concern	Units	Wasteload Allocation	Average Monthly Limit	Daily Maximum Limit
BOD5	mg/l	20	20	40
TSS	mg/l	20	20	40
Dissolved Oxygen	mg/l	5	5	5 min
Ammonia	mg/l	4.6	4.6	12.1
Bacteria (E. Coli)	#/100ml	126	126	630
Oil & Grease	mg/l	10	10	15

These proposed limits must not violate water quality standards, be protective of beneficial uses and achieve the highest statutory and regulatory requirements.


Attach the Antidegradation Review report and all supporting documentation.

CONSULTANT: I have prepared or reviewed this form and all attached reports and documentation. The conclusion proposed is consistent with the Antidegradation Implementation Procedure and current state and federal regulation.

SIGNATURE 	DATE 6-11-12
NAME AND OFFICIAL TITLES Shelly Hall, PE	
COMPANY NAME LO Environmental, LLC	


ADDRESS PO Box 2325	CITY Lake Ozark	STATE MO	ZIP CODE 65049
TELEPHONE NUMBER WITH AREA CODE 573-964-6956	E-MAIL ADDRESS shelly@loenvironmental.com		


OWNER: I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE 	DATE 6/14/12		
NAME AND OFFICIAL TITLES Curt Mooney Chairman of the Board			
ADDRESS 16537 N. Hwy 5	CITY Sunrise Beach	STATE mo	ZIP CODE 65079
TELEPHONE NUMBER WITH AREA CODE 573-374-8782	E-MAIL ADDRESS citysb@yahoo.com		

CONTINUING AUTHORITY: Continuing Authority is the permanent organization that will be responsible for the operation, maintenance and modernization of the facility. The regulatory requirement regarding continuing authority is found in 10 CSR 20-6.010(3) available at www.sos.mo.gov/adrules/csr/current/10csr/10c20-6a.pdf.

I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE 	DATE 6/14/12		
NAME AND OFFICIAL TITLES Curt Mooney Chairman of the Board			
ADDRESS 16537 N. Hwy 5	CITY Sunrise Beach	STATE mo	ZIP CODE 65079
TELEPHONE NUMBER WITH AREA CODE 573-374-8782	E-MAIL ADDRESS citysb@yahoo.com		



MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM, WATER POLLUTION CONTROL BRANCH
ANTIDegradation REVIEW SUMMARY
ATTACHMENT A: TIER 2 – SIGNIFICANT DEGRADATION

1. FACILITY			
NAME Village of Sunrise Beach, Buccaneer Bay WWTF		TELEPHONE NUMBER WITH AREA CODE	
ADDRESS (PHYSICAL) 82 Aloha	CITY Sunrise Beach	STATE MO	ZIP CODE 65079

2. RECEIVING WATER BODY SEGMENT #1
NAME Lake of the Ozarks

3. WATER BODY SEGMENT #2 (IF APPLICABLE)
NAME

4. IDENTIFYING ALTERNATIVES

Supply a summary of the alternatives considered and the level of treatment attainable with regards to the alternative. "For Discharges likely to cause significant degradation, an analysis of non-degrading and less-degrading alternatives must be provided," as stated in the Antidegradation Implementation Procedure Section II.B.1. Per 10 CSR 20-6.010(4)(D)1., the feasibility of a no-discharge system must be considered. Attach all supportive documentation in the Antidegradation Review report.

Non-degrading alternatives: Connection to Regional

Alternatives ranging from less-degrading to degrading including Preferred Alternative (All must meet water quality standards):

Alternatives	Level of Treatment Attainable for each Pollutant of Concern				
	BOD	TSS	Ammonia as N	Bacteria (E. Coli)	
	(mg/L)	(mg/L)	(mg/L)	(#/100mL)	
Delta Pod/UV/Reaeration	9	8	0.8-2.5	126 (UV)	
Extended Aeration/UV	10	15	5	126 (UV)	
Recirculating Sand Filter/UV	15	10	5	126 (UV)	

Identifying Alternatives Summary: _____

Expanding the existing 9,000 gallon per day plant is the most cost effective. Present Worth Cost with a 20 year life cycle was used.

MO780-2021 (01/09)

5. DETERMINATION OF THE REASONABLE ALTERNATIVE

Per the Antidegradation Implementation Procedure Section II.B.2, "a reasonable alternative is one that is practicable, economically efficient and affordable." Provide basis and supporting documentation in the Antidegradation Review report.

Practicability Summary:

"The practicability of an alternative is considered by evaluating the effectiveness, reliability, and potential environmental impacts," according to the Antidegradation Implementation Procedure Section II.B.2.a. Examples of factors to consider, including secondary environmental impacts, are given in the Antidegradation Implementation Procedure Section II.B.2.a.

The BIOPOD system installed is technology that can effectively meet the effluent limits w/minimal risk to the lake.

Economic Efficiency Summary:

Alternatives that are deemed practicable must undergo a direct cost comparison in order to determine economic efficiency. Means to determine economic efficiency are provided in the Antidegradation Implementation Procedure Section II.B.2.b.

All treatments considered are capable of meeting stringent limits. Therefore the least expensive one was chosen.

Affordability Summary:

Alternatives identified as most practicable and economically efficient are considered affordable if the applicant does not supply an affordability analysis. An affordability analysis per the Antidegradation Implementation Procedure Section II.B.2.c, "may be used to determine if the alternative is too expensive to reasonably implement."

An affordability analysis was not performed

Preferred Chosen Alternative:

BIOPOD/UV/Re-aeration/grease traps/septic tank

Reasons for Rejecting the other Evaluated Alternatives:

Sand Filter & Mechanical plant was rejected because of the higher cost.

Comments/Discussion:

The proposed project shall include the expansion of a permitted facility from 9,000 gpd to 50,000 gpd. The existing permit has a design flow of 9,000 for the first phase but has been approved for 23,690 gpd. The facility discharges to a small drainage approximately 700 feet up shore from the Lake of the Ozarks, a gaining setting. The plant shall meet all MODNR effluent limits for pollutants of concern as detailed in the Antidegradation Review Summary Attachment A: Tier 2. The expansion will serve the first phase for the Village of Sunrise Beach Sewer.

6. SOCIAL AND ECONOMIC IMPORTANCE OF THE PREFERRED ALTERNATIVE

If the preferred alternative will result in significant degradation, then it must be demonstrated that it will allow important economic and social development in accordance to the Antidegradation Implementation Procedure Section II.E. Social and Economic Importance is defined as the social and economic benefits to the community that will occur from any activity involving a new or expanding discharge.

Identify the affected community:
The affected community is defined in 10 CSR 20-7.031(2)(B) as the community "in the geographical area in which the waters are located.: Per the Antidegradation Implementation Procedure Section II.E.1, "the affected community should include those living near the site of the proposed project as well as those in the community that are expected to directly or indirectly benefit from the project."

Property owners and business in the Village of Sunrise Beach located along Hwy 5 south of F and north of the Hurricane Deck Bridg

Identify relevant factors that characterize the social and economic conditions of the affected community:
Examples of social and economic factors are provided in the Antidegradation Implementation Procedure Section II.E.1., but specific community examples are encouraged.

Many businesses and home owners have struggled with failing sewer systems. Most cannot afford the cost associated with upgrading their systems or do not have the land needed to build on-site systems. Failing systems can pollute the Lake which many rely on for jobs. Growth my very well be stymied if the Village cannot move forward with a centralized sewer system.

Describe the important social and economic development associated with the project:
Determining benefits for the community and the environment should be site specific and in accordance with the Antidegradation Implementation Procedure Section II.E.1.

Centralized sewer in the area would encourage development, with development comes needed employment and protection of health.

PROPOSED PROJECT SUMMARY:

Public sewer is desperately needed in this area of the Lake. Phase I would provide sewer to 76 customers.

Attach the Antidegradation Review report and all supporting documentation. This is a technical document, which must be signed, sealed and dated by a registered professional engineer of Missouri.

CONSULTANT: I have prepared or reviewed this form and all attached reports and documentation. The conclusion proposed in consistent with the Antidegradation Implementation Procedure and current state and federal regulations.

SIGNATURE	DATE
-----------	------

PRINT NAME Shelly Hall, PE	LICENSE #: MO 2009001084
-------------------------------	-----------------------------

TELEPHONE NUMBER WITH AREA CODE 573-964-6956	E-MAIL ADDRESS: shelly@loenvironmental.com
---	---

OWNER: I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE <i>Curt Moony</i>	DATE 6/14/12
--------------------------------	-----------------

CONTINUING AUTHORITY: I have read and reviewed the prepared documents and agree with this submittal.

SIGNATURE <i>Curt Moony</i>	DATE 6/14/12
--------------------------------	-----------------

APPENDIX 4 – FINDING OF AFFORDABILITY:

**Missouri Department of Natural Resources
Water Protection Program
Affordability Determination and Finding
(In accordance with RSMo 644.145)**

**Sunrise Beach WWTF
Village of Sunrise Beach
For the purpose of construction of a new WWTF
Operating Permit MO-0137278**

Section 644.145 RSMo requires the Missouri Department of Natural Resources to make a “finding of affordability” when “issuing permits under” or “enforcing provisions of” state or federal clean water laws “pertaining to any portion of a combined or separate sanitary sewer system or publicly-owned treatment works.”

Facility Description:

The proposed Sunrise Beach Wastewater Treatment Facility (WWTF) will be located near the intersection of Highway 5 and Kula Bay Drive, Sunrise Beach, Missouri in Camden County. The proposed treatment facility shall consist of flow equalization, extended aeration mechanical package plant, tertiary filtration, chemical addition for phosphorus removal, ultraviolet disinfection, and sludge disposal by contract hauler. The proposed design average flow is 50,000 gallons per day (gpd) and a peak wet weather flow of 124,000 gpd.

Receiving Stream: Unnamed Tributary to Lake of the Ozarks (U)
First Classified Stream and ID: Lake of the Ozarks (L2) (07205) 303(d) list
USGS Basin & Sub-watershed No.: (102901090207)

Residential Connections:	<u>39</u>
Commercial Connections:	<u>37</u>
Total Connections ¹ :	<u>76</u>

New Permit Requirements or Requirements Now Being Enforced:

The Village of Sunrise Beach is an unsewered community. The village desires to construct a centralized collection system and treatment facility in anticipation of economic growth for the community. The Department received a construction permit application request on December 6, 2012 for the proposed construction of a collection system and new wastewater treatment facility. The village plans on phasing the construction of the wastewater system in order to provide service to the entire community.

Range of Anticipated Costs Associated with Complying with Requirements:

According to the Village of Sunrise Beach Facility Plan estimates the cost of constructing the treatment facility to be \$652,500 (Page 22 of the facility plan). The total project cost of phase 1 including the collection system is estimated to be \$2,548,300 (Page 23 of the facility plan).

¹ The number of connections was obtained from the Facility Plan for the Village of Sunrise Beach received on August 7, 2012 and approved on January 16, 2013.

(1) A community’s financial capability and ability to raise or secure necessary funding:

The Village of Sunrise Beach is on the 2013 Intended Use Plan under the fundable projects list. The village has passed a \$8,000,000 bond issue on April 7, 2009. The Village of Sunrise Beach anticipates receiving a \$2,292,800 loan from the Department’s State Revolving Fund (SRF) (Page 24 of the facility plan).

Proposed User Rates (monthly 3,000 gpd usage):	<u>\$46.12</u>
Municipal Bond Rating (if applicable):	<u>N/A</u>
Bonding Capacity: <i>(General Obligation Bond capacity allowed by constitution: cities=up to 20% of taxable tangible property sewer districts=up to 5% of taxable tangible property)</i>	<u>Unknown</u>
Current outstanding debt:	<u>Unknown</u>

Other indicators:

Since the Village of Sunrise Beach has passed a \$8,000,000 bond issue, they are capable of completing the construction of the treatment facility and phase 1 of the collection system contingent on receiving SRF financing.

(2) Affordability of pollution control options for the individuals or households of the community:

Current annual operating costs (exclude depreciation):	<u>\$0</u>
Current user rate:	<u>\$0</u>
Estimated capital cost of pollution control options:	<u>\$2,548,300</u>
Annual Cost of Additional (Operating Costs & Debt Service):	<u>\$218,500</u>
Estimated Resulting User Rate and/or Cost per Household:	<u>\$553.44</u>
Median Household Income	<u>\$28,730</u>
Rate and/or Cost per Household as a Percent of Median Household Income: <i>(Rate/MHI = (553.44/28,730)*100 = 1.93%)</i>	<u>1.93%</u>

Check Appropriate Box	Financial Impact	Residential Indicator (Usage Rate as a percent of MHI = annual cost/MHI)
	Low	Less than 1% MHI
X	Medium	Between 1% and 2% MHI
	High	Greater than 2% MHI

The residential indicator was determined to have a medium financial impact based on the proposed user rate, which is approximately 1.93% of the median household income.

(3) An evaluation of the overall costs and environmental benefits of the control technologies:

The Village of Sunrise Beach evaluated multiple alternatives for the proposed treatment facility. The Antidegradation Report and Facility Plan completed for the village provides detailed discussions of the alternatives evaluated. Alternatives ranged from regionalization with the Gravois Arms Sewer District, land application, and new discharging wastewater treatment facilities. The construction of an extended aeration mechanical package plant was determined to be the most cost effective and practical option. The village elected to phase the development of the treatment facility and collection system to serve the entire community.

An extended aeration treatment facility is a proven technology in the state that achieves a high quality of effluent. The facility will treat an organic load of 170 pounds of Bio-chemical Oxygen Demand (BOD₅) per day. The proposed facility is designed to meet average monthly limits of 20 milligrams per liter (mg/L) BOD₅ and 20 mg/L Total Suspended Solids (TSS).

The receiving stream is an Unnamed Tributary to the Lake of the Ozarks. The permit limits were derived to protect the beneficial uses of the Lake of the Ozarks. The beneficial uses of the Lake of the Ozarks are whole body contact recreation, secondary contact recreation, livestock and wildlife watering, and protection of warm water aquatic life and human health fish consumption.

(4) An inclusion of ways to reduce economic impacts on distressed populations in the community, including but not limited to, low and fixed income populations. This requirement includes but is not limited to:

- (a) *Allowing adequate time in implementation schedules to mitigate potential adverse impacts on distressed populations resulting from the costs of the improvements and taking into consideration local community economic considerations; and*
- (b) *Allowing for reasonable accommodations for regulated entities when inflexible standards and fines would impose a disproportionate financial hardship in light of the environmental benefits to be gained.*

Potentially Distressed Populations	
Unemployment for Village of Sunrise Beach ²	8.2%
Median Household Income (MHI) in Village of Sunrise Beach ³	\$28,730
Percent Change in MHI (1990-2010)	+29.9%
Percent Population Growth/Decline (1990-2010) ⁴	+138.1%
Change in Median Age in Years (1990-2010)	+8.1 years
Percent of Households in Poverty ⁵	14.3%
Percent of Households Relying on Food Stamps	11.6%

Opportunity for cost savings or cost avoidance:

The Village of Sunrise Beach has applied for a SRF loan. The village will realize savings in interest comparing a SRF loan to a private loan.

Opportunity for changes to implementation/compliance schedule:

None Noted

(5) An assessment of other community investments relating to environmental improvements:

The Village of Sunrise Beach owns and operates a public drinking water system for the community. Annual operation and maintenance budgets must be maintained for the drinking water system as well.

² Unemployment data was obtained from American Fact Finder at http://factfinder2.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_10_5YR_S1901&prodType=table

³ Median Household Income is provided by the American Fact Finder – INCOME IN THE PAST 12 MONTHS (IN 2010 INFLATION ADJUSTED DOLLARS) – 2006 – 2010 American Community Survey 5-Year Estimates, which can be found online at:

http://factfinder2.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_10_5YR_S1901&prodType=table

⁴ Population trend data was obtained from online at http://mcdc1.missouri.edu/cgi-bin/profiler/profiler.py?profile_id=SF1_2010&geoids=16000US2912988

⁵ Poverty data is provided by the American Fact Finder – POVERTY STATUS IN THE PAST 12 MONTHS – 2006-2010 American Community Survey 5-Year Estimates, which can be found online at

http://factfinder2.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_10_5YR_DP03&prodType=table

- (6) An assessment of factors set forth in the United States Environmental Protection Agency's guidance, including but not limited to the "Combined Sewer Overflow Guidance for Financial Capability Assessment and Schedule Development" that may ease the cost burdens of implementing wet weather control plans, including but not limited to, small system considerations, the attainability of water quality standards, and the development of wet weather standards:

Secondary indicators for consideration:

Socioeconomic, Debt and Financial Indicators

Indicators	Strong (3 points)	Mid-Range (2 points)	Weak (1 point)	Score
Bond rating indicator	Above BBB or Baa	BBB or Baa	Below BBB or Baa	N/A
Overall net debt as a % of full market property value	Below 2%	2% - 5%	Above 5%	N/A
Unemployment Rate	>1% below Missouri average	± 1% of Missouri average	>1% above Missouri average	1
Median household income	More than 25% above Missouri MHI	± 25% of Missouri MHI	More than 25% below Missouri average	1
Property tax revenues as a % of full market property value	Below 2%	2% - 4%	Above 4%	N/A
Property tax collection rate	Above 98%	94% - 98%	Below 94%	N/A

Secondary Indicators Average Score: 1

Residential Indicator (from Criteria #2 above): 1.93% medium impact

Financial Capability Matrix:

Financial Capability Indicators Score from above ↓	Residential Indicator (User rate as a % of MHI)		
	Low (Below 1%)	Mid-Range (Between 1.0% and 2.0%)	High (Above 2.0%)
Weak (below 1.5)	Medium Burden	High Burden	High Burden
Mid-Range (1.5 – 2.5)	Low Burden	Medium Burden	High Burden
Strong (above 2.5)	Low Burden	Low Burden	Medium Burden

Estimated Financial Burden: high burden

- (7) An assessment of any other relevant local community economic condition.

The Village of Sunrise Beach's population grew 138.1% from 1990-2010. In terms of economic strength, Camden County is on lower than average when compared to other counties in the State. The per capita income is 13.2% lower than the State's average.⁶

In terms of retail Sales, Camden County gains retail customers from surrounding counties and the County residents spend more than the state average on retail goods and services. The buying power index of Camden County residents is above average compared to the rest of the regional economy.⁷

⁶ County per capita income was obtained online at <http://www.missourieconomy.org/indicators/wages/pci10county.stm>.

Conclusion and Finding

The Village of Sunrise Beach requested a construction permit for the construction of a centralized collection system and new wastewater treatment facility for the village. The Department finds that these improvements will improve the water quality of the Lake of the Ozarks by elimination of failing on-site systems and improve the public health of the community.

The Department considered all seven (7) of the criteria presented in subsection 644.145.3 when evaluating the affordability of the relevant actions. Taking into consideration these criteria, this analysis examined whether the above referenced permit modifications affects the ability of an individual customer or household to pay a utility bill without undue hardship or unreasonable sacrifice in the essential lifestyle or spending patterns of the individual or household. As a result of reviewing the above criteria, the Department hereby finds that the action described above will result in a high burden with regard to the community's overall financial capability and a medium financial impact for most individual customers/households.

⁷ Retail trade analysis was obtained online at http://www.missourieconomy.org/pdfs/central_wia_retail_trade_analysis.pdf.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

These Standard Conditions incorporate permit conditions as required by 40 CFR 122.41 or other applicable state statutes or regulations. These minimum conditions apply unless superseded by requirements specified in the permit.

PART I – GENERAL CONDITIONS

SECTION A – SAMPLING, MONITORING, AND RECORDING

1. **Sampling Requirements.**
 - a. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity.
 - b. All samples shall be taken at the outfall(s) or Missouri Department of Natural Resources (Department) approved sampling location(s), and unless specified, before the effluent joins or is diluted by any other body of water or substance.
2. **Monitoring Requirements.**
 - a. Records of monitoring information shall include:
 - i. The date, exact place, and time of sampling or measurements;
 - ii. The individual(s) who performed the sampling or measurements;
 - iii. The date(s) analyses were performed;
 - iv. The individual(s) who performed the analyses;
 - v. The analytical techniques or methods used; and
 - vi. The results of such analyses.
 - b. If the permittee monitors any pollutant more frequently than required by the permit at the location specified in the permit using test procedures approved under 40 CFR Part 136, or another method required for an industry-specific waste stream under 40 CFR subchapters N or O, the results of such monitoring shall be included in the calculation and reported to the Department with the discharge monitoring report data (DMR) submitted to the Department pursuant to Section B, paragraph 7.
3. **Sample and Monitoring Calculations.** Calculations for all sample and monitoring results which require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in the permit.
4. **Test Procedures.** The analytical and sampling methods used shall conform to the reference methods listed in 10 CSR 20-7.015 unless alternates are approved by the Department. The facility shall use sufficiently sensitive analytical methods for detecting, identifying, and measuring the concentrations of pollutants. The facility shall ensure that the selected methods are able to quantify the presence of pollutants in a given discharge at concentrations that are low enough to determine compliance with Water Quality Standards in 10 CSR 20-7.031 or effluent limitations unless provisions in the permit allow for other alternatives. A method is “sufficiently sensitive” when: 1) the method minimum level is at or below the level of the applicable water quality criterion for the pollutant or, 2) the method minimum level is above the applicable water quality criterion, but the amount of pollutant in a facility’s discharge is high enough that the method detects and quantifies the level of pollutant in the discharge, or 3) the method has the lowest minimum level of the analytical methods approved under 10 CSR 20-7.015. These methods are also required for parameters that are listed as monitoring only, as the data collected may be used to determine if limitations need to be established. A permittee is responsible for working with their contractors to ensure that the analysis performed is sufficiently sensitive.
5. **Record Retention.** Except for records of monitoring information required by the permit related to the permittee's sewage sludge use and disposal activities, which shall be retained for a period of at least five (5) years (or longer as required by 40 CFR part 503), the permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the application for the permit, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Department at any time.

6. **Illegal Activities.**
 - a. The Federal Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the permit shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than two (2) years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than \$20,000 per day of violation, or by imprisonment of not more than four (4) years, or both.
 - b. The Missouri Clean Water Law provides that any person or who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than six (6) months, or by both. Second and successive convictions for violation under this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.

SECTION B – REPORTING REQUIREMENTS

1. **Planned Changes.**
 - a. The permittee shall give notice to the Department as soon as possible of any planned physical alterations or additions to the permitted facility when:
 - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b); or
 - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements under 40 CFR 122.42(a)(1);
 - iii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan;
 - iv. Any facility expansions, production increases, or process modifications which will result in a new or substantially different discharge or sludge characteristics must be reported to the Department 60 days before the facility or process modification begins. Notification may be accomplished by application for a new permit. If the discharge does not violate effluent limitations specified in the permit, the facility is to submit a notice to the Department of the changed discharge at least 30 days before such changes. The Department may require a construction permit and/or permit modification as a result of the proposed changes at the facility.
2. **Twenty-Four Hour Reporting.**
 - a. The permittee shall report any noncompliance which may endanger health or the environment. Relevant information shall be provided orally or via the current electronic method approved by the Department, within 24 hours from the time the permittee becomes aware of the circumstances, and shall be reported to the appropriate Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. A written submission shall also be provided within five (5) business days of the time the permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

- b. The following shall be included as information which must be reported within 24 hours under this paragraph.
 - i. Any unanticipated bypass which exceeds any effluent limitation in the permit.
 - ii. Any upset which exceeds any effluent limitation in the permit.
 - iii. Violation of a maximum daily discharge limitation for any of the pollutants listed by the Department in the permit required to be reported within 24 hours.
 - c. The Department may waive the written report on a case-by-case basis for reports under paragraph 2. b. of this section if the oral report has been received within 24 hours.
3. **Sanitary Sewer Overflow Reporting.** The following requirements solely reflect reporting obligations, and reporting does not necessarily reflect noncompliance, which may depend on the circumstances of the incident reported.
- a. **Twenty-Four Hour (24-Hour) Reporting.** The permittee or owner shall report any incident in which wastewater escapes the collection system such that it reaches waters of the state or it may pose an imminent or substantial endangerment to the health or welfare of persons. Relevant information shall be provided orally or via the current electronic method approved by the Department within 24 hours from the time the permittee becomes aware of the incident. A written submission shall also be provided within five (5) business days of the time the permittee or owner becomes aware of the incident. The Department may waive the written report on a case-by-case basis if the oral report has been received within 24 hours. The five (5) day reports may be provided via the current electronic method approved by the Department.
 - b. **Incidents Reported via Discharge Monitoring Reports (DMRs).** The permittee or owner shall report any event in which wastewater escapes the collection system, which does not enter waters of the state and is not expected to pose an imminent or substantial endangerment to the health or welfare of persons, which occur typically during wet weather events. Relevant information shall be provided with the permittee's or owner's DMRs.
4. **Anticipated Noncompliance.** The permittee shall give advance notice to the Department of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements. The notice shall be submitted to the Department 60 days prior to such changes or activity.
5. **Compliance Schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date. The report shall provide an explanation for the instance of noncompliance and a proposed schedule or anticipated date, for achieving compliance with the compliance schedule requirement.
6. **Other Noncompliance.** The permittee shall report all instances of noncompliance not reported under paragraphs 2, 3, 4, and 7 of this section, at the time monitoring reports are submitted. The reports shall contain the information listed in paragraph 2. a. of this section.
7. **Other Information.** Where the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Department, it shall promptly submit such facts or information.
8. **Discharge Monitoring Reports.**
- a. Monitoring results shall be reported at the intervals specified in the permit.
 - b. Monitoring results must be reported to the Department via the current method approved by the Department, unless the permittee has been granted a waiver from using the method. If the permittee has been granted a waiver, the permittee must use forms provided by the Department.
 - c. Monitoring results shall be reported to the Department no later than the 28th day of the month following the end of the reporting period.

SECTION C – BYPASS/UPSET REQUIREMENTS

1. **Definitions.**
 - a. *Bypass:* the intentional diversion of waste streams from any portion of a treatment facility.
 - b. *Severe Property Damage:* substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
 - c. *Upset:* an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
2. **Bypass Requirements.**
 - a. Bypass not exceeding limitations. The permittee may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of paragraphs 2. b. and 2. c. of this section.
 - b. Notice.
 - i. Anticipated bypass. If the permittee knows in advance of the need for a bypass, it shall submit prior notice, if possible at least 10 days before the date of the bypass.
 - ii. Unanticipated bypass. The permittee shall submit notice of an unanticipated bypass as required in Section B – Reporting Requirements, paragraph 5 (24-hour notice).
 - c. Prohibition of bypass.
 - i. Bypass is prohibited, and the Department may take enforcement action against a permittee for bypass, unless:
 1. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
 2. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and
 3. The permittee submitted notices as required under paragraph 2. b. of this section.
 - ii. The Department may approve an anticipated bypass, after considering its adverse effects, if the Department determines that it will meet the three (3) conditions listed above in paragraph 2. c. i. of this section.
3. **Upset Requirements.**
 - a. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of paragraph 3. b. of this section are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.
 - b. Conditions necessary for a demonstration of upset. A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
 - i. An upset occurred and that the permittee can identify the cause(s) of the upset;
 - ii. The permitted facility was at the time being properly operated; and
 - iii. The permittee submitted notice of the upset as required in Section B – Reporting Requirements, paragraph 2. b. ii. (24-hour notice).
 - iv. The permittee complied with any remedial measures required under Section D – Administrative Requirements, paragraph 4.
 - c. Burden of proof. In any enforcement proceeding, the permittee seeking to establish the occurrence of an upset has the burden of proof.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

SECTION D – ADMINISTRATIVE REQUIREMENTS

1. **Duty to Comply.** The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Missouri Clean Water Law and Federal Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.
 - a. The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
 - b. The Federal Clean Water Act provides that any person who violates section 301, 302, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any such sections in a permit issued under section 402, or any requirement imposed in a pretreatment program approved under sections 402(a)(3) or 402(b)(8) of the Act, is subject to a civil penalty not to exceed \$25,000 per day for each violation. The Federal Clean Water Act provides that any person who negligently violates sections 301, 302, 306, 307, 308, 318, or 405 of the Act, or any condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, or any requirement imposed in a pretreatment program approved under section 402(a)(3) or 402(b)(8) of the Act, is subject to criminal penalties of \$2,500 to \$25,000 per day of violation, or imprisonment of not more than one (1) year, or both. In the case of a second or subsequent conviction for a negligent violation, a person shall be subject to criminal penalties of not more than \$50,000 per day of violation, or by imprisonment of not more than two (2) years, or both. Any person who knowingly violates such sections, or such conditions or limitations is subject to criminal penalties of \$5,000 to \$50,000 per day of violation, or imprisonment for not more than three (3) years, or both. In the case of a second or subsequent conviction for a knowing violation, a person shall be subject to criminal penalties of not more than \$100,000 per day of violation, or imprisonment of not more than six (6) years, or both. Any person who knowingly violates section 301, 302, 303, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, and who knows at that time that he thereby places another person in imminent danger of death or serious bodily injury, shall, upon conviction, be subject to a fine of not more than \$250,000 or imprisonment of not more than 15 years, or both. In the case of a second or subsequent conviction for a knowing endangerment violation, a person shall be subject to a fine of not more than \$500,000 or by imprisonment of not more than 30 years, or both. An organization, as defined in section 309(c)(3)(B)(iii) of the CWA, shall, upon conviction of violating the imminent danger provision, be subject to a fine of not more than \$1,000,000 and can be fined up to \$2,000,000 for second or subsequent convictions.
 - c. Any person may be assessed an administrative penalty by the EPA Director for violating section 301, 302, 306, 307, 308, 318 or 405 of this Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of this Act. Administrative penalties for Class I violations are not to exceed \$10,000 per violation, with the maximum amount of any Class I penalty assessed not to exceed \$25,000. Penalties for Class II violations are not to exceed \$10,000 per day for each day during which the violation continues, with the maximum amount of any Class II penalty not to exceed \$125,000.
 - d. It is unlawful for any person to cause or permit any discharge of water contaminants from any water contaminant or point source located in Missouri in violation of sections 644.006 to 644.141 of the Missouri Clean Water Law, or any standard, rule or regulation promulgated by the commission. In the event the commission or the director determines that any provision of sections 644.006 to 644.141 of the Missouri Clean Water Law or standard, rules, limitations or regulations promulgated pursuant thereto, or permits issued by, or any final abatement order, other order, or determination made by the commission or the director, or any filing requirement pursuant to sections 644.006 to 644.141 of the Missouri Clean Water Law or any other provision which this state is required to enforce pursuant to any federal water pollution control act, is being, was, or is in imminent danger of being violated, the commission or director may cause to have instituted a civil action in any court of competent jurisdiction for the injunctive relief to prevent any such violation or further violation or for the assessment of a penalty not to exceed \$10,000 per day for each day, or part thereof, the violation occurred and continues to occur, or both, as the court deems proper. Any person who willfully or negligently commits any violation in this paragraph shall, upon conviction, be punished by a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than one year, or both. Second and successive convictions for violation of the same provision of this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.
2. **Duty to Reapply.**
 - a. If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and obtain a new permit.
 - b. A permittee with a currently effective site-specific permit shall submit an application for renewal at least 180 days before the expiration date of the existing permit, unless permission for a later date has been granted by the Department. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
 - c. A permittees with currently effective general permit shall submit an application for renewal at least 30 days before the existing permit expires, unless the permittee has been notified by the Department that an earlier application must be made. The Department may grant permission for a later submission date. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
3. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.
4. **Duty to Mitigate.** The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.
5. **Proper Operation and Maintenance.** The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems which are installed by a permittee only when the operation is necessary to achieve compliance with the conditions of the permit.
6. **Permit Actions.**
 - a. Subject to compliance with statutory requirements of the Law and Regulations and applicable Court Order, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:
 - i. Violations of any terms or conditions of this permit or the law;
 - ii. Having obtained this permit by misrepresentation or failure to disclose fully any relevant facts;
 - iii. A change in any circumstances or conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge; or
 - iv. Any reason set forth in the Law or Regulations.
 - b. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
NOVEMBER 1, 2013

7. **Permit Transfer.**
 - a. Subject to 10 CSR 20-6.010, an operating permit may be transferred upon submission to the Department of an application to transfer signed by the existing owner and the new owner, unless prohibited by the terms of the permit. Until such time the permit is officially transferred, the original permittee remains responsible for complying with the terms and conditions of the existing permit.
 - b. The Department may require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the Missouri Clean Water Law or the Federal Clean Water Act.
 - c. The Department, within 30 days of receipt of the application, shall notify the new permittee of its intent to revoke or reissue or transfer the permit.
8. **Toxic Pollutants.** The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the Federal Clean Water Act within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
9. **Property Rights.** This permit does not convey any property rights of any sort, or any exclusive privilege.
10. **Duty to Provide Information.** The permittee shall furnish to the Department, within a reasonable time, any information which the Department may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The permittee shall also furnish to the Department upon request, copies of records required to be kept by this permit.
11. **Inspection and Entry.** The permittee shall allow the Department, or an authorized representative (including an authorized contractor acting as a representative of the Department), upon presentation of credentials and other documents as may be required by law, to:
 - a. Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of the permit;
 - b. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
 - c. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
 - d. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Federal Clean Water Act or Missouri Clean Water Law, any substances or parameters at any location.
12. **Closure of Treatment Facilities.**
 - a. Persons who cease operation or plan to cease operation of waste, wastewater, and sludge handling and treatment facilities shall close the facilities in accordance with a closure plan approved by the Department.
 - b. Operating Permits under 10 CSR 20-6.010 or under 10 CSR 20-6.015 are required until all waste, wastewater, and sludges have been disposed of in accordance with the closure plan approved by the Department and any disturbed areas have been properly stabilized. Disturbed areas will be considered stabilized when perennial vegetation, pavement, or structures using permanent materials cover all areas that have been disturbed. Vegetative cover, if used, shall be at least 70% plant density over 100% of the disturbed area.
13. **Signatory Requirement.**
 - a. All permit applications, reports required by the permit, or information requested by the Department shall be signed and certified. (See 40 CFR 122.22 and 10 CSR 20-6.010)
 - b. The Federal Clean Water Act provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or non-compliance shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than six (6) months per violation, or by both.
14. **Severability.** The provisions of the permit are severable, and if any provision of the permit, or the application of any provision of the permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of the permit, shall not be affected thereby.



STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
REVISED
MAY 1, 2013

PART II - SPECIAL CONDITIONS – PUBLICLY OWNED
TREATMENT WORKS
SECTION A – INDUSTRIAL USERS

1. Definitions

Definitions as set forth in the Missouri Clean Water Laws and approved by the Missouri Clean Water Commission shall apply to terms used herein.

Significant Industrial User (SIU). Except as provided in the *General Pretreatment Regulation* 10 CSR 20-6.100, the term Significant Industrial User means:

1. All Industrial Users subject to Categorical Pretreatment Standards; and
2. Any other Industrial User that: discharges an average of 25,000 gallons per day or more of process wastewater to the Publicly-Owned Treatment Works (POTW) (excluding sanitary, noncontact cooling and boiler blowdown wastewater); contributes a process wastestream which makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the POTW treatment plant; or is designated as such by the Control Authority on the basis that the Industrial User has a reasonable potential for adversely affecting the POTW's or for violating any Pretreatment Standard or requirement.

Clean Water Act (CWA) is the federal Clean Water Act of 1972, 33 U.S.C. § 1251 et seq. (2002).

2. Identification of Industrial Discharges

Pursuant to 40 CFR 122.44(j)(1), all POTWs shall identify, in terms of character and volume of pollutants, any Significant Industrial Users discharging to the POTW subject to Pretreatment Standards under section 307(b) of the CWA and 40 CFR 403.

3. Application Information

Applications for renewal or modification of this permit must contain the information about industrial discharges to the POTW pursuant to 40 CFR 122.21(j)(6)

4. Notice to the Department

Pursuant to 40 CFR 122.42(b), all POTWs must provide adequate notice of the following:

1. Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to section 301 or 306 of CWA if it were directly discharging these pollutants; and
2. Any substantial change into the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit.
3. For purposes of this paragraph, adequate notice shall include information on:
 - i. the quality and quantity of effluent introduced into the POTW, and
 - ii. any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

For POTWs without an approved pretreatment program, the notice of industrial discharges which was not included in the permit application shall be made as soon as practicable. For POTWs with an approved pretreatment program, notice is to be included in the annual pretreatment report required in the special conditions of this permit. Notice may be sent to:

Missouri Department of Natural Resources
Water Protection Program
Attn: Pretreatment Coordinator
P.O. Box 176
Jefferson City, MO 65102

STANDARD CONDITIONS FOR NPDES PERMITS
ISSUED BY
THE MISSOURI DEPARTMENT OF NATURAL RESOURCES
MISSOURI CLEAN WATER COMMISSION
March 1, 2014

**PART III – SLUDGE AND BIOSOLIDS FROM DOMESTIC AND INDUSTRIAL WASTEWATER
TREATMENT FACILITIES**

SECTION A – GENERAL REQUIREMENTS

1. This permit pertains to sludge requirements under the Missouri Clean Water Law and regulation for domestic wastewater and industrial process wastewater. This permit also incorporates applicable federal sludge disposal requirements under 40 CFR 503 for domestic wastewater. The Environmental Protection Agency (EPA) has principal authority for permitting and enforcement of the federal sludge regulations under 40 CFR 503 for domestic wastewater. EPA has reviewed and accepted these standard sludge conditions. EPA may choose to issue a separate sludge addendum to this permit or a separate federal sludge permit at their discretion to further address the federal requirements.
2. These PART III Standard Conditions apply only to sludge and biosolids generated at domestic wastewater treatment facilities, including public owned treatment works (POTW), privately owned facilities and sludge or biosolids generated at industrial facilities.
3. Sludge and Biosolids Use and Disposal Practices:
 - a. The permittee is authorized to operate the sludge and biosolids treatment, storage, use, and disposal facilities listed in the facility description of this permit.
 - b. The permittee shall not exceed the design sludge volume listed in the facility description and shall not use sludge disposal methods that are not listed in the facility description, without prior approval of the permitting authority.
 - c. The permittee is authorized to operate the storage, treatment or generating sites listed in the Facility Description section of this permit.
4. Sludge Received from other Facilities:
 - a. Permittees may accept domestic wastewater sludge from other facilities including septic tank pumpings from residential sources as long as the design sludge volume is not exceeded and the treatment facility performance is not impaired.
 - b. The permittee shall obtain a signed statement from the sludge generator or hauler that certifies the type and source of the sludge
5. These permit requirements do not supersede nor remove liability for compliance with county and other local ordinances.
6. These permit requirements do not supersede nor remove liability for compliance with other environmental regulations such as odor emissions under the Missouri Air Pollution Control Law and regulations.
7. This permit may (after due process) be modified, or alternatively revoked and reissued, to comply with any applicable sludge disposal standard or limitation issued or approved under Section 405(d) of the Clean Water Act under Chapter 644 RSMo.
8. In addition to STANDARD CONDITIONS, the Department may include sludge limitations in the special conditions portion or other sections of a site specific permit.
9. Alternate Limits in the Site Specific Permit.

Where deemed appropriate, the Department may require an individual site specific permit in order to authorize alternate limitations:

 - a. A site specific permit must be obtained for each operating location, including application sites.
 - b. To request a site specific permit, an individual application, permit fee, and supporting documents shall be submitted for each operating location. This shall include a detailed sludge/biosolids management plan or engineering report.
10. Exceptions to these Standard Conditions may be authorized on a case-by-case basis by the Department, as follows:
 - a. The Department will prepare a permit modification and follow permit notice provisions as applicable under 10 CSR 20-6.020, 40 CFR 124.10, and 40 CFR 501.15(a)(2)(ix)(E). This includes notification of the owner of the property located adjacent to each land application site, where appropriate.
 - b. Exceptions cannot be granted where prohibited by the federal sludge regulations under 40 CFR 503.

SECTION B – DEFINITIONS

1. Best Management Practices include agronomic loading rates, soil conservation practices and other site restrictions.
2. Biosolids means organic fertilizer or soil amendment produced by the treatment of domestic wastewater sludge.
3. Biosolids land application facility is a facility where biosolids are spread onto the land at agronomic rates for production of food or fiber. The facility includes any structures necessary to store the biosolids until soil, weather, and crop conditions are favorable for land application.
4. Class A biosolids means a material that has met the Class A pathogen reduction requirements or equivalent treatment by a Process to Further Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
5. Class B biosolids means a material that has met the Class B pathogen reduction requirements or equivalent treatment by a Process to Significantly Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
6. Domestic wastewater means wastewater originating from the sanitary conveniences of residences, commercial buildings, factories and institutions; or co-mingled sanitary and industrial wastewater processed by a (POTW) or a privately owned facility.
7. Industrial wastewater means any wastewater, also known as process water, not defined as domestic wastewater. Per 40 CFR Part 122, process water means any water which, during manufacturing or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct, or waste product.
8. Mechanical treatment plants are wastewater treatment facilities that use mechanical devices to treat wastewater, including septic tanks, sand filters, extended aeration, activated sludge, contact stabilization, trickling filters, rotating biological discs, and other similar facilities. It does not include wastewater treatment lagoons and constructed wetlands for wastewater treatment.
9. Operating location as defined in 10 CSR 20-2.010 is all contiguous lands owned, operated or controlled by one (1) person or by two (2) or more persons jointly or as tenants in common.
10. Plant Available Nitrogen (PAN) is the nitrogen that will be available to plants during the growing seasons after biosolids application.
11. Public contact site is land with a high potential for contact by the public. This includes, but is not limited to, public parks, ball fields, cemeteries, plant nurseries, turf farms, and golf courses.
12. Sludge is the solid, semisolid, or liquid residue removed during the treatment of wastewater. Sludge includes septage removed from septic tanks or equivalent facilities. Sludge does not include carbon coal byproducts (CCBs)
13. Sludge lagoon is part of a mechanical wastewater treatment facility. A sludge lagoon is an earthen basin that receives sludge that has been removed from a wastewater treatment facility. It does not include a wastewater treatment lagoon or sludge treatment units that are not a part of a mechanical wastewater treatment facility.
14. Septage is the material pumped from residential septic tanks and similar treatment works (with a design population of less than 150 people). The standard for biosolids from septage is different from other sludges.

SECTION C – MECHANICAL WASTEWATER TREATMENT FACILITIES

1. Sludge shall be routinely removed from wastewater treatment facilities and handled according to the permit facility description and sludge conditions of this permit.
2. The permittee shall operate the facility so that there is no sludge discharged to waters of the state.
3. Mechanical treatment plants shall have separate sludge storage compartments in accordance with 10 CSR 20, Chapter 8. Failure to remove sludge from these storage compartments on the required design schedule is a violation of this permit.

SECTION D – SLUDGE DISPOSED AT OTHER TREATMENT FACILITY OR CONTRACT HAULER

1. This section applies to permittees that haul sludge to another treatment facility for disposal or use contract haulers to remove and dispose of sludge.
2. Permittees that use contract haulers are responsible for compliance with all the terms of this permit including final disposal, unless the hauler has a separate permit for sludge or biosolids disposal issued by the Department; or the hauler transports the sludge to another permitted treatment facility.
3. Haulers who land apply septage must obtain a state permit.
4. Testing of sludge, other than total solids content, is not required if sludge is hauled to a municipal wastewater treatment facility or other permitted wastewater treatment facility, unless it is required by the accepting facility.

SECTION E – INCINERATION OF SLUDGE

1. Sludge incineration facilities shall comply with the requirements of 40 CFR 503 Subpart E; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
2. Permittee may be authorized under the facility description of this permit to store incineration ash in lagoons or ash ponds. This permit does not authorize the disposal of incineration ash. Incineration ash shall be disposed in accordance with 10 CSR 80; or if the ash is determined to be hazardous with 10 CSR 25.
3. In addition to normal sludge monitoring, incineration facilities shall report the following as part of the annual report, quantity of sludge incinerated, quantity of ash generated, quantity of ash stored, and ash used or disposal method, quantity, and location. Permittee shall also provide the name of the disposal facility and the applicable permit number.

SECTION F – SURFACE DISPOSAL SITES AND SLUDGE LAGOONS

1. Surface disposal sites of domestic facilities shall comply with the requirements in 40 CFR 503 Subpart C; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
2. Sludge storage lagoons are temporary facilities and are not required to obtain a permit as a solid waste management facility under 10 CSR 80. In order to maintain sludge storage lagoons as storage facilities, accumulated sludge must be removed routinely, but not less than once every two years unless an alternate schedule is approved in the permit. The amount of sludge removed will be dependent on sludge generation and accumulation in the facility. Enough sludge must be removed to maintain adequate storage capacity in the facility.
 - a. In order to avoid damage to the lagoon seal during cleaning, the permittee may leave a layer of sludge on the bottom of the lagoon, upon prior approval of the Department; or
 - b. Permittee shall close the lagoon in accordance with Section H.

SECTION G – LAND APPLICATION

1. The permittee shall not land apply sludge or biosolids unless land application is authorized in the facility description or the special conditions of the issued NPDES permit.
2. Land application sites within a 20 miles radius of the wastewater treatment facility are authorized under this permit when biosolids are applied for beneficial use in accordance with these standard conditions unless otherwise specified in a site specific permit. If the permittee's land application site is greater than a 20 mile radius of the wastewater treatment facility, approval must be granted from the Department.
3. Land application shall not adversely affect a threatened or endangered species or its designated critical habitat.
4. Biosolids shall not be applied unless authorized in this permit or exempted under 10 CSR 20, Chapter 6.
 - a. This permit does not authorize the land application of domestic sludge except for when sludge meets the definition of biosolids.
 - b. This permit authorizes "Class A or B" biosolids derived from domestic wastewater and/or process water sludge to be land applied onto grass land, crop land, timber or other similar agricultural or silviculture lands at rates suitable for beneficial use as organic fertilizer and soil conditioner.
5. Public Contact Sites:

Permittees who wish to apply Class A biosolids to public contact sites must obtain approval from the Department after two years of proper operation with acceptable testing documentation that shows the biosolids meet Class A criteria. A shorter length of testing will be allowed with prior approval from the Department. Authorization for land applications must be provided in the special conditions section of this permit or in a separate site specific permit.

 - a. After Class B biosolids have been land applied, public access must be restricted for 12 months.
 - b. Class B biosolids are only land applied to root crops, home gardens or vegetable crops whose edible parts will not be for human consumption.
6. Agricultural and Silvicultural Sites:

Septage – Based on Water Quality guide 422 (WQ422) published by the University of Missouri

- a. Haulers that land apply septage must obtain a state permit
- b. Do not apply more than 30,000 gallons of septage per acre per year.
- c. Septage tanks are designed to retain sludge for one to three years which will allow for a larger reduction in pathogens and vectors, as compared to other mechanical type treatment facilities.
- d. To meet Class B sludge requirements, maintain septage at 12 pH for at least thirty (30) minutes before land application. 50 pounds of hydrated lime shall be added to each 1,000 gallons of septage in order to meet pathogen and vector stabilization for septage biosolids applied to crops, pastures or timberland.
- e. Lime is to be added to the pump truck and not directly to the septic tanks, as lime would harm the beneficial bacteria of the septic tank.

Biosolids - Based on Water Quality guide 423, 424, and 425 (WQ423, WQ424, WQ425) published by the University of Missouri;

- a. Biosolids shall be monitored to determine the quality for regulated pollutants
- b. The number of samples taken is directly related to the amount of sludge produced by the facility (See Section I of these Standard Conditions). Report as dry weight unless otherwise specified in the site specific permit. Samples should be taken only during land application periods. When necessary, it is permissible to mix biosolids with lower concentrations of biosolids as well as other suitable Department approved material to reach the maximum concentration of pollutants allowed.
- c. Table 1 gives the maximum concentration allowable to protect water quality standards

TABLE 1

Biosolids ceiling concentration ¹	
Pollutant	Milligrams per kilogram dry weight
Arsenic	75
Cadmium	85
Copper	4,300
Lead	840
Mercury	57
Molybdenum	75
Nickel	420
Selenium	100
Zinc	7,500

¹ Land application is not allowed if the sludge concentration exceeds the maximum limits for any of these pollutants

- d. The low metal concentration biosolids has reduced requirements because of its higher quality and can safely be applied for 100 years or longer at typical agronomic loading rates. (See Table 2)

TABLE 2

Biosolids Low Metal Concentration ¹	
Pollutant	Milligrams per kilogram dry weight
Arsenic	41
Cadmium	39
Copper	1,500
Lead	300
Mercury	17
Nickel	420
Selenium	36
Zinc	2,800

¹ You may apply low metal biosolids without tracking cumulative metal limits, provided the cumulative application of biosolids does not exceed 500 dry tons per acre.

- e. Each pollutant in Table 3 has an annual and a total cumulative loading limit, based on the allowable pounds per acre for various soil categories.

TABLE 3

Pollutant	CEC 15+		CEC 5 to 15		CEC 0 to 5	
	Annual	Total ¹	Annual	Total ¹	Annual	Total ¹
Arsenic	1.8	36.0	1.8	36.0	1.8	36.0
Cadmium	1.7	35.0	0.9	9.0	0.4	4.5
Copper	66.0	1,335.0	25.0	250.0	12.0	125.0
Lead	13.0	267.0	13.0	267.0	13.0	133.0
Mercury	0.7	15.0	0.7	15.0	0.7	15.0
Nickel	19.0	347.0	19.0	250.0	12.0	125.0
Selenium	4.5	89.0	4.5	44.0	1.6	16.0
Zinc	124.0	2,492.0	50.0	500.0	25.0	250.0

¹ Total cumulative loading limits for soils with equal or greater than 6.0 pH (salt based test) or 6.5 pH (water based test)

TABLE 4 - Guidelines for land application of other trace substances ¹

Cumulative Loading	
Pollutant	Pounds per acre
Aluminum	4,000 ²
Beryllium	100
Cobalt	50
Fluoride	800
Manganese	500
Silver	200
Tin	1,000
Dioxin	(10 ppt in soil) ³
Other	⁴

¹ Design of land treatment systems for Industrial Waste, 1979. Michael Ray Overcash, North Carolina State University and Land Treatment of Municipal Wastewater, EPA 1981.)

² This applies for a soil with a pH between 6.0 and 7.0 (salt based test) or a pH between 6.5 to 7.5 (water based test). Case-by-case review is required for higher pH soils.

³ Total Dioxin Toxicity Equivalents (TEQ) in soils, based on a risk assessment under 40 CFR 744, May 1998.

⁴ Case by case review. Concentrations in sludge should not exceed the 95th percentile of the National Sewage Sludge Survey, EPA, January 2009.

Best Management Practices – Based on Water Quality guide 426 (WQ426) published by the University of Missouri

- a. Use best management practices when applying biosolids.
- b. Biosolids cannot discharge from the land application site
- c. Biosolid application is subject to the Missouri Department of Agriculture State Milk Board concerning grazing restrictions of lactating dairy cattle.
- d. Biosolid application must be in accordance with section 4 of the Endangered Species Act.
- e. Do not apply more than the agronomic rate of nitrogen needed.
- f. The applicator must document the Plant Available Nitrogen (PAN) loadings, available nitrogen in the soil, and crop removals unless the nitrogen content of the biosolids does not exceed 50,000 milligrams per kilogram of total nitrogen on a dry weight basis or biosolids application rate is less than two dry tons per acre per year.
 - i. PAN can be determined as follows and is in accordance with WQ426
(Nitrate + nitrite nitrogen) + (organic nitrogen x 0.2) + (ammonia nitrogen x volatilization factor¹).
¹ Volatilization factor is 0.7 for surface application and 1 for subsurface application.
- g. Buffer zones are as follows:
 - i. 300 feet of a water supply well, sinkhole, lake, pond, water supply reservoir or water supply intake in a stream;
 - ii. 300 feet of a losing stream, no discharge stream, stream stretches designated for whole body contact recreation, wild and scenic rivers, Ozark National Scenic Riverways or outstanding state resource waters as listed in the Water Quality Standards, 10 CSR 20-7.031;
 - iii. 150 feet if dwellings;
 - iv. 100 feet of wetlands or permanent flowing streams;
 - v. 50 feet of a property line or other waters of the state, including intermittent flowing streams.
- h. Slope limitation for application sites are as follows:
 - i. A slope 0 to 6 percent has no rate limitation
 - ii. Applied to a slope 7 to 12 percent, the applicator may apply biosolids when soil conservation practices are used to meet the minimum erosion levels
 - iii. Slopes > 12 percent, apply biosolids only when grass is vegetated and maintained with at least 80 percent ground cover at a rate of two dry tons per acre per year or less.
- i. No biosolids may be land applied in an area that it is reasonably certain that pollutants will be transported into waters of the state.
- j. Do not apply biosolids to sites with soil that is snow covered, frozen or saturated with liquid without prior approval by the Department.
- k. Biosolids / sludge applicators must keep detailed records up to five years.

SECTION H – CLOSURE REQUIREMENTS

1. This section applies to all wastewater facilities (mechanical, industrial, and lagoons) and sludge or biosolids storage and treatment facilities and incineration ash ponds. It does not apply to land application sites.
2. Permittees of a domestic wastewater facility who plan to cease operation must obtain Department approval of a closure plan which addresses proper removal and disposal of all residues, including sludge, biosolids. Mechanical plants, sludge lagoons, ash ponds and other storage structures must obtain approval of a closure plan from the Department. Permittee must maintain this permit until the facility is closed in accordance with the approved closure plan per 10 CSR 20 – 6. 010 and 10 CSR 20 – 6.015.
3. Residuals that are left in place during closure of a lagoon or earthen structure or ash pond shall not exceed the agricultural loading rates as follows:
 - a. Residuals shall meet the monitoring and land application limits for agricultural rates as referenced in Section H of these standard conditions.
 - b. If a wastewater treatment lagoon has been in operation for 15 years or more without sludge removal, the sludge in the lagoon qualifies as a Class B biosolids with respect to pathogens due to anaerobic digestion, and testing for fecal coliform is not required. For other lagoons, testing for fecal coliform is required to show compliance with Class B biosolids limitations. In order to reach Class B biosolids requirements, fecal coliform must be less than 2,000,000 colony forming units or 2,000,000 most probable number. All fecal samples must be presented as geometric mean per gram.
 - c. The allowable nitrogen loading that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. For a grass cover crop, the allowable PAN is 300 pounds/acre.
 - i. PAN can be determined as follows:
(Nitrate + nitrite nitrogen) + (organic nitrogen x 0.2) + (ammonia nitrogen x volatilization factor¹).
¹ Volatilization factor is 0.7 for surface application and 1 for subsurface application.
4. When closing a domestic wastewater treatment lagoon with a design treatment capacity equal or less than 150 persons, the residuals are considered “septage” under the similar treatment works definition. See Section B of these standard conditions. Under the septage category, residuals may be left in place as follows:
 - a. Testing for metals or fecal coliform is not required
 - b. If the wastewater treatment lagoon has been in use for less than 15 years, mix lime with the sludge at a rate of 50 pounds of hydrated lime per 1000 gallons (134 cubic feet) of sludge.
 - c. The amount of sludge that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. 100 dry tons/acre of sludge may be left in the basin without testing for nitrogen. If 100 dry tons/acre or more will be left in the lagoon, test for nitrogen and determine the PAN using the calculation above. Allowable PAN loading is 300 pounds/acre.
5. Residuals left within the domestic lagoon shall be mixed with soil on at least a 1 to 1 ratio, the lagoon berm shall be demolished, and the site shall be graded and contain $\geq 70\%$ vegetative density over 100% of the site so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
6. Lagoons and/or earthen structure and/or ash pond closure activities shall obtain a storm water permit for land disturbance activities that equal or exceed one acre in accordance with 10 CSR 20-6.200
7. When closing a mechanical wastewater and/or industrial process wastewater plant; all sludge must be cleaned out and disposed of in accordance with the Department approved closure plan before the permit for the facility can be terminated.
 - a. Land must be stabilized which includes any grading, alternate use or fate upon approval by the Department, remediation, or other work that exposes sediment to stormwater per 10 CSR 20-6.200. The site shall be graded and contain $\geq 70\%$ vegetative density over 100% of the site, so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
 - b. Per 10 CSR 20-6.015(4)(B)6, Hazardous Waste shall not be land applied or disposed during industrial and mechanical plant closures unless in accordance with Missouri Hazardous Waste Management Law and Regulations under 10 CSR 25.
 - c. After demolition of the mechanical plant / industrial plant, the site must only contain clean fill defined in RSMo 260.200 (5) as uncontaminated soil, rock, sand, gravel, concrete, asphaltic concrete, cinderblocks, brick, minimal amounts of wood and metal, and inert solids as approved by rule or policy of the Department for fill or other beneficial use. Other solid wastes must be removed.
8. If sludge from the domestic lagoon or mechanical treatment plant exceeds agricultural rates under Section G and/or H, a landfill permit or solid waste disposal permit must be obtained if the permittee chooses to seek authorization for on-site sludge disposal under the Missouri Solid Waste Management Law and regulations per 10 CSR 80, and the permittee must comply with the surface disposal requirements under 40 CFR 503, Subpart C.

SECTION I – MONITORING FREQUENCY

1. At a minimum, sludge or biosolids shall be tested for volume and percent total solids on a frequency that will accurately represent sludge quantities produced and disposed. Please see the table below.

TABLE 5

Design Sludge Production (dry tons per year)	Monitoring Frequency (See Notes 1 and 2)			
	Metals, Pathogens and Vectors	Nitrogen TKN ¹	Nitrogen PAN ²	Priority Pollutants and TCLP ³
0 to 100	1 per year	1 per year	1 per month	1 per year
101 to 200	biannual	biannual	1 per month	1 per year
201 to 1,000	quarterly	quarterly	1 per month	1 per year
1,001 to 10,000	1 per month	1 per month	1 per week	-- ⁴
10,001 +	1 per week	1 per week	1 per day	-- ⁴

¹ Test total Kjeldahl nitrogen, if biosolids application is 2 dry tons per acre per year or less

² Calculate plant available nitrogen, nitrogen content of the biosolids is greater than 50,000 milligrams per kilogram of total nitrogen on dry weight basis or if the biosolids application rate is greater than two dry tons per acre per year.

³ Priority pollutants (40 CFR 122.21, Appendix D, Tables II and III) and toxicity characteristic leaching procedure (40 CFR 261.24) is required only for permit holders that must have a pre-treatment program.

⁴ One sample for each 1,000 dry tons of sludge.

Note 1: Total solids: A grab sample of sludge shall be tested one per day during land application periods for percent total solids.

This data shall be used to calculate the dry tons of sludge applied per acre.

Note 2: Total Phosphorus: Total phosphorus and total potassium shall be tested at the same monitoring frequency as metals.

2. If you own a wastewater treatment lagoon or sludge lagoon that is cleaned out once a year or less, you may choose to sample only when the sludge is removed or the lagoon is closed. Test one composite sample for each 100 dry tons of sludge or biosolids removed from the lagoon during the year within the lagoon at closing. Composite sample must represent various areas at one-foot depth.
3. Additional testing may be required in the special conditions or other sections of the permit. Permittees receiving industrial wastewater may be required to conduct additional testing upon request from the Department.
4. At this time, the Department recommends monitoring requirements shall be performed in accordance with, "POTW Sludge Sampling and Analysis Guidance Document," United States Environmental Protection Agency, August 1989, and the subsequent revisions.

SECTION J – RECORD KEEPING AND REPORTING REQUIREMENTS

1. The permittee shall maintain records on file at the facility for at least five years for the items listed in these standard conditions and any additional items in the Special Conditions section of this permit. This shall include dates when the sludge facility is checked for proper operation, records of maintenance and repairs and other relevant information.
2. Reporting period
 - a. By January 28th of each year, an annual report shall be submitted for the previous calendar year period for all mechanical wastewater treatment facilities, sludge lagoons, and sludge or biosolids disposal facilities.
 - b. Permittees with wastewater treatment lagoons shall submit the above annual report only when sludge or biosolids are removed from the lagoon during the report period or when the lagoon is closed.
3. Report Forms. The annual report shall be submitted on report forms provided by the Department or equivalent forms approved by the Department.
4. Reports shall be submitted as follows:

Major facilities (those serving 10,000 persons or 1 million gallons per day) shall report to both the Department and EPA. Other facilities need to report only to the Department. Reports shall be submitted to the addresses listed as follows:

DNR regional office listed in your permit
 (see cover letter of permit)
 ATTN: Sludge Coordinator

EPA Region VII
 Water Compliance Branch (WACM)
 Sludge Coordinator
 11201 Renner Blvd.
 Lenexa, KS 66219

5. Annual report contents. The annual report shall include the following:
- a. Sludge and biosolids testing performed. Include a copy or summary of all test results, even if not required by the permit.
 - b. Sludge or biosolids quantity shall be reported as dry tons for quantity generated by the wastewater treatment facility, the quantity stored on site at the end of the year, and the quantity used or disposed.
 - c. Gallons and % solids data used to calculate the dry ton amounts.
 - d. Description of any unusual operating conditions.
 - e. Final disposal method, dates, and location, and person responsible for hauling and disposal.
 - i. This must include the name, address for the hauler and sludge facility. If hauled to a municipal wastewater treatment facility, sanitary landfill, or other approved treatment facility, give the name of that facility.
 - ii. Include a description of the type of hauling equipment used and the capacity in tons, gallons, or cubic feet.
 - f. Contract Hauler Activities:

If contract hauler, provide a copy of a signed contract from the contractor. Permittee shall require the contractor to supply information required under this permit for which the contractor is responsible. The permittee shall submit a signed statement from the contractor that he has complied with the standards contained in this permit, unless the contract hauler has a separate sludge or biosolids use permit.
 - g. Land Application Sites:
 - i. Report the location of each application site, the annual and cumulative dry tons/acre for each site, and the landowners name and address. The location for each spreading site shall be given as a legal description for nearest ¼, ¼, Section, Township, Range, and county, or UTM coordinates. If nitrogen content of the biosolids is greater than 50,000 milligrams per kilogram of total nitrogen on dry weight basis or if the biosolids application rate is greater than two dry tons per acre per year, report biosolids nitrogen results, PAN in pounds/acre crop nitrogen requirement.
 - ii. If the “Low Metals” criteria are exceeded, report the annual and cumulative pollutant loading rates in pounds per acre for each applicable pollutant, and report the percent of cumulative pollutant loading which has been reached at each site.
 - iii. Report the method used for compliance with pathogen and vector attraction requirements.
 - iv. Report soil test results for pH, CEC, and phosphorus. If none was tested during the year, report the last date when tested and results.

C295540-01
5-457-08
SG-497

AP14077
CPSE00664



MISSOURI DEPARTMENT OF NATURAL RESOURCES
WATER PROTECTION PROGRAM, WATER POLLUTION BRANCH
FORM B - APPLICATION FOR CONSTRUCTION OR OPERATING PERMIT FOR FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WASTE (≤100,000 gallons per day) UNDER MISSOURI CLEAN WATER LAW

FOR AGENCY USE ONLY	
CHECK NUMBER	1105
DATE RECEIVED	12/6/12
FEE SUBMITTED	\$750.00

NOTE ► PLEASE READ THE ACCOMPANYING INSTRUCTIONS BEFORE COMPLETING THIS FORM!

1. This application is for:

- An operating permit and antidegradation review public notice.
- A construction permit following an appropriate operating permit and antidegradation review public notice.
- A construction permit and a concurrent operating permit and antidegradation review public notice.
- A construction permit (submitted before Aug. 30, 2008 or antidegradation review is not required).
- An operating permit for a new or unpermitted facility. Construction Permit # _____
- An operating permit renewal: Permit #MO-_____ Expiration Date _____
- An operating permit modification: Permit #MO-_____ Reason: _____

1.1 Is this a Federal/State Funded Project? YES NO Funding Agency/Project #: _____

1.2 Is the appropriate fee included with the application (See instructions for appropriate fee)? YES NO

2. FACILITY (Outfall 1 of 1)

NAME Sunrise Beach Phase 1 WWTF		TELEPHONE WITH AREA CODE (573) 374-8782	
ADDRESS (PHYSICAL) Hwy. 5 & Kula Bay Dr.	CITY Sunrise Beach	STATE MO	ZIP CODE 65079

2.1 LEGAL DESCRIPTION: ¼, SW ¼, SE ¼, Sec. 9, T 39, R 17 Camd County

2.2 UTM Coordinates Easting (X): 38.1316 Northing (Y): 92.7928
For Universal Transverse Mercator (UTM), Zone 15 North referenced to North American Datum 1983 (NAD83)

2.3 Name of receiving stream:

3. OWNER

NAME Village of Sunrise Beach		E-MAIL ADDRESS citysb@yahoo.com	TELEPHONE WITH AREA CODE (573) 374-8782
ADDRESS 16537 MO Hwy 5	CITY Sunrise Beach	STATE MO	ZIP CODE 65079

3.1 Request review of draft permit prior to Public Notice? YES NO

4. CONTINUING AUTHORITY: Permanent organization which will serve as the continuing authority for the operation, maintenance and modernization of the facility.

NAME Same as Owner		TELEPHONE WITH AREA CODE	
ADDRESS	CITY	STATE	ZIP CODE

5. OPERATOR

NAME TBD	CERTIFICATE NUMBER	TELEPHONE WITH AREA CODE
-------------	--------------------	--------------------------

6. FACILITY CONTACT

NAME Curt Mooney	TITLE Chairman	TELEPHONE WITH AREA CODE (573) 480-0608
---------------------	-------------------	--

7.0 ADDITIONAL FACILITY INFORMATION

7.1 Description of facilities (Attach additional sheet if required). Attach a 1" = 2,000' scale U.S. Geological Survey topographic map showing location of all outfalls and downstream landowners. (See Item 9.)

7.2 Facility SIC code: 7011; Discharge SIC code: 4952; Facility NAICS code: _____; Discharge NAICS code: _____.

7.3 Number of people presently connected or population equivalent (P.E.) _____ Design P.E. _____
 Number of units presently connected: Homes _____ Trailers _____ Apartments _____ Other _____
 Design flow for this outfall: 49640 Total design flow for the facility: 50000 Actual flow for this outfall: _____
 Commercial Establishment: Daily number of employees working _____ Daily number of customers/guests _____

7.4 Length of pipe in the sewer collection system? TBD feet/miles (Please denote which unit is appropriate.)

7.5 Does any bypassing occur in the collection system or at the treatment facility? Yes No (If yes, attach explanation.)

7.6 Does significant infiltration occur in the collection system? Yes No (If yes, attach explanation and proposed repair.)

7.7 Is industrial waste discharged to the facility identified in Item 2? Yes No (If yes, see instructions.)

7.8 Will the discharge be continuous through the year? Yes No
 a. Discharge will occur during the following months: All
 b. How many days of the week will the discharge occur? 7

7.9 Is wastewater land applied? Yes No (If yes, attach Form I.)

7.10 Will chlorine be added to the effluent? Yes No
 a. If chlorine is added, what is the resulting residual? _____ µg/l (micrograms per liter)


7.11 Does this facility discharge to a losing stream or sinkhole? Yes No


7.12 Attach a flow chart showing all influents, treatment facilities and outfalls.

7.13 Has a waste load allocation study been completed for this facility? Yes No

7.14 List all permit violations, including effluent limit exceedances in the last five years. Attach a separate sheet if necessary.
 If none, write none. None

RECEIVED
DEC 6 2012
WATER PROTECTION PROGRAM

8. SLUDGE HANDLING, USE AND DISPOSAL			
8.1	Is the sludge a hazardous waste as defined by 10 CSR 25? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
8.2	Sludge Production, including sludge received from others: _____ Design Dry Tons/Year _____ Actual Dry Tons/Year		
8.3	Capacity of sludge holding structures: Sludge storage provided: <u>1070</u> cubic feet; _____ days of storage; _____ average percent solids of sludge; <input type="checkbox"/> No sludge storage is provided.		
8.4	Type of Storage:	<input type="checkbox"/> Holding tank <input type="checkbox"/> Building <input checked="" type="checkbox"/> Basin <input type="checkbox"/> Other (Please describe) _____ <input type="checkbox"/> Concrete Pad	
8.5	Sludge Treatment:	<input type="checkbox"/> Anaerobic Digester <input type="checkbox"/> Lagoon <input type="checkbox"/> Composting <input checked="" type="checkbox"/> Storage Tank <input type="checkbox"/> Aerobic Digester <input type="checkbox"/> Other (Attach description) <input type="checkbox"/> Lime Stabilization <input type="checkbox"/> Air or Heat Drying	
8.6	Sludge Use or Disposal:	<input type="checkbox"/> Land Application <input type="checkbox"/> Surface Disposal (Sludge Disposal Lagoon, Sludge held for more than two years) <input checked="" type="checkbox"/> Contract Hauler <input type="checkbox"/> Incineration <input type="checkbox"/> Hauled to Another Treatment Facility <input type="checkbox"/> Sludge Retained in Wastewater treatment lagoon <input type="checkbox"/> Solid Waste Landfill <input type="checkbox"/> Other _____ Attach explanation sheet.	
8.7	PERSON RESPONSIBLE FOR HAULING SLUDGE TO DISPOSAL FACILITY <input type="checkbox"/> By Applicant <input checked="" type="checkbox"/> By Others (complete below)		
NAME TBD			
ADDRESS		CITY	STATE ZIP CODE
CONTACT PERSON		TELEPHONE WITH AREA CODE	PERMIT NO. MO-
8.8 SLUDGE USE OR DISPOSAL FACILITY			
<input type="checkbox"/> By Applicant <input checked="" type="checkbox"/> By Others (Please complete below.)			
NAME TBD			
ADDRESS		CITY	STATE ZIP CODE
CONTACT PERSON		TELEPHONE WITH AREA CODE	PERMIT NO. MO-
8.9	Does the sludge or biosolids disposal comply with federal sludge regulations under 40 CFR 503? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Please attach explanation)		
9. DOWNSTREAM LANDOWNER (S). ATTACH ADDITIONAL SHEETS AS NECESSARY. SEE INSTRUCTIONS.			
NAME Willie & Gayla Beisswenger			
ADDRESS 6929 Arthur Ave		CITY St. Louis	STATE ZIP CODE MO 63139
10. DRINKING WATER SUPPLY INFORMATION			
10.1	WHAT IS THE SOURCE OF YOUR DRINKING WATER SUPPLY: A. Public supply (municipal or water district water) <u>X</u> If public, please give name of the public supply <u>Sunrise Bea</u> B. Private well _____ C. Surface water (lake, pond or stream) _____		
10.2	Does your drinking water source serve at least 25 people at least 60 days per year (not necessarily consecutive days)? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
10.3	Does your supply serve housing which is occupied year round by the same people? This does not include housing which is occupied seasonally? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
11.	I certify that I am familiar with the information contained in the application, that to the best of my knowledge and belief such information is true, complete and accurate, and if granted this permit, I agree to abide by the Missouri Clean Water Law and all rules, regulations, orders and decisions, subject to any legitimate appeal available to applicant under the Missouri Clean Water Law.		
NAME AND OFFICIAL TITLE (TYPE OR PRINT) Curt Mooney, Village of Sunrise Beach Chairman		TELEPHONE WITH AREA CODE (573) 374-8782	
SIGNATURE 		DATE SIGNED 11/29/12	



1" = 2000'
USGS MAP

11/29/2012
Designed by: AutoCAD Civil 3d
Surveyed by:
Checked by: JW Drawn by: JW
Project #: 750067 Sheet Size: 8.5x11
File: EXHIBITS.DWG

PHASE 1 SANITARY SEWER IMPROVEMENTS
SUNRISE BEACH, MISSOURI



SSS Engineering
Schultz & Summers
www.schultzandsummers.com

Southeast Missouri Office - (573) 686-0806
Lake of the Ozarks Office - (573) 365-2003
Branson Office - (417) 337-8820
New Orleans, LA Office - (504) 467-6009

Civil Engineering - Land Surveying - Materials Testing

INFLUENT
RAW
SEWAGE

FLOW
EQUILIZATION
TANK W/SCREEN

MECHANICAL
PACKAGE PLANT

AERATION
TANK

SLUDGE
RETURN

CLARIFIER
TANK

SLUDGE
HOLDING

WASTE
SLUDGE

UV
DISINFECTION
STRUCTURE

FLOW MEASURING
DEVICE &
SAMPLING STATION

TREATED
EFFLUENT
DISCHARGE

SHEET

WWTF FLOW DIAGRAM
SUNRISE BEACH

08-02-12 AutoCAD Civil 3d
Designed by: JWW Surveyed by: N/A
Checked by: JWW Drawn by: JWW
Project #: 750067 Sheet Size: 8.5x11

File: FLOW DIAGRAM.DWG

SUNRISE BEACH WWTF
FLOW DIAGRAM
SUNRISE BEACH, MO



Southeast Missouri Office - (573) 686-0806
Lake of the Ozarks Office - (573) 365-2003
Branson, MO Office - (417) 337-8820
New Orleans, LA Office - (504) 467-6009
www.schultzandsummers.com

Civil Engineering - Land Surveying - Materials Testing