Form No. 10-300 (Rev. 10-74)

PH0663450

DATA SHEET

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED FEB 21 1978
DATE ENTERED MAY 22 1978

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC: Row House Building

AND/OR COMMON: Row House Building

2 LOCATION

STREET & NUMBER: 1-3-5-7 East 34th Street, 3401 Main Street — NOT FOR PUBLICATION

CITY, TOWN: Kansas City — VICINITY OF

CONGRESSIONAL DISTRICT: #5 Hon. Richard Bolling

STATE: Missouri — CODE: 29

COUNTY: Jackson — CODE: 095

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE	
__DISTRICT	__PUBLIC	__OCCUPIED	__AGRICULTURE	__MUSEUM
X BUILDING(S)	X PRIVATE	X UNOCCUPIED	X COMMERCIAL	__PARK
__STRUCTURE	__BOTH	__WORK IN PROGRESS	__EDUCATIONAL	__PRIVATE RESIDENCE
__SITE	PUBLIC ACQUISITION	ACCESSIBLE	__ENTERTAINMENT	__RELIGIOUS
__OBJECT	__IN PROCESS	X YES: RESTRICTED	__GOVERNMENT	__SCIENTIFIC
	__BEING CONSIDERED	__YES: UNRESTRICTED	__INDUSTRIAL	__TRANSPORTATION
		__NO	__MILITARY	__OTHER:

4 OWNER OF PROPERTY

NAME: Mr. James N. Hueser

STREET & NUMBER: 401 Keene Street

CITY, TOWN: Columbia — VICINITY OF

STATE: Missouri 65201

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: Office of Recorder of Deeds, Jackson County Courthouse, Kansas City Annex

STREET & NUMBER: 415 East 12th Street

CITY, TOWN: Kansas City

STATE: Missouri 64106

6 REPRESENTATION IN EXISTING SURVEYS

TITLE: Landmarks Commission of Kansas City, Missouri Survey

DATE: 1976 — __FEDERAL __STATE __COUNTY X LOCAL

DEPOSITORY FOR SURVEY RECORDS: 414 East 12th Street

CITY, TOWN: Kansas City

STATE: Missouri 64106

RECEIVED
FEB 21 1978
NATIONAL REGISTER

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
_EXCELLENT	_DETERIORATED	_UNALTERED	X ORIGINAL SITE
_GOOD	_RUINS	X ALTERED	_MOVED DATE
X FAIR	_UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Row House Building, 1-3-5-7 East 34th Street and 3401 Main Street, Kansas City, Missouri, is a three-story (including the ground story) red pressed brick, wood and coursed stone, multi-family residential structure of Queen Anne design with Eastlake decorative elements. Built in 1887-1888, the main facade of the four residential units at Nos. 1-7 East 34th Street faces north, while the main facade of the single residential unit at 3401 Main Street faces west. Because of the slope of the land along East 34th Street, the ground story on the north facade is approximately four feet below grade.[1] Originally the design of the Row House Building was L-shape with seven row houses located along Main Street, and four row houses along East 34th Street.[2] The L-shape placement of the buildings created a small courtyard in the rear of the buildings.[3]

EXTERIOR

Over-all dimensions

Asymmetrical in design and plan, the Row House Building contains a projecting three-story semi-octagonal bay on the north (main) facade of No. 7 East 34th Street; a one-story wooden rectangular bay located on the second story of the north facade of Nos. 5 and 3 East 34th Street; a three-story semi-cylindrical bay placed on the north facade of No. 1 East 34th Street; and a three-quarters projecting bay placed at the northwest corner of the west facade at 3401 Main Street. The Row House Building, inclusive of the south facade porches and additions measures at its maximum dimension 72.5'x111'. The total footage of interior space, exclusive of the rear porches and additions, is approximately 9,400 square feet.

Construction materials and colors

A fieldstone foundation supports walls of pressed red brick in common bond. Course limestone is used for string coursing (between the ground story and second story, and the second and third story) and lugsills. Decorative features are made of white vermiculated limestone and wood trim painted white and green. The roof, porches, and single run staircases are of wood frame construction.

Openings

Windows. Fenestration on the north (main) facade of Nos. 1-7 East 34th Street and west (main) facade of 3401 Main Street consists of one-over-one light, double hung sash rectangular windows placed in segmental arched openings. Above each window is a wooden sash decorated with an incised floral motif. Radiating brick voussoirs accented with stone skewbacks trim the windows.

Located on the second story of the north facade at No. 5 and No. 1 East 34th Street are rectangular wooden bays. Window openings in these bays are one-over-one light, double hung sash windows in rectangular openings. Queen Anne windows with single light transoms above are located on the ground story of the main facade of Nos. 1 and 5 East 34th Street and are trimmed with vermiculated stone quoining.

RECEIVED
FEB 21 1978
NATIONAL REGISTER

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
__PREHISTORIC	__ARCHEOLOGY-PREHISTORIC	__COMMUNITY PLANNING	__LANDSCAPE ARCHITECTURE	__RELIGION	
__1400-1499	__ARCHEOLOGY-HISTORIC	__CONSERVATION	__LAW	__SCIENCE	
__1500-1599	__AGRICULTURE	__ECONOMICS	__LITERATURE	__SCULPTURE	
__1600-1699	X ARCHITECTURE	__EDUCATION	__MILITARY	__SOCIAL/HUMANITARIAN	
__1700-1799	__ART	__ENGINEERING	__MUSIC	__THEATER	
X 1800-1899	__COMMERCE	__EXPLORATION/SETTLEMENT	__PHILOSOPHY	__TRANSPORTATION	
__1900-	__COMMUNICATIONS	__INDUSTRY	__POLITICS/GOVERNMENT	__OTHER (SPECIFY)	
		__INVENTION			

SPECIFIC DATES 1887-88 BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Row House Building at 1-3-5-7 East 34th Street and 3401 Main Street in the Westport district of Kansas City, Missouri, is significant as a rare surviving example of row house architecture in Kansas City. The Row House Building is further significant as a fine example of the Queen Anne style design, incorporating some Eastlake style elements. The irregularity of its plan, its variety of texture and its use of many bays and roof shapes attest to this.[1]

Row house buildings of this design were being constructed during the building boom of the late 1880s in Kansas City. Some examples of these include: Quinlan Flats, northeast corner of 8th Street and Highland; Garland Block, 1815-31 East 7th Street; and Donnelly Flats, southeast corner of 8th and Locust Streets.[2] Unfortunately, all of these structures have been demolished.

Information about the original designer/architect of the Row House Building is lacking from the records, but may be uncovered in future historical research. The Row House Building, located on the southeast corner of East 34th Street and Main Street, was built in 1888 for George W. Craig.[3] In 1887-88 George W. Craig was a laborer for the Metropolitan Streetcar Railway Company.[4] It is presumed that Craig had the Row House Building constructed, and resided in Kansas City during the years of its transaction and development. It is highly unlikely that a laborer for a streetcar railway company would have the financial means to build a structure of this size. Therefore, it is also presumed that Craig was a representative for an out-of-state individual or firm. A major building boom was occurring in Kansas City and Westport during the construction of the Row House Building and it was not uncommon at this time for out-of-town speculators to invest in property in Kansas City and its environs, such as Westport.

The Row House Building at its time of construction was located in what was then Westport, Missouri, and formed an integral part of a residential area that was located outside of the Kansas City city limits, similar to present-day suburbs. Westport became part of Kansas City, Missouri, when it was annexed in 1899.[5]

The survey of Missouri's historic sites is based on the selection of sites as they relate to theme studies in Missouri history as outlined in "Missouri's State Historic Preservation Plan." The Row House Building is therefore, being nominated to the National Register of Historic Places as an example of the theme of "Architecture."

9 MAJOR BIBLIOGRAPHICAL REFERENCES

1. Haskell, Henry C., Jr. and Fowler, Richard B. City of the Future A Narrative History of Kansas City, 1850-1950. Kansas City, Mo.: Frank Green Publishing Co. Inc., 1950.

2. Hopkins, G.M., C.E. A Complete Set of Surveys and Plats of Properties of Kansas City, Missouri. Philadelphia, Pa." G.M. Hopkins, C.E. 1891.

continued:

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY .17 acres

UTM REFERENCES

	ZONE	EASTING	NORTHING		ZONE	EASTING	NORTHING
A	15	362870	4325040	B			
C				D			

VERBAL BOUNDARY DESCRIPTION

E 19.29 ft. of Lots 5 & 6 Also undivided 1 11 Int.
In court adj. Halsey & Dudley's add.

Halsey & Dudley's add. E. 100.71 ft. of W 110.71 ft. lots 5 & 6 Exc. S 3.95 ft. of E 73 ft. of W 83 ft Lot 6 & Inc. 6/11 Int. in private aly A.K.A. The Court.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
STATE	CODE	COUNTY	CODE

11 FORM PREPARED BY

NAME / TITLE
Linda F. Becker, Administrative Assistant

ORGANIZATION
Landmarks Commission

DATE
October 25, 1977

STREET & NUMBER
414 East 12th Street, City Hall, 26th Floor E.,

TELEPHONE
816 274-2555

CITY OR TOWN
Kansas City

STATE
Missouri 64106

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL ___ STATE ___ LOCAL X

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE Robert L. Ironsead

TITLE Director, Department of Natural Resources and State Historic Preservation Officer

DATE February 8, 1978

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

[signature]

DATE 5 22 78

~~DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION~~ KEEPER OF THE NATIONAL REGISTER

ATTEST: Catherine H. Cole

DATE 5 29 78

~~KEEPER OF THE NATIONAL REGISTER~~

GPO 892-459

Form No 10 300a
(Rev 10 74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED FEB 21 1978
DATE ENTERED

ROW HOUSE BUILDING

CONTINUATION SHEET ITEM NUMBER 7 PAGE 1

The only window openings on the east facade are located on the 1½ story addition behind No. 7 East 34th Street. They are single light windows in a square frame with metal bars running horizontally and vertically in front of the light.

The fenestration on the south facade (rear) of Nos. 1-7 East 34th Street consists of one-over-one light, double hung sash rectangular windows with decorative sashes above, placed in segmental arched openings and trimmed with radiating brick voussoirs. The south facade of 3401 Main Street has no window openings.

Doorways. Each row house has three entrances on the main facade and are as follows:

No. 7 East 34th Street. The main entrance, a wooden double panel door, with a single light in the upper panel, is located at the west end of the first story of the north facade. Above the door is a single light transom. The entire doorway is placed in a segmental arched opening. A twelve light paneled door is located in front of the main doorway. A double panel wooden door in a rectangular frame, with a single light in the upper panel, is located at the ground level, to the east of the main staircase on the north facade. An indentical door is located on the ground level directly behind the staircase and directly below the main entrance.

No. 5 East 34th Street. The main entrance is identical in location and style with that of No. 7. The transom light however, has been filled in with wood and a paneled screen door has been placed in front of the main entrance. The doorways at the ground level are identical with those found at No. 7. Their locations are also similar. The entrance east of the staircase, however, is flush with the ground level wall rather than being flush with the staircase as in No. 7.

No. 3 East 34th Street. The main entrance located in the same place as Nos. 5 and 7, is a two panel wooden door with the original Queen Anne sash window in the upper panel. The doors located at ground level are identical in design with those at No. 7. One is located in the center of the semi-cylindrical bay which is to the east of the stairs and the other is located behind the staircase and directly below the main entrance, and has a paneled screen door in front of it.

No. 1 East 34th Street. The main entrance is a two paneled wooden door with a sealed upper panel, which at one time was a Queen Anne sash window. The ground level doors are identical in style and location with No. 7. They, however, have screen doors in front.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED FEB 21 1978
DATE ENTERED

ROW HOUSE BUILDING

3401 Main Street. The main entrance located on the first story is placed on the south end of the west facade. There are two doorways located on the ground story, one located on the three-quarter cylindrical bay facing northwest and one located directly below the main entrance. All doorways on the west facade have been sealed.

The rear entrances, located on the south facade, are two panel wooden doors, with a single light in the upper panel and placed in segmental arch frames. A single light transom is located above the doorway. The doorways are located at the extreme east end of each unit on each of the three floors, with the exception of No. 7 and 3401 Main Street. No. 7 East 34th Street has a five panel wooden door with a two panel screen door in front located on the first story of the rear addition. There is also a twelve panel wooden garage door on the ground story of the same addition. 3401 Main Street has no rear doorways.

Porches

Porches are situated on the north (main) facades of Nos. 1-7 East 34th Street and on the south (rear) facades of Nos. 1-5 East 34th Street.

Porches on the main facades are as follows:

No. 7 East 34th Street. The one-story main entrance porch has a shed roof supported by metal posts. A single-run wooden staircase with metal balustrades, located on the west end of the porch provides access to the porch.

No. 5 East 34th Street. A one-story, two bay wide porch protects the main entrance. Lathe-turned posts with brackets support a shed roof, which connects to the shed roof of No. 7. A gabled roof with a fan design in the pediment is located over the main entrance. A lathe-turned balustrade with lathe-turned balusters runs along the north side of the porch. On the west end of the porch a single run wooden staircase provides access to the porch.

Nos. 3 and 1 East 34th Street. A gabled roof porch, with a fan design in the pediment is located over each of the main entrances. The two structures share a shed roof porch which connects to the gabled roofs over the entrances. The roof is supported by lathe-turned posts and brackets. A lathe-turned balustrade with balusters runs along the north side of the porch of No. 3 while a plain 2"x4" bannister runs along the north and west side of the porch at No. 1. Access to the shared porch is provided by a single run wooden staircase located directly in front of the main entrance of No. 3.

The floor of all the porches is wood and provides the roof for the veranda found directly below the main porches at the ground story.

Form No 10-300a
(Rev 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED FEB 21 1978
DATE ENTERED MAY 22 1978

ROW HOUSE BUILDING

A three-story veranda with a shed roof supported by 2"x4" plain posts and balustrade runs along the rear (south) facade of Nos. 1-5 East 34th Street. A three-story single run wooden staircase situated at the east end of the facade provides access to the veranda.

Chimneys

Two small red brick chimney stacks are on the west common wall of each row house with the exception of 3401 Main Street. The chimney stacks which would have been on the south common wall of 3401 Main Street have been removed. On No. 7 East 34th Street the chimney stacks have been replaced by plain chimney pots.

Roofs

A flat roof of built-up asphalt covers most of the structure. The main facade, however, has shingles which are used to provide a hipped and polygonal shape roof over the semi-octangle bay, a gable roof over the second story wooden bays at Nos. 5 and 1, a conical shape roof over the semi-cylindrical bay and a dome roof over the three-quarters cylindrical bay. A shingled, shed roof is located between each of the bays on the north facade and along the west facade.

Decorative details

Decorative details include:

1. radiating brick voussoirs accented by vermiculated stone skewbacks,
2. vermiculated stone quoining,
3. limestone string coursing,
4. box cornice,
5. frieze with alternating square and rectangular panels running across the north and west facade,
6. voluted wooden brackets supporting the box cornice,
7. decorative wooden second story bays with gable roofs,
8. decorative pediments over the second story bays,
9. a cupola decorated with wooden engaged urns within an arcade,
10. gabled porch with fan design in pediments,
11. lathe-turned posts and brackets on the main porches,
12. a three-story semi-cylindrical bay on the north facade,
13. a three-story three-quarter cylindrical bay located on the northwest corner of the north facade,

14. a three-story semi-octangle bay at the northeast corner of the north facade,
15. lathe-turned balustrades and balusters on the main porches of Nos. 1,3, and 5 East 34th Street, and
16. wooden finials on pediments over doorways and second story bays.

INTERIOR

Access into the interior was unobtainable.

ALTERATIONS

Alterations to the building include:

1. 1921:
   a. an addition of a wooden garage behind No. 5 East 34th Street,[4]
2. 1922:
   a. an addition of a sleeping porch on the rear facade of No. 7 East 34th Street,[5]
3. 1939-1940:
   a. removal of six row house units along Main Street,[6]
4. date unknown:
   a. removal of wooden bannister, balustrade and balusters from No. 7 East 34th Street,
   b. removal of lathe-turned post and brackets from No. 5 East 34th Street,
   c. removal of lathe-turned balusters from part of porch of No. 5 and all of Nos. 3 and 1 East 34th Street,
   d. removal of wooden finial over the roof of the pediment of No. 5 East 34th Street,
   e. removal of wooden finial over the pediment over the main doorway of No. 5 East 34th Street,
   f. removal of a wooden single run staircase on the main facade providing access to No. 1 East 34th Street,
   g. removal of porch and staircase on main facade of 3401 Main Street,
   h. a metal addition on the first floor of rear of No. 7 East 34th Street,
   i. removal of two chimney stacks on west end of north facade,
   j. an addition of asbestos shingles covering fieldstone foundation on the north facade of No. 7 East 34th Street,
   k. removal of chimney stacks at No. 7 East 34th Street.

CONDITION

The Row House Building is in fair condition.

SITE

The Row House Building is located along East 34th Street and Main Street, and is situated in the Westport District of Kansas City, Missouri. A one-story detached wooden garage with a wooden panel is located behind No. 5 East 34th Street. A north-south alley runs along the east facade of No. 7 East 34th Street. To the north and west of the Row House Building are commercial structures and single and multi-family dwellings; to the south are commercial structures, and to the east are single and multi-family dwellings.

PRESENT STATUS

Presently there is no threat of demolition of the Row House Building. The structure is being renovated by the owner for commercial use.

FOOTNOTES

1. Tax Assessment Form, Office of Recorder of Deeds, Jackson County Courthouse, 415 East 12th Street, Kansas City, Missouri.

2. G.M. Hopkins, C.E., A Complete Set of Surveys and Plats of Properties of Kansas City, Missouri, (Philadelphia, Pa.: G.M. Hopkins, C.E., 1891) p. 42.

3. Tuttle and Pike's Atlas of Kansas City and Vicinity (Kansas City, Mo.: Tuttle and Pike Civil Engineers, 1907), p. 16.

4. Building Permit Number 71434 dated March 15, 1921, Public Works Department, City Hall, 5th Floor West, City Hall, 414 East 12th Street, Kansas City, Missouri 64106.

5. Building Permit Number 75184 dated August 8, 1922, Public Works Department, City Hall, 5th Floor West, City Hall, 414 East 12th Street, Kansas City, Missouri 64106.

6. Building Permit Number 8173A dated December 1, 1939, Public Works Department, City Hall, 5th Floor West, City Hall, 414 East 12th Street, Kansas City, Missouri 64106.

Form No 10-300a
(Rev 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED FEB 21 1978
DATE ENTERED MAY 22 1978

ROW HOUSE BUILDING

FOOTNOTES

1. Marcus Whiffen, American Architecture Since 1780, A Guide to the Styles (Cambridge, Mass.: M.I.T. Press, 1969), p. 115.

2. "Judge C.C. Quinlan is Dead," Kansas City /Missouri/ Star, 22 February 1900, p.2; Structural Kansas City Residential Districts Part III, p. 216, Native Sons Collection, Missouri Valley Room, Kansas City Public Library, Kansas City, Missouri; Mounted Clippings, "Apartments," Missouri Valley Room, Kansas City Public Library, Kansas City, Missouri.

3. Water Permit Number 8345 dated August 15, 1888, and Nos.8552-8558 dated September 26, 1888, and No. 8559 dated November 20, 1888, Water Department, City Hall, 5th Floor West, City Hall, 414 East 12th Street, Kansas City, Missouri 64106.

4. Hoye's City Directory of Kansas City, Missouri, (Kansas City, Missouri: Hoye Directory Company, 1887-88), p. 181.

5. Henry C. Haskell, Jr. and Richard B. Fowler, City of the Future, A Narrative History of Kansas City, 1850-1950 (Kansas City, Missouri: Frank Green Publishing Co. Inc., 1950), p. 77.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED 1978
DATE ENTERED

ROW HOUSE BUILDING

CONTINUATION SHEET ITEM NUMBER 9 PAGE 1

3. Hoye's City Directory of Kansas City, Mo. Kansas City, Mo.: Hoye Directory Co., 1887-88.

4. "Judge C.C. Quinlan is Dead." Kansas City /Missouri/ Star, 22 February 1900.

5. Kansas City, Missouri. Jackson County Court House, 1940 Tax Assessment Grid.

6. Kansas City, Missouri. Kansas City Public Library, Missouri Valley Room. Mounted Clippings and The Native Sons Collection.

7. Kansas City, Missouri. Public Works Department, City Hall. Building Permits.

8. Kansas City, Missouri. Water Department, City Hall. Water Permits.

9. Tuttle and Pike's Atlas of Kansas City and Vicinity. Kansas City, Mo.: Tuttle and Pike Civil Engineers, 1907.

10. Whiffen, Marcus. American Architecture Since 1780 A Guide to the Styles. Cambridge, Mass.: M.I.T. Press, 1969.

Row House Buildings
Kansas City, Missouri
U.S.G.S. 7.5" Quadrangle
Scale: 1:24,000
"Kansas City, Mo."

UTM References:
Bldg.#1 - 15/362860/4325020

Bldg.#2 - 15/362890/4328020



U.S.G.S. 7.5' Quadrangle
"Kansas City,Mo.-Kans." (1970)
Scale: 1:24,000
Row House Building

UTM Reference:

15/362870/4325040

Row House Building #1
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

North facade; view looking southwest.

Row House Building #2
Kansas City, Missouri
photographer: Victoria Karel
1976

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

Detail of the upper northeast corner of the north facade; view looking southeast.

Row House Building #3
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

North facade of No. 7 East 34th Street;
view looking south.

Row House Building #4
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

Detail of porch of No. 5 East 34th Street on the north facade, view looking southeast.

Row House Building #5
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

Southeast corner, view looking northwest; showing south facade and additions on the left and the east facade on the right.

Row House Building #6
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

South facade, showing rear porches
and additions; view looking north.

Row House Building #7
Kansas City, Missouri
photographer: Sherry Piland
August, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

North facade of No. 5 East 34th Street;
view looking south.

7 E. 34 TH. ST.
5

Row House Building #8
Kansas City, Missouri
photographer: Sherry Piland
August, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

Southwest corner, view looking northeast showing portions of the west facade on the left and the south facade on right. Main Street commercial buildings are in the foreground.

ALLIED BUILDING
CONTRACTORS
3407
Barnes
BEAUTY SALON
931-0679

Row House Building #9
Kansas City, Missouri
photographer: Sherry Piland
July, 1977

Kansas City Landmarks Commission
City Hall - 26th Floor East
414 East 12th Street
Kansas City, Missouri 64106

Northwest corner, view looking southeast. View showing north facade on the left and west facade on the right.

MAIN

Row House Buildings
Kansas City, Missouri 1 of 11
Photographer: Sherry Piland
June, 1983

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City Missouri 64106

1-7 East 34th Street (& 3401 Main)
(Building #1)
North Facade of Left; West facade
on Right; View Looking Southeast

AUTO PARTS
3324 MAIN
561-0323
OPEN
24-HRS

Row House Buildings
Kansas City, Missouri 2 of 11
Photographer: Sherry Piland
June 1983

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

1-7 East 34th Street (& 3401 Main)
(Building #1)
North Facade, View looking
southwest

1 HOUR
PARKING
7 AM-6 PM

Row House Buildings
Kansas City Missouri 3 of 11
Photographer: Sherry Piland
June, 1983

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

1-7 East 34th Street (& 3401 Main)
(Building #1)
Detail, North Facade, East end
View Looking South

Row House Buildings
Kansas City, Missouri 4 of 11
Photographer: Sherry Piland
June 1983

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

1-7 East 34th Street (& 3401 Main)
(Building #1)
Detail, North Facade, West end
View looking Southwest

Row House Buildings 5 of 11
Kansas City, Missouri

Photographer: Sherry Piland
October, 1984

Kansas City Landmarks Commission
City Hall, 26th Floor
414 East 12th Street
Kansas City, MO 64106

1-7 East 34th Street
(Building #1)

North facade on left, west facade on right; view looking east.

6987

MAIN
OFFICE SPACE FOR LEA
CALL 756-3439

Row House Buildings
Kansas CIty, Missouri 6 of 11
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
North Facade, View Looking
Southwest

Row House Buildings 7 of 11
Kansas City, Missouri

Photographer: Sherry Piland
September, 1984

Kansas City Landmarks Commission
City Hall, 26th Floor
414 East 12th Street
Kansas City, MO 64106

9-23 East 34th Street
(Building #2)

North facade, view looking southwest.

Row House Buildings
Kansas City, Missouri 8 of 11
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
Detail, North Facade
View Looking Southwest

Row House Buildings
Kansas City Missouri 9 of 11
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
Detail, North Facade
View Looking Southwest

Row House Buildings 10 of 11
Kansas City, Missouri
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
West Facade,
View Looking Southeast

Row House Buildings
Kansas City, Missouri 11 of 11
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
South Facade, View Looking
Northeast

VOLVO
MAK 844

Row House Buildings
Kansas City, Missouri 7 of 11
Photographer; Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
Detail, North Facade;
View Looking southeast

Row House BUildings
Kansas CIty, Missouri 7 of 11
Photographer: Sherry Piland
July 1982

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

9-23 East 34th Street
(Building #2)
Detail, North Facade;
View Looking Southeast

Row House Buildings
Kansas City, Missouri 5 of 11
Photographer: Sherry Piland
June 1983

Kansas City Landmarks Commission
26th Floor, City Hall
414 East 12th Street
Kansas City, Missouri 64106

1-7 East 34th Street (& 3401 Main
(Building #1)
South Facade, View Looking North